

**DELTA HELIX ENERGY LLC
W. M. KAUFMAN W-7
UIC PERMIT APPLICATION
UIC #2D08700985**

12/15/24

CHECKLIST FOR FILING A UIC PERMIT APPLICATION

Please utilize this checklist to ensure you have prepared, completed, and enclosed all required documentation and payment to ensure a timely review of your submittal.

Operator	Delta Helix Energy, LLC		
Existing UIC Permit ID Number	2D08700985-002	UIC Well API Number	4708700985

Office of Oil and Gas Office Use Only	
Permit Reviewer	
Date Received	
Administratively Complete Date	
Approved Date	
Permit Issued	

Please check the fees and payment included.

Fees		Payment Type	
UIC Permit Fee: \$500	☒	Check	☒
Groundwater Protection Plan (GPP) Fee: \$50.00	☐	Electronic	☐
		Other	☐

Please check the items completed and enclosed.

- ☒ Checklist
- ☒ UIC-1
 - ☒ Section 1 – Facility Information
 - ☒ Section 2 – Operator Information
 - ☒ Section 3 – Application Information
 - ☒ Section 4 – Applicant/Activity Request and Type
 - ☒ Section 5 – Brief description of the Nature of the Business
 - ☒ CERTIFICATION
- ☒ Section 6 – Construction
 - ☒ Appendix A Injection Well Form
 - ☒ Appendix B Storage Tank Inventory
- ☒ Section 7 – Area of Review
 - ☒ Appendix C Wells Within the Area of Review

- N/A ☒ Appendix D Public Service District Affidavit
- ☒ Appendix E Water Sources
- ☒ Appendix F Area Permit Wells
- ☒ Section 8 – Geological Data on Injection and Confining Zones
- ☒ Section 9 – Operating Requirements / Data
- ☒ Appendix G Wells Serviced by Injection Well
- ☒ Section 10 – Monitoring
- ☒ Section 11 – Groundwater Protection Plan (GPP)
- ☒ Appendix H Groundwater Protection Plan (GPP)
- ☒ Section 12 – Plugging and Abandonment
- ☒ Section 13 – Additional Bonding
- ☒ Section 14 – Financial Responsibility
- ☒ Appendix I Financial Responsibility
- ☒ Section 15 – Site Security Plan
- ☒ Appendix J Site Security for Commercial Wells
- ☒ Section 16 – Additional Information
- ☒ Appendix K Other Permit Approvals

****NOTE: For all 2D wells an additional bond in the amount of \$5,000 is required.***

Reviewed by (Print Name): Brad Morris

Reviewed by (Sign): 

Date Reviewed: 5/28/25

Section 1 – 5

UIC-1 Form

4708700985



WEST VIRGINIA DEPARTMENT OF
ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS
601 57th Street, SE
Charleston, WV 25304
(304) 926-0450
www.dep.wv.gov/oil-and-gas

UNDERGROUND INJECTION CONTROL
(UIC)
PERMIT APPLICATION

UIC PERMIT ID # 2D08700985002 API # 4708700985 WELL # Kaufman W-7

Section 1. Facility Information

Facility Name: Kaufman W-7 Disposal

Address: 1.25 miles East on Kaufman Road (CR 48/3) off of Otto Road (CR 48)

City: Spencer State: WV Zip: 25276

County: Roane District: Smithfield 7.5' Quad: Spencer

Location description:

1.25 miles East on Kaufman Road (CR 48/3) off of Otto Road (CR 48) on the waters of Millstone Run

Location of well(s) or approximate center of field/project in UTM NAD 83 (meters) Latitude: 38.756034
Northing: 4289738 Easting: 476780 Longitude: -81.267241

Environmental Contact Information:

Name: Brad Morris
Phone: 681-229-1558

Title: Office Manager
Email: bmorris@topdrilling.com

Section 2. Operator Information

Operator Name: Delta Helix Energy, LLC
Operator ID: 494530855

Address: 300 Star Avenue, Suite 321

City: Parkersburg State: WV Zip: 26101

County: Roane

Contact Name: Brian Haught
Contact Phone: 681-229-1558

Contact Title: Operator Manager
Contact Email: bhaught@topdrilling.com

4708700985

Section 3. Applicant Information

Ownership Status: ☒ PRIVATE ☐ PUBLIC ☐ FEDERAL ☐ STATE
☐ OTHER (explain):

SIC code: ☒ 1311 (2D, 2H, 2R) ☐ 1479 (3S) ☐ OTHER (explain):

Section 4. Applicant / Activity Request and Type:

- A. Apply for a new UIC Permit: ☐ 2D ☐ 2H ☐ 2R ☐ 3S
B. Reissue existing UIC Permit: ☒ 2D ☐ 2H ☐ 2R ☐ 3S
C. Modify existing UIC Permit: ☐ 2D ☐ 2H ☐ 2R ☐ 3S
(Submit only documentation pertaining to the modification request)
2D COMMERCIAL FACILITY: ☐ YES ☐ NO

Section 5. Briefly describe the nature of business and the activities to be conducted:

Oil & Natural Gas production. Water Produced from approximately 75 shallow wells is injected into the Big Injun Sand.

APPLICATION CERTIFICATION

In accordance with WV Code 47CSR13.13.11, all UIC permit applications must be signed by one of the following:

1. For a corporation: by a principle corporate officer of at least the level of vice-president;
2. For a partnership or sole proprietorship: by a general partner or the proprietor, respectively;
3. For a municipality, State, Federal, or other public agency: by either a principle executive officer or ranking elected official;
4. Or a duly authorized representative in accordance with 47CSR13.13.11.b.
(A person may be duly authorized by one of the primary entities (1-3) listed above by submitting a written authorization to the Chief of the WVDEP Office of Oil and Gas designating an individual or a position having responsibility for the overall operation of the regulated facility or activity, such as the position of plant manager, operator of a well or a well field, superintendent, or position of equivalent responsibility. A duly authorized representative may thus be either a named individual or any individual occupying a named position.)

Delta Helix Energy, LLC

(Company Name)

2D08700985-002 (Kaufman W-7)

(UIC Permit Number)

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

(47CSR13.13.11.d)

B. Douglas Haught

(Print Name)

CEO

(Print Title)

(Signature)

5-28-25

(Date)

Section 6

Construction

Section No. 6

6. The water produced in conjunction with crude oil from the William Kaufman lease is separated from the oil and gathered in a 100 bbl storage tank near the location of Kaufman W- 17. This water along with the water produced from nearby Clover Field Big Injun wells is filtered and injected into Kaufman W- 7. A Schematic of the production facility is shown in the attached Fig No. 1. The attached Fig No. 2 shows the location of the tanks, injection facility, and injection line to W M Kaufman W-7 and W M Kaufman W-19. Figure No. 3 (attached) shows the oil lines and oil and water stock tank locations. The ¼ mile AOR is shown on both Fig Nos 2 and 3. There are no USDWs located within the AOR. Two USDWs located approximately 1000' and 2200' from the AOR were sampled.
7. The attached Fig No. 4 is a schematic of the as drilled injection well, W M Kaufman W-7 with Big Injun (injection zone), Big lime and shale (confining layers) marked. Tubing and casing depths along with cement info (TOC) is also shown on the schematic.
8. See Appendices A& B.
9. This disposal well was drilled in 1963 and logged with Gamma Ray / Density/ Caliper logs. A copy of the United States Department of the Interior Report No. 6992 (Reservoir Study of the William Kaufman Clover-Rush Run Oilfield, Roane County, WV by Karl-Heinz Frohne) is enclosed in Fig No. 5. This study provides a detailed study of the reservoir based on a core from W M Kaufman No. 7 located approximately 1300' South of Kaufman W-7. Reservoir properties as determined from that study are:

Gross Sand thickness: 24'

Pay thickness: 12.5'

Permeability: .8 md

Porosity: 15%

Connate water saturation: 65%

Kaufman W-7 was completed with a small fracture treatment soon after drilling. Both the Breakdown Pressure and Instantaneous Shut In Pressure were recorded at 1300 psig (surface).

The attached Fig No. 6 is a copy of the McCullough Scintillometer/ Gamma Ray long run at the time the well was drilled. The tops of the relevant formations are marked on this log.

APPENDIX A

Injection Well Form

1) GEOLOGIC TARGET FORMATION		Big Injun Sandstone	
Depth	2150	Feet (top)	2188
		Feet (bottom)	
2) Estimated Depth of Completed Well, (or actual depth of existing well):		2219	Feet
3) Approximate water strata depths:		Fresh	N/A
		Feet	
		Salt	N/A
		Feet	
4) Approximate coal seam depths:		None	
5) Is coal being mined in the area?		Yes	☐
		No	☒
6) Virgin reservoir pressure in target formation		960	psig
	Source	Estimated	
7) Estimated reservoir fracture pressure		2164 per step rate test (1987)	
		psig (BHFP)	
8) MAXIMUM PROPOSED INJECTION OPERATIONS:			
Injection rate (bbl/hour)	12		
Injection volume (bbl/day)	50		
Injection pressure (psig)	883		
Bottom hole pressure (psig)	1943		
9) DETAILED IDENTIFICATION OF MATERIALS TO BE INJECTED, INCLUDING ADDITIVES:			
Produced Big Injun brine			
Temperature of injected fluid: (°F)		60	
10) FILTERS (IF ANY)			
10 micron at the well and at injection plant			
11) SPECIFICATIONS FOR CATHODIC PROTECTION AND OTHER CORROSION CONTROL			
Corrosion inhibitor in annular fluid			

APPENDIX A (cont.)12. Casing and Tubing Program

TYPE	<u>Size</u>	<u>New or Used</u>	<u>Grade</u>	<u>Weight per ft. (lb/ft)</u>	<u>FOOTAGE: For Drilling</u>	<u>INTERVALS: Left in Well</u>	<u>CEMENT: Fill-up (Cu. Ft.)</u>
Conductor							
Fresh Water	8 5/8	New	LS	28#	172	172	30 sks CTS
Coal							
Intermediate 1							
Intermediate 2							
Production	4 1/2	New	J-55	9.5#	2219	2219	53 sks
Tubing	2 3/8	New	J-55	4.6#	2130	2130	
Liners							

TYPE	<u>Wellbore Diameter</u>	<u>Casing Size</u>	<u>Wall Thickness</u>	<u>Burst Pressure</u>	<u>Cement Type</u>	<u>Cement Yield (cu. ft./sk)</u>	<u>Cement to Surface ? (Y or N)</u>
Conductor							
Fresh Water	10 5/8	8 5/8	.264	2950	Reg. Neat	1.18	Y
Coal							
Intermediate 1							
Intermediate 2							
Production	7 7/8	4 1/2"	.205	4380	50/50 Poz	1.26	N
Tubing		2 3/8	.167	6770	NA	NA	N
Liners							

PACKERS	Packer #1	Packer #2	Packer #3	Packer #4
Kind:	tension			
Sizes:	4 x 2			
Depths Set:	2130			


Well Bore Diagram

W.M. Kaufman W-7

API 47-087-00985

Delta Helix Energy, LLC


UIC 2D08700985-003



4708700985

W M Kaufman W-7
47-087-00985

FIG No. 4



8 5/8" csng set @ 174'- CTS

est TOC = 1933'
1975'-2130'

Big Lime

2130'
2163'-2166'
2170'-2219'
TD 2219

2 3/8" tubing on tension packer
Big Injun perforations
Shale
4 1/2" csng @ 2219'

5/24/2018

Not to scale



4708700985

GEORGE H. HAYES, JR. (WV) VAGUE

W-7

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

December 33 1967

Quadrangle SPENCER

Permit No. ROA-985

WELL RECORD

Oil or Gas Well

(KIND)

Company WOLF'S HEAD OIL REFINING COMPANY, INC.

Address P. O. Box 1588, Parkersburg, W. Va.

Farm Wm. Kaufman Acres 800

Location (waters) Slab Camp Run

Well No. W-7 Elev. 1003.40

District Smithfield County Roane

The surface of tract is owned in fee by Harold Rhodes

Otto Route Address Spencer, W. Va.

Mineral rights are owned by Alfred M. Oppenheimer II,

300 South Lang Avenue Address Pittsburgh 8, Pa.

Drilling commenced November 20, 1963

Drilling completed November 27, 1963

Date Shot - - From - - To - -

With - -

Open Flow /10ths Water in - - Inch

/10ths Merc. in - - Inch

Volume Show Oil & Gas (Drilled w/Rotary) Cu. Ft.

Rock Pressure - - lbs. - - hrs.

Oil - - bbls., 1st 24 hrs.

WELL ACIDIZED - -

WELL FRACTURED December 12, 1963

RESULT AFTER TREATMENT Gas - 42,000 Cu. Ft.

ROCK PRESSURE AFTER TREATMENT Oil - 33 Bbls.

Fresh Water - - Feet

Salt Water - - Feet

508 Lbs.

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			Steel Shoe
10			Float Collar
8 5/8"	174' 2"	174' 2"	Guide Shoe
6 3/4"			Size of OD
4 1/2" OD	2230' 7"	2230' 7"	4 1/2" OD
3			Depth set
2 3/8" Tbg.	2230'	2230'	2188
Liners Used			Perf. top
			Perf. bottom
			Perf. top
			Perf. bottom

CASING CEMENTED 8 5/8" SIZE 172 No. Ft. 11/21/63 Date 4 1/2" 2219 11/29/63

COAL WAS ENCOUNTERED AT - FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES


FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES



(over)

Formation	Color	Hard or Soft	Top 7'	Bottom	Oil, Gas or Water	Depth Found	Remarks
Little Lime			1955	1970			
Sandy Shale			1970	1975			
Big Lime			1975	2130			
Keener Sand			2130	2141			
Big Injun			2141	2170			
Shale			2170	2219	Oil & Gas	2141-2170	Show
4 1/2" Casing			2219	2219			
TOTAL DEPTH			2219	2219			
			1000	1020			
			1030	1050			
			1060	1080			
			1090	1110			
			1120	1140			
			1150	1170			
			1180	1200			
			1210	1230			
			1240	1260			
			1270	1290			
			1300	1320			
			1330	1350			
			1360	1380			
			1390	1410			
			1420	1440			
			1450	1470			
			1480	1500			
			1510	1530			
			1540	1560			
			1570	1590			
			1600	1620			
			1630	1650			
			1660	1680			
			1690	1710			
			1720	1740			
			1750	1770			
			1780	1800			
			1810	1830			
			1840	1860			
			1870	1890			
			1900	1920			
			1930	1950			
			1960	1980			
			1990	2010			
			2020	2040			
			2050	2070			
			2080	2100			
			2110	2130			
			2140	2160			
			2170	2190			
			2200	2220			
			2210	2230			
			2220	2240			
			2230	2250			
			2240	2260			
			2250	2270			
			2260	2280			
			2270	2290			
			2280	2300			
			2290	2310			
			2300	2320			
			2310	2330			
			2320	2340			
			2330	2350			
			2340	2360			
			2350	2370			
			2360	2380			
			2370	2390			
			2380	2400			
			2390	2410			
			2400	2420			
			2410	2430			
			2420	2440			
			2430	2450			
			2440	2460			
			2450	2470			
			2460	2480			
			2470	2490			
			2480	2500			
			2490	2510			
			2500	2520			
			2510	2530			
			2520	2540			
			2530	2550			
			2540	2560			
			2550	2570			
			2560	2580			
			2570	2590			
			2580	2600			
			2590	2610			
			2600	2620			
			2610	2630			
			2620	2640			
			2630	2650			
			2640	2660			
			2650	2670			
			2660	2680			
			2670	2690			
			2680	2700			
			2690	2710			
			2700	2720			
			2710	2730			
			2720	2740			
			2730	2750			
			2740	2760			
			2750	2770			
			2760	2780			
			2770	2790			
			2780	2800			
			2790	2810			
			2800	2820			
			2810	2830			
			2820	2840			
			2830	2850			
			2840	2860			
			2850	2870			
			2860	2880			
			2870	2890			
			2880	2900			
			2890	2910			
			2900	2920			
			2910	2930			
			2920	2940			
			2930	2950			
			2940	2960			
			2950	2970			
			2960	2980			
			2970	2990			
			2980	3000			
			2990	3010			
			3000	3020			
			3010	3030			
			3020	3040			
			3030	3050			
			3040	3060			
			3050	3070			
			3060	3080			
			3070	3090			
			3080	3100			
			3090	3110			
			3100	3120			
			3110	3130			
			3120	3140			
			3130	3150			
			3140	3160			
			3150	3170			
			3160	3180			
			3170	3190			
			3180	3200			
			3190	3210			
			3200	3220			
			3210	3230			
			3220	3240			
			3230	3250			
			3240	3260			
			3250	3270			
			3260	3280			
			3270	3290			
			3280	3300			
			3290	3310			
			3300	3320			
			3310	3330			
			3320	3340			
			3330	3350			
			3340	3360			
			3350	3370			
			3360	3380			
			3370	3390			
			3380	3400			
			3390	3410			
			3400	3420			
			3410	3430			
			3420	3440			
			3430	3450			
			3440	3460			
			3450	3470			
			3460	3480			
			3470	3490			
			3480	3500			
			3490	3510			
			3500	3520			
			3510	3530			
			3520	3540			
			3530	3550			
			3540	3560			
			3550	3570			
			3560	3580			
			3570	3590			
			3580	3600			
			3590	3610			
			3600	3620			
			3610	3630			
			3620	3640			
			3630	3650			
			3640	3660			
			3650	3670			
			3660	3680			
			3670	3690			
			3680	3700			
			3690	3710			
			3700	3720			
			3710	3730			
			3720	3740			
			3730	3750			
			3740	3760			
			3750	3770			
			3760	3780			
			3770	3790			
			3780	3800			
			3790	3810			
			3800	3820			
			3810	3830			
			3820	3840			
			3830	3850			
			3840	3860			
			3850	3870			
			3860	3880			
			3870	3890			
			3880	3900			
			3890	3910			
			3900	3920			
			3910	3930			
			3920	3940			
			3930	3950			
			3940	3960			
			3950	3970			
			3960	3980			
			3970	3990			
			3980	4000			
			3990	4010			
			4000	4020			
			4010	4030			
			4020	4040			
			4030	4050			
			4040	4060			
			4050	4070			
			4060	4080			
			4070	4090			
			4080	4100			
			4090	4110			
			4100	4120			
			4110	4130			
			4120	4140			
			4130	4150			
			4140	4160			
			4150	4170			
			4160	4180			
			4170	4190			
			4180	4200			
			4190	4210			
			4200	4220			
			4210	4230			
			4220	4240			
			4230	4250			
			4240	4260			
			4250	4270			
			4260	4280			
			4270	4290			
			4280	4300			
			4290	4310			
			4300	4320			
			4310	4330			
			4320	4340			
			4330	4350			
			4340	4360			
			4350	4370			
			4360	4380			
			4370	4390			
			4380	4400	</		

Date December 23, 1963

APPROVED WOLF'S HEAD OIL REFINING COMPANY, INC. Owner

By George W. Wiseman
George W. Wiseman, (Title) Agent



Select County: (087) Roane ☐ (Check All)

Enter Permit #: 985

Get Data Reset

☒ Location ☒ Production ☒ Plugging
☒ Owner/Completion ☒ Stratigraphy ☒ Sample
☒ Pay/Show/Water ☒ Logs ☒ Btm Hole Loc

[Table Descriptions](#)
[County Code Translations](#)
[Permit-Numbering Series](#)
[Usage Notes](#)
[Contact Information](#)
[Disclaimer](#)
[WVGES Main](#)
["Pipeline-Plus" New](#)

W-7

WV Geological & Economic Survey:

Well: County = 087 Permit = 985 [Link to all digital records for well](#)

Report Time: Thursday, April 03, 2025 1:09:14 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX_DISTRICT	QUAD_75	QUAD_15	LAT_DD	LON_DD	UTME	UTMN
4708700985	Roane	985	Smithfield	Spencer	Spencer	38.755755	-81.267503	476757	4289707

There is no Bottom Hole Location data for this well

Owner Information:

API	CMP_DT	SUFFIX	STATUS	SURFACE_OWNER	WELL_NUM	CO_NUM	LEASE	LEASE_NUM	MINERAL_OWN	OPERATOR_AT_COMPLETION	PROP_VD	PROP_TRGT_FM
4708700985	11/27/1963	Original Loc	Completed	Harold Rhodes	W-7		William Kaufman	81219	Alfred M Oppenheimer II et al	Wolf's Head Oil Refining Co., Inc.		
4708700985	--	Worked Over	Completed	Terry A Samples	W-7		W M Kaufman			Pennzoil Company		Big Injun (Price&eq)

Completion Information:

API	CMP_DT	SPUD_DT	ELEV	DATUM	FIELD	DEEPEST_FM	DEEPEST_FMT	INITIAL_CLASS	FINAL_CLASS	TYPE	RIG	CMP_MTHD	TVD	TMD	NEW_FTG	KOD	G_E
4708700985	11/27/1963	11/20/1963	1003	Ground Level	Civr-Rsh Rn	Price Fm & equivs	Price Fm & equivs	Development Well	Development Well	Oil and Gas	unknown	Fractured	2219		2219		
4708700985	--	--	1003	Ground Level	Civr-Rsh Rn	Price Fm & equivs	Big Injun (Price&eq)	Service Well	Unsuccessful	Salt Water Disp	unknown	unknown	2219				0

Comment: -- Injection zone footage proposed.

Pay/Show/Water Information:

API	CMP_DT	ACTIVITY	PRODUCT	SECTION	DEPTH_TOP	FM_TOP	DEPTH_BOT	FM_BOT	G_BEf	G_AfT	O_BEf	O_AfT	WATER_QNTY
4708700985	--	Horizon	Injection	Vertical	2163	Big Injun (Price&eq)	2166	Big Injun (Price&eq)					
4708700985	11/27/1963	Pay	Oil & Gas	Vertical			2170	Big Injun (Price&eq)	0		0		

Production Gas Information: (Volumes in Mcf)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_GAS	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700985	Pennzoil Company	1981	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	Pennzoil Company	1982	999	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	Pennzoil Company	1983	1,492	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	Pennzoil Company	1984	1,470	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Production Oil Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_OIL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700985	Pennzoil Company	1981	440	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	Pennzoil Company	1982	307	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	Pennzoil Company	1983	445	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	Pennzoil Company	1984	382	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Production NGL Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_NGL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700985	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Production Water Information: (Volumes in Gallons)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_WTR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700985	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Stratigraphy Information:

API	SUFFIX	FM	FM_QUALITY	DEPTH_TOP	DEPTH_QUALITY	THICKNESS	THICKNESS_QUALITY	ELEV	DATUM
4708700985	Original Loc	Little Lime	Well Record	1955	Reasonable	15	Reasonable	1003	Ground Level
4708700985	Original Loc	Big Lime	Well Record	1975	Reasonable	155	Reasonable	1003	Ground Level
4708700985	Original Loc	Greenbrier Group	Past WVGES Staff Geologist	1975	Reasonable	155	Reasonable	1003	Ground Level
4708700985	Original Loc	Big Injun (Price&eq)	Past WVGES Staff Geologist	2130	Reasonable	11	Reasonable	1003	Ground Level
4708700985	Original Loc	Keener	Well Record	2130	Reasonable	11	Reasonable	1003	Ground Level

Wireline (E-Log) Information:

* There is no Scanned/Raster Log data for this well

* There is no Digitized/LAS Log data for this well

* There is no Scanned or Digital Logs available for download

There is no Plugging data for this well

There is no Sample data for this well


Section 7

Area of Review

Section No. 7

9. A ¼ mile fixed radius from the injection well, W M Kaufman W-7, was utilized for the AOR investigation.
10. Attached in Fig No 3 is a map showing the wells within the AOR. The wells within the AOR are listed in the attached APPENDIX C. The Well Records available are also enclosed in Fig No. 7. The attached Fig No 8 is a topographic map extending a mile from the Kaufman W-7 injection well. The maps show the facilities and injection, producing, plugged and abandoned wells within the one mile radius.
11. The Local PSD (Clover PSD) was contacted and the required Affidavit obtained. It is enclosed in APPENDIX D.
12. The USDWs in this area vary from approximately 20' to 100'. No USDWs are located within the AOR. Two USDWs located outside the AOR boundary were sampled. The results of the analysis are shown in the attached APPENDIX E. TDS was measured as part of the analysis. Most of the USDWs in this field were drilled prior to the current owner and they know very little about the wells. The results of the analysis are shown in APPENDIX E.
13. The samples were collected by a WVDEP certified laboratory as set forth in 40CFR Part 136.
14. No corrective action is deemed necessary at this time.
15. This application is for a single disposal well and not an area permit.
16. Groundwater use in this area of Roane County is limited. Located approximately 3 miles from this injection well is the Charles Fork Lake. This lake is utilized as a water source for the City of Spencer as well as recreational activities. It is located on a different drainage than W M Kaufman W-7. Other than the water supply for the City of Spencer the only other know Ground Water uses are agricultural.

4708700985




Scale 1" = 2000'

Wm Kaufman W-19
Section 7 AOR

Fig No 8

Injection Line

4708700985



- CLOVER FIELD -
Injection Wells

Wm. Kaufman No.W-7 (47-087-00985)

ROANE CO., WV

**Map Showing All Known Wells
Within the Quarter-Mile AOR
& WVGES Well Data Spots**

1/29/2018


RECEIVED
Office of Oil and Gas
1 2019

JUL 11 2019

U.S. Department of
Environmental Protection



- LEGEND**
- 1148
2 - Surveyed Well or HG Energy Map Location
 - 4708730043
- Well Location from WVGES Well Database
 - 1148
2 - Surveyed Well - Class I
 - 1148
2 - Denotes a Water Source Tested Jan. 2018



- CLOVER FIELD -
Injection Wells
Wm. Kaufman No. W-7 (47-087-00985)
Injection + pipeline facilities

ROANE CO., WV

Map Showing All Known Wells
Within the Quarter-Mile AOR
& WVGES Well Data Spots

Fig No 2

UIC Permit No.


Storage Tank Inventory

[illegible]

4708700985

Fig No 1

FACILITY SITE PLAN



Facility Name: Kaufman, Wm. W-5, W-6, W-8, W-12, W-13, W-17, W-18, W-20, W-21, 5, 605 & 606

State: WV

County: Roane

District: Smithfield

Name of Nearest Stream: Millstone Run

Direction & Distance from Facility: 185° @ 300'

~STORAGE TANKS~

No. 3

Volume bbl: 210

Tank #'s: 321-323

Dike Dimensions: 150' peri. X 2.2' depth

Calculated Capacity: 471 bbl



HG ENERGY, LLC
SPCC PLAN


Drawn By: KAB
File Name: Clover Area
Scale: _____
Date: 11-6-14
Print No.: _____

Operator: Delta Helix Energy, LLC
 UIC Permit No.: 2D08700985

Secondary Containment Calculations
Earth Berm Containment
 (Input Measurements In Blue Cells)

Tank	Tank Dimensions		Capacity		
	Height (Ft)	Dia (Ft)	Barrels	Gallons	Cu Ft
1	15	10	209.8	8812.8	1178.1
2	15	10	209.8	8812.8	1178.1
3	10	8.5	101.1	4244.8	567.4
4			0.0	0.0	0.0
5			0.0	0.0	0.0
6			0.0	0.0	0.0
7			0.0	0.0	0.0
8			0.0	0.0	0.0
9			0.0	0.0	0.0
10			0.0	0.0	0.0
Total			520.7	21,870.4	2,923.6
Enter largest tank as Tank 1.					

Tank	Tank Base Exclusions		
	Dia (Ft)	Depth (Ft)	Vol (CuFt)
1	0	2.50	0.0
2	10	2.50	196.3
3	8.5	2.50	141.9
4	0	2.50	0.0
5	0	2.50	0.0
6	0	2.50	0.0
7	0	2.50	0.0
8	0	2.50	0.0
9	0	2.50	0.0
10	0	2.50	0.0
Total Tank Base Exclusions			338.2
Tank 1 entered as "0" diameter to exclude it from the tank base exclusion calculations.			



Containment Dimensions	
Top Interior Perimeter	
Length (Ft)	Width (Ft)
65.00	20.00
Bottom Interior Perimeter	
Length (Ft)	Width (Ft)
57.00	12.00
Depth (Ft)	
2.50	
Total Containment Volume (CuFt)	2439.1
All containment measurements must be interior dimensions.	

Tank Containment Volume (CuFt)	2439.1
Minus Tank Base Exclusions (CuFt)	338.2
Net Containment Volume (CuFt)	2100.9
Largest Tank Volume (CuFt)	1178.1
Available Containment Volume (CuFt)	178.3%

4708700985

APPENDIX C
Wells within the Area of Review

	API No.	Well No.	Well Type	Well Status	Northing	Easting	Penetrate Injection Zone	Penetrate Confining Zone	Total Vertical Depth	Surface Elevation
1	4708700878	Wines 1	Oil Prod	Active	4289856.6	476352.3	Y	Y	2273	1076
2	4708700894	Kaufman 5	Oil Prod	Active	4289879.0	476728.0	Y	Y	2281	1109
3	4708700954	Wines 3	Gas Prod	Active	4290082.6	476637.5	Y	Y	2180	1092
4	4708700984	W-5	Oil Prod	Active	4299499.9	476642.1	Y	Y	2270	1040
5	4708700985	W-7	Injector	Active	4289738.0	476780.0	Y	Y	2219	1003
6	4708700987	W-6	Gas Prod	Active	4289588.2	476357.8	Y	Y	2335	1132
7	4708700988	W-8	Oil Prod	Active	4289673.2	477190.2	Y	Y	2430	1225
8	4708701053	W-17	Oil Prod	Active	4289888.7	477092.4	Y	Y	2190	971
9	4708730190	?	Plugged	Abandoned	4289635.7	476521.2	Y	Y	2245	1052
10	4708770398	?	Unknown	Abandoned	4289564.9	476487.5	?	?	?	?
11	4708791143	?	Unknown	Abandoned	4289549.2	476326.3	?	?	?	?
12	4708791144	?	Unknown	Abandoned	4289645.6	476423.3	?	?	?	?
13	4708791145	?	Unknown	Abandoned	4289758.0	476520.2	?	?	?	?

See Completion Logs Attached Below

(4/25)

APPENDIX D

Public Service District Affidavit

Underground Injection Control Permit applicants must identify all publically recorded drinking water sources within a one (1) mile radius of the proposed injection well facility. If no drinking water sources are present within this radius a written affidavit shall be supplied by the local Public Service District (PSD) as ample verification.

"I certify under penalty of law that (state name of business)

Top Drilling / Delta Helix

has verified with the public service district (state name of PSD)

Clover Public Service District

that there are no such publically recorded sources.

Alison Spaur


(Signature of Authorized Representative)

Sworn and subscribed to before me this 15th day of October, 2024.

Ella D. Cottrell, my commission expires Dec. 7th 2025.

(Notary Signature)

Ella D. Cottrell



4708700985

APPENDIX E

Water Sources


Operator: Delta Helix Energy

Year: 2024

UIC Permit: 2D08700985

		Source # 1	Source# 2
Water Source Name		Joseph Lung	James Warden
Norhting		4,289,922.12	4,290,238.23
Easting		477,868.12	477,263.23
Parameter	Units		
Chloride	mg/L	4.9	5.8
Bromide	mg/L	0.10	0.10
Strontium	mg/L	0.093	0.054
Barium	mg/L	0.051	0.14
Iron	mg/L	0.050	0.76
Total Dissolved Solids	mg/L	254	210
pH	SI Units	8.57	6.93
Manganese	mg/L	0.0081	0.10
Aluminum	mg/L	0.020	0.020
Arsenic	mg/L	0.020	0.020
Sodium	mg/L	101	66.3
Calcium	mg/L	2.4	8.5
Sulfate	mg/L	5.0	5.1
MABAS	mg/L	ND	ND

DOMESTIC WATER ANALYSES



0 1,000 2,000 4,000 Feet



Wm Kaufman W-7
Section 7 AOR
Clover Injection System
Roane County, WV

Fig No 8



TABLE 1A. Chemical water quality for stations (KJL) and (KJW) associated with HG Energy's Kaufman Sites. Kirk Environmental, LLP., October 31, 2024.

PARAMETER	SAMPLING STATION	
	KJL	KJW
Field Water Temperature (°C)	16.4	18.0
Field Dissolved Oxygen (mg/L)	7.08	3.64
Field pH (SI Units)	8.57	6.93
Field Conductivity (µS)	561.1	434.0
Aluminum (mg/L)	< 0.020	< 0.020
Arsenic (mg/L)	< 0.020	< 0.020
Barium (mg/L)	0.051	0.14
Calcium (mg/L)	2.4	8.5
Total Iron (mg/L)	< 0.050	0.76
Manganese (mg/L)	0.0081	0.10
Sodium (mg/L)	101	66.3
Strontium (mg/L)	0.093	0.054
TDS (mg/L)	254	210
Bromide (mg/L)	< 0.10	< 0.10
Chloride (mg/L)	4.9	5.8
Sulfate (mg/L)	< 5.0	5.1

KJL = Joseph Lung OSDW

KJW = James Warden USDW

**Laboratory Report**

ED KIRK
KIRK ENVIRONMENTAL,LLP
PO BOX 1783
Beaver, WV 25813

Report Date: 11/26/2024
Date Received: 10/31/2024

Project: KAUFMAN SITES
Pace Project No.: 30730511

Sample: KJL		Lab ID: 30730511001	Collected: 10/31/24 11:55	Matrix: Water			
Method	Parameters	Results	Units	Report Limit	Analyzed	Qualifiers	
EPA 200.7	Aluminum	ND	mg/L	0.020	11/04/24 17:08		
EPA 200.7	Arsenic	ND	mg/L	0.020	11/04/24 17:08		
EPA 200.7	Barium	0.051	mg/L	0.0050	11/04/24 17:08		
EPA 200.7	Calcium	2.4	mg/L	0.50	11/04/24 17:08		
EPA 200.7	Iron	ND	mg/L	0.050	11/04/24 17:08		
EPA 200.7	Manganese	0.0081	mg/L	0.0050	11/04/24 17:08		
EPA 200.7	Sodium	101	mg/L	0.50	11/04/24 17:08		
EPA 200.7	Strontium	0.093	mg/L	0.010	11/04/24 17:08		
SM 2540C-2015	Total Dissolved Solids	254	mg/L	10.0	11/01/24 18:20		
EPA 300.0, Rev 2.1	Bromide	ND	mg/L	0.10	11/20/24 21:28		
EPA 300.0, Rev 2.1	Chloride	4.9	mg/L	1.0	11/20/24 21:28		
EPA 300.0, Rev 2.1	Sulfate	ND	mg/L	5.0	11/20/24 21:28		
	Collected By	EK			11/01/24 09:53		
	Field pH	8.57	Std. Units		11/01/24 09:53		
	Field Temperature, C	16.4	deg C		11/01/24 09:53		
	Field Specific Conductance	561.1	umhos/cm		11/01/24 09:53		
	Oxygen, Dissolved	7.08	mg/L		11/01/24 09:53		

Sample: KJW		Lab ID: 30730511002	Collected: 10/31/24 12:45	Matrix: Water			
Method	Parameters	Results	Units	Report Limit	Analyzed	Qualifiers	
EPA 200.7	Aluminum	ND	mg/L	0.020	11/04/24 17:10		
EPA 200.7	Arsenic	ND	mg/L	0.020	11/04/24 17:10		
EPA 200.7	Barium	0.14	mg/L	0.0050	11/04/24 17:10		
EPA 200.7	Calcium	8.5	mg/L	0.50	11/04/24 17:10		
EPA 200.7	Iron	0.76	mg/L	0.050	11/04/24 17:10		
EPA 200.7	Manganese	0.10	mg/L	0.0050	11/04/24 17:10		
EPA 200.7	Sodium	66.3	mg/L	0.50	11/04/24 17:10		
EPA 200.7	Strontium	0.054	mg/L	0.010	11/04/24 17:10		
SM 2540C-2015	Total Dissolved Solids	210	mg/L	10.0	11/01/24 18:20		
EPA 300.0, Rev 2.1	Bromide	ND	mg/L	0.10	11/20/24 21:48		
EPA 300.0, Rev 2.1	Chloride	5.8	mg/L	1.0	11/20/24 21:48		
EPA 300.0, Rev 2.1	Sulfate	5.1	mg/L	5.0	11/20/24 21:48		
	Collected By	EK			11/01/24 09:56		
	Field pH	6.93	Std. Units		11/01/24 09:56		
	Field Temperature, C	18.0	deg C		11/01/24 09:56		
	Field Specific Conductance	434.0	umhos/cm		11/01/24 09:56		
	Oxygen, Dissolved	3.64	mg/L		11/01/24 09:56		

Sample: KPW		Lab ID: 30730511003	Collected: 10/31/24 10:50	Matrix: Water			
Method	Parameters	Results	Units	Report Limit	Analyzed	Qualifiers	
EPA 200.7	Aluminum	0.29	mg/L	0.20	11/05/24 13:38		



Laboratory Report

ED KIRK
KIRK ENVIRONMENTAL,LLP
PO BOX 1783
Beaver, WV 25813

Report Date: 12/18/2024
Date Received: 12/13/2024

Project: KAUFMAN HOMES
Pace Project No.: 30742291

Sample: KAUFMAN JI LUNG		Lab ID: 30742291001	Collected: 12/13/24 10:20	Matrix: Water			
Method	Parameters	Results	Units	Report Limit	Analyzed	Qualifiers	
SM5540C-2011	LAS Molecular Weight, g/mol	340			12/17/24 12:28	H1,H2	
SM5540C-2011	MBAS, Calculated as LAS	ND	mg/L	0.10	12/17/24 12:28	H1,H2,M1,R1	
Sample: KAUFMAN JI WODEN		Lab ID: 30742291002	Collected: 12/13/24 10:30	Matrix: Water			
Method	Parameters	Results	Units	Report Limit	Analyzed	Qualifiers	
SM5540C-2011	MBAS, Calculated as LAS	ND	mg/L	0.10	12/17/24 12:28	H1,H2	
SM5540C-2011	LAS Molecular Weight, g/mol	340			12/17/24 12:28	H1,H2	

ANALYTE QUALIFIERS

- H1 Analysis conducted outside the EPA method holding time.
- H2 Extraction or preparation conducted outside EPA method holding time.
- M1 Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.
- R1 RPD value was outside control limits.

Reviewed by:

Beth Johnson
(800)999-0105
beth.johnson@pacelabs.com

Pace Analytical Services Beaver
225 Industrial Park Road, Beaver, WV 25813
Virginia VELAP 460148
West Virginia DEP 060
West Virginia DHHR 00412CM

North Carolina DEQ 466
Kentucky Wastewater Certification KY90039
Pennsylvania DEP 68-00839

Notes

Profile #

Client

Sample Line Item	Matrix	AG1H	AG1U	AG2S	AG3S	AG4U	BP1N	BP1U	BP1Z	BP2N	BP2S	BP2U	BP3B	BP3N	BP3S	BP3U	BP4N	BP4O	CG3H	WGPU	WGFU	CG1U	AG74	DG9H	DG9S	DG9U	VG9A	VG9B	VG9H	VG9U	GN	SP5T	ZPLC		
1								—																											
2																																			
3																																			
4																																			
5																																			
6																																			
7																																			
8																																			
9																																			
10																																			
11																																			
12																																			

Glass		Plastic		Misc.	
DG9H	40mL HCl amber vial	GBOD	300mL BOD Glass Stopper	BP1N	1L HNO ₃ plastic
DG9M	40mL MeOH clear vial	WGKU	8oz clear soil jar	BP1S	1L H ₂ SO ₄ plastic
DG9P	40mL TSP amber vial	WGFU	4oz clear soil jar	BP1U	1L unpreserved plastic
DG9S	40mL H ₂ SO ₄ amber vial	BJFU	4oz unpreserved amber wide	BP1Z	1L NaOH, Zn Acetate
DG9T	40mL Na Thio amber vial	CG3H	250mL clear glass HCl	BP2A	500mL NaOH/Asc Acid plastic
DG9U	40mL amber unpreserved	AG1H	1L HCl amber glass	BP2N	500mL HNO ₃ plastic
VG9A	40mL Asc Acid glass	AG1S	1L H ₂ SO ₄ amber glass	BP2S	500mL H ₂ SO ₄ plastic
VG9B	40mL Sodium Bisulfate glass	AG1U	1liter unpres amber glass	BP2U	500mL unpreserved plastic
VG9C	40mL NaOH clear vial	AG2S	500mL H ₂ SO ₄ amber glass	BP2Z	500mL NaOH, Zn Acetate
VG9H	40mL HCl clear vial	AG3S	250mL H ₂ SO ₄ amber glass	BP3B	250mL NaOH plastic
VG9T	40mL Na Thio. clear vial	AG3U	250mL unpres amber glass	BP3N	250mL HNO ₃ plastic
VG9U	40mL unpreserved clear vial	AG74	60mL amber glass NH ₄ Cl	BP3U	250mL unpreserved plastic
		AG4U	100mL unpres amber glass	BP3S	250mL H ₂ SO ₄ plastic
				BP4N	125mL HNO ₃ plastic
				BP4O	125mL (NH ₄) 2SO ₄ /NH ₄ OH plastic
				Matrix	
				WT	Water
				SL	Solid
				OL	Non-aqueous liquid
				WP	Wipe
				DW	Drinking Water

WO#: 30742291

LIMS30 Lab Sample Condition Upon Receipt (West Virgi

PM: BMJ Due Date: 12/31/24
CLIENT: BV-KIRKENV

Courier: ☐ Fed Ex ☐ UPS ☐ USPS ☐ Client ☐ 3rd Party Courier ☒ Pace ☐ Other

Tracking#:

Custody Seal on Cooler/Box/Containers Present: ☐ yes ☐ no

Seals intact: ☐ yes ☐ no

Thermometer Used

24

Type of Ice: ☒ Wet ☐ Blue ☐ None

Cooler Temperature

Observed Temp

0.8 °C

Correction Factor: 0.0 °C

Final Temp: 0.8 °C

Thermal Preservation Requirement Met Yes ☒ No ☐

pH paper Lot#

Date and Initials of person examining

contents:

	Yes	No	N/A	
Chain of Custody Present:	☒	☐	☐	1.
Chain of Custody Filled Out:	☒	☐	☐	2.
Chain of Custody Relinquished:	☒	☐	☐	3.
Sampler Name & Signature on COC:	☒	☐	☐	4.
Sample Labels match COC:	☒	☐	☐	5.
-Includes date/time/ID				
Matrix: <u>WT</u>				
Samples Arrived within Hold Time:	☒	☐	☐	6.
Short Hold Time Analysis (<72hr remaining):	☒	☐	☐	7.
Rush Turn Around Time Requested:	☒	☐	☐	8. <u>5 Day</u>
Sufficient Volume:	☒	☐	☐	9.
Correct Containers Used:	☒	☐	☐	10.
-Pace Containers Used:	☐	☐	☐	
Containers Intact:	☒	☐	☐	11.
Orthophosphate field filtered:	☐	☐	☒	12.
Hex Cr Aqueous sample field filtered:	☐	☐	☒	13.
-pH adjusted within 24 hours? (If yes, indicate acid lot #)	☐	☐	☒	
Filtered volume received for Dissolved tests:	☐	☐	☒	14.
All containers have been checked for chemical preservation:	☐	☐	☒	15.
exceptions: VOA, coliform, O&G, LLMercury, Non-aqueous matrix				
All containers meet method/chemical preservation requirements:	☐	☐	☒	
				Initial when completed
				Date:
				Tests not preserved:
Headspace in VOA Vials:	☐	☐	☒	16.
Trip Blank Present:	☐	☐	☒	17.
				Initial when completed: <u>UW</u>
				Date: <u>12/13/24</u>

Comments:

*PM review is documented electronically in LIMS, when the Project Manager closes the SRF Review schedule in LIMS. The status may be reviewed in the Status section of the Workorder Edit Screen.

Section 8

Geological Data Injection and Confining Zones

Section No. 8

The Clover Field is located on the western flank of the Arches Fork Anticline. The reservoir boundary, as determined from early drilling, was controlled on the west and down dip by water and on the east and up dip by a decrease in permeability. The Big Injun Sandstone is the productive interval in this field. The Keener is a very fine grained to coarse grained, tightly cemented, with very low permeability, sandstone. The Keener grades into the oil productive Pocono Big Injun Sandstone. The Big Injun is light gray to light green, very fine to medium grained, moderate to well sorted, sub angular, calcite or dolomite cemented sandstone. The Big Lime overlays the Keener and the Pocono Shale underlies the Big Injun. Both are thick impermeable formations. The Big Injun Sandstone on the Kaufman lease can be described as follows:

Gross Sand thickness: 24'

Pay thickness: 12.5'

Permeability: .8 md

Porosity: 15%

Connate water saturation: 65%

The full core report from W M Kaufman No. 7 is included in the Department of the Interior Report No. 6992 and is shown in Figure No. 5. Also included in the report are isopach and structure maps of the Big Injun that include the area surrounding this injection well.

A search of the West Virginia Geologic and economic Survey web site revealed data on earthquakes from 1824-2023. There was one event recorded in western Roane County in 2016 (2.51 magnitude). Kanawha and Jackson Counties also recorded a small number of quakes. All the recorded quakes were 20 miles or further from this injection well. A copy of this data is shown in the attached Fig No. 9.

Water injection (both Disposal and Secondary recovery) projects have been active in Roane County since the 1960's. Water injection in the Clover Field has been active since the 1970's with no known cases of induced seismic activity.

The accumulated volume of produced water injected into this well as of 9/30/2024 is 177,120 bbls. Based on this volume and the following reservoir characteristics:

Gross thickness- 33'

Net thickness (pay) -10'

Porosity- 15%

Water saturation – 32%

The Fluid flood front is 460' from the well bore of this injection well.

Section No. 8 (cont)


Fig No. 3 shows the calculated radial distance the water injected into this well has moved in the Big Injun formation. Assuming 2000 barrels of water are injected into this well in a years' time over the next 5 years the flood front would advance an additional 12' to 472' from the injection well W M Kaufman W-7.

LEGEND

-  - Surveyed Well or HG Energy Map Location
-  - Well Location from WVGES Well Database
-  - Surveyed Well - Class I
-  - Denotes a Water Source Tested Jan. 2018

Nov 2024

Jan. 2018




- CLOVER FIELD -
Injection Wells

Wm. Kaufman No. W-7 (47-087-00985)

ROANE CO., WV

Map Showing All Known Wells
Within the Quarter-Mile AOR
& WVGES Well Data Spots

Fig No 3




Well Bore Diagram

W.M. Kaufman W-7

API 47-087-00985

Delta Helix Energy, LLC

UIC 2D08700985-003



4708700985



McCallum
SCINTILLOMETER
GAMMA RAY LOG

ROA-985

PLUNG NO. H-56661

COMPANY: HOI FERRAD OIL FIELD SERVICE COMPANY

WELL: KAUFMAN #2 A-7

FIELD: CLOVER POOL

COUNTY: ROANE STATE: W. VIRGINIA

LOCATION: OTHER SERVICES:

SEC. TWP. ROE.

ELEVATIONS:

PERMANENT CATTAN LOG MEASURED FROM 6.1' ELEV. 1005.40'
 DRILLING MEASURED FROM 5' ABOVE PERMANENT CATTAN LOG 1008.40'
 DATE 1-28-63

RUN NO. 1

TYPE LOG: GAMMA RAY

DEPTH - SHALLOM 2219'

DEPTH - LOGGING 2210'

BOTTOM LOGGED INTERVAL 2210' - 2219'

TOP LOGGED INTERVAL 2118'

TYPE FILLED IN HOLE: MUD

SALINITY PPM CL.

DENSITY LB./GAL.

LEVEL.

MAX. REEL TEMP. DEG. F.

OPE. RIG TIME

RECORDED BY: J. H. HARRIS

WITNESSED BY: H. H. HARRIS

BUN

BORE HOLE RECORD

CASSING RECORD

NO. 1

FROM 0'

TO 172'

DIAM. 8"

DETECT. MODEL NO. 131

TYPE SCINT

LENGTH 1'

DIST. TO N. SOURCE

HONEY TRACK NO. 2086

INST. TRUCK NO. 2086

TOOL SERIAL NO. D-8

LOG TICKET NO. E-15073

GENERAL

FROM 2210

TO 2219

SPEED FT./MIN. 18

Y.C. REC. 1.8

GROSS MEASUREMENT 0-150

ZERO DIV. L. OF R. 1-2

APRIL UNITS PER 100 DIV. 81

T.E. SET

SERIAL SETTINGS

ZERO DIV. L. OF R.

APRIL UNITS PER 100 DIV.

REFERENCE LITERATURE:

REMARKS:

0 1.35" GAMMA RAY ZERO & STATISTICAL TAKEN AT 1930'

1.35"

A. P. I. UNITS

0 64 168 252 336

1950

2000

**Big Lime
Top: 2024**

2050

2100

Big Lime
Bottom: 2150

Big Injun
Top: 2150
Bottom: 2188

2150

2200

A. P. I. UNITS

0 84 168 252 336

LOG BOTTOM 2210'

WOLFHEAD OIL & REFINING COMPANY
KAUFMAN #7
CLOVER POOL FIELD
ROANE COUNTY, W. VIRGINIA

2150
2016
130

REPEAT

2100


2150

2200




4708700985 W-7⁻¹⁷⁻

4708701056 W-19

**Pay Sand**

Big Injun Isopach


4708700985
Kaufman W-7



Isopachous Map of the Big Injun Sand, William Kaufman Lease, Clover-Rush Run Oilfield.


4708700985 W-7
4708701056 W-19

8.



4708700985

W-7




0 800 1600
Scale, feet

LEGEND

- Oil well
- ⊗ Gas-injection well

- Structure Contour Map on Top of Big Injun Sand, William Kaufman Lease, Clover-Rush Run Oilfield.





Earthquake Epicenters of West Virginia



1824 through 2024

Publications Policy:

This publication represents interpretations of best available data made by professional geologists and geographers. As in all research work, professional interpretations may vary, and can change with advancements in both technology and data quality. This publication is offered as a service of the State of West Virginia; proper use of the information herein is the sole responsibility of the user.

Permission to reproduce this publication is granted if acknowledgement is given to the West Virginia Geological and Economic Survey.

Map Date: 2/23/2024
Earthquake Data: 2/16/2024
Projection: Transverse Mercator
Horizontal Datum: NAD 1983
Map scale for full
8.5" x 11" display: 1:2,000,000



West Virginia Geological
and Economic Survey
Mont Chateau Research Center
1 Mont Chateau Road
Morgantown, WV 26508-8079
Phone: (304) 594-2331
www.wvgs.wvnet.edu

Map Num	Time (event ID)	County	UTC Year	UTC Month	UTC Day	UTC Hour	UTC Minute	UTC Seconds	Latitude	Longitude	Magnitude	Magnitude Type	Recorded	MMI	Event URL
1	1824-07-15T16:20:00	Wetzel	1824	07	15	16	20	00	39.70000	-80.50000	4.1	mb	Historic	4.0	<NULL>
2	1846-10-19T02:00:00	Jefferson	1846	10	19	02	00	00	39.30000	-77.90000	2.7	<NULL>	Historic	3	<NULL>
3	1853-05-02T14:20:00	Pendleton	1853	05	02	14	20	00	38.50000	-79.50000	4.4	<NULL>	Historic	5	<NULL>
4	1909-04-02T07:25:00	Berkeley	1909	04	02	07	25	00	39.40000	-78.00000	3.6	mb	Historic	5	<NULL>
5	1933-06-15T01:14:36.8	Mingo	1933	06	15	01	14	36.8	37.56800	-81.97300	0.0	<NULL>	Historic	<NULL>	<NULL>
6	1935-11-01T08:30:00	Hardy	1935	11	01	08	30	00	38.90000	-78.90000	3.3	<NULL>	Historic	4	<NULL>
7	1957-03-07T21:05:09	Monongalia	1957	03	07	21	05	09	39.60000	-79.90000	2.9	mb	Historic	3	<NULL>
8	1957-03-13T21:00:41	Monongalia	1957	03	13	21	00	41	39.60000	-79.90000	2.9	mb	Historic	3	<NULL>
9	1963-10-10T00:00:00	Morgan	1963	10	10	00	00	00	39.65500	-78.19700	3.6	<NULL>	Historic	<NULL>	<NULL>
10	1964-11-25T02:50:05	McDowell	1964	11	25	02	50	05	37.40000	-81.50000	4.5	mb	Instrumental	<NULL>	<NULL>
11	1965-04-26T15:26:19.7	McDowell	1965	04	26	15	26	19.7	37.32500	-81.60200	3.5	mblg	Instrumental	<NULL>	<NULL>
12	1966-09-28T00:00:00	Harrison	1966	09	28	00	00	00	39.30000	-80.30000	3.1	<NULL>	Instrumental	4	<NULL>
13	1967-12-16T12:23:33.4	McDowell	1967	12	16	12	23	33.4	37.36000	-81.60400	3.5	mb	Instrumental	<NULL>	<NULL>
14	1969-11-20T01:00:09.3	Mercer	1969	11	20	01	00	09.3	37.44900	-80.93200	4.6	mblg	Instrumental	6	<NULL>
15	1969-11-20T01:00:10.700Z	Mercer	1969	11	20	01	00	10.700	37.449000	-80.932000	4.54	mw	Instrumental	5	https://earthquake.usgs.gov/earthquakes/eventpage/ushis3082/
16	1970-08-11T06:14:25.5	Lincoln	1970	08	11	06	14	25.5	38.23000	-82.05000	2.8	mblg	Instrumental	4	<NULL>
17	1971-04-01T05:05:11	McDowell	1971	04	01	05	05	11	37.40000	-81.60000	3.0	mb	Instrumental	0	<NULL>
18	1972-01-09T23:24:29	McDowell	1972	01	09	23	24	29	37.40000	-81.60000	3.7	mblg	Instrumental	0	<NULL>
19	1972-09-12T15:17:13.7	Monongalia	1972	09	12	15	17	13.7	39.60000	-79.90000	2.9	mb	Historic	3	<NULL>
20	1974-10-20T15:13:55.100Z	Wood	1974	10	20	15	13	55.100	39.095000	-81.593000	3.40	lg	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/usp00008g9/
21	1976-01-30T18:58:49.800Z	Morgan	1976	01	30	18	58	49.800	39.683000	-78.170000	2.80	lg	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/usp0000eu9/
22	1976-05-06T18:46:08.1	Monongalia	1976	05	06	18	46	08.1	39.60000	-79.90000	3.1	mb	Historic	4	<NULL>
23	1976-06-19T05:54:13.900Z	McDowell	1976	06	19	05	54	13.900	37.362000	-81.624000	4.70	mb	Instrumental	6	https://earthquake.usgs.gov/earthquakes/eventpage/usp0000gyg/
24	1976-07-03T20:53:45.08	Mercer	1976	07	03	20	53	45.08	37.32000	-81.13000	2.7	mblg	Instrumental	<NULL>	<NULL>
25	1978-08-14T04:50:05.4	Fayette	1978	08	14	04	50	05.4	37.93900	-80.87400	1.6	mc	Instrumental	<NULL>	<NULL>
26	1979-09-16T09:39:22.6	Pocahontas	1979	09	16	09	39	22.6	38.09900	-80.24000	1.6	mc	Instrumental	<NULL>	<NULL>
27	1979-09-19T00:45:57.4	Pocahontas	1979	09	19	00	45	57.4	38.11000	-80.24300	2.0	mc	Instrumental	<NULL>	<NULL>
28	1979-10-31T08:32:47.3	Raleigh	1979	10	31	08	32	47.3	37.61700	-81.20700	0.8	mc	Instrumental	<NULL>	<NULL>
29	1980-04-10T22:33:15.7	Mercer	1980	04	10	22	33	15.7	37.48700	-81.08600	0.7	mc	Instrumental	<NULL>	<NULL>
30	1980-09-21T10:02:46.3	Pocahontas	1980	09	21	10	02	46.3	38.17500	-80.07000	1.4	mc	Instrumental	<NULL>	<NULL>
31	1980-10-16T03:48:07.6	Pocahontas	1980	10	16	03	48	07.6	38.06600	-80.21500	1.1	mc	Instrumental	<NULL>	<NULL>
32	1980-11-05T21:48:14.2	Pocahontas	1980	11	05	21	48	14.2	38.18800	-79.93600	3.0	ml	Instrumental	<NULL>	<NULL>
33	1980-11-25T07:44:04	Pocahontas	1980	11	25	07	44	04	38.09500	-80.12300	0.6	md	Instrumental	<NULL>	<NULL>
34	1981-11-30T17:33:11	Mingo	1981	11	30	17	33	11	37.63000	-82.20000	2.5	mc	Instrumental	<NULL>	<NULL>
35	1982-06-23T16:17:34.1	Fayette	1982	06	23	16	17	34.1	37.87000	-80.95700	2.5	md	Instrumental	<NULL>	<NULL>
36	1983-01-21T05:33:20.4	Pocahontas	1983	01	21	05	33	20.4	38.06700	-80.14400	0.4	md	Instrumental	<NULL>	<NULL>
37	1983-05-26T01:04:44.8	Monroe	1983	05	26	01	04	44.8	37.50600	-80.31600	2.2	md	Instrumental	<NULL>	<NULL>
38	1983-06-10T00:18:40.4	Greenbrier	1983	06	10	00	18	40.4	37.94800	-80.16300	1.2	md	Instrumental	<NULL>	<NULL>
39	1983-06-10T00:24:57	Greenbrier	1983	06	10	00	24	57	37.95100	-80.18900	1.2	md	Instrumental	<NULL>	<NULL>
40	1983-06-10T00:31:08.3	Greenbrier	1983	06	10	00	31	08.3	37.93800	-80.16800	0.4	md	Instrumental	<NULL>	<NULL>
41	1983-07-20T04:41:40.9	Greenbrier	1983	07	20	04	41	40.9	37.88500	-80.69100	1.6	md	Instrumental	<NULL>	<NULL>
42	1983-07-25T03:27:00.2	Wyoming	1983	07	25	03	27	00.2	37.49600	-81.35200	0.6	md	Instrumental	<NULL>	<NULL>
43	1983-11-13T16:51:06.7	Summers	1983	11	13	16	51	06.7	37.55600	-80.77500	0.4	md	Instrumental	<NULL>	<NULL>
44	1983-11-13T17:50:50.1	Monroe	1983	11	13	17	50	50.1	37.55900	-80.75300	0.7	md	Instrumental	<NULL>	<NULL>
45	1983-11-25T16:27:47.8	Monroe	1983	11	25	16	27	47.8	37.56800	-80.74500	0.7	md	Instrumental	<NULL>	<NULL>
46	1983-12-23T10:51:21.9	Summers	1983	12	23	10	51	21.9	37.76600	-80.83700	0.3	md	Instrumental	<NULL>	<NULL>
47	1984-02-02T05:10:19.7	Mingo	1984	02	02	05	10	19.7	37.71700	-82.21800	1.9	md	Instrumental	<NULL>	<NULL>
48	1984-03-11T04:01:38.9	Summers	1984	03	11	04	01	38.9	37.47400	-80.90000	1.1	md	Instrumental	<NULL>	<NULL>
49	1984-10-09T05:33:31.5	Summers	1984	10	09	05	33	31.5	37.71300	-80.89100	2.1	md	Instrumental	<NULL>	<NULL>
50	1984-12-21T13:12:21.9	Pocahontas	1984	12	21	13	12	21.9	38.19800	-80.20800	1.6	md	Instrumental	<NULL>	<NULL>
51	1985-06-14T07:57:10.2	Mercer	1985	06	14	07	57	10.2	37.53400	-81.02000	0.8	md	Instrumental	<NULL>	<NULL>
52	1986-02-26T21:53:20.8	Pendleton	1986	02	26	21	53	20.8	38.50700	-79.29200	2.3	md	Instrumental	<NULL>	<NULL>
53	1986-12-20T08:13:12.8	Greenbrier	1986	12	20	08	13	12.8	38.05800	-80.64300	1.2	md	Instrumental	<NULL>	<NULL>
54	1989-03-19T10:07:55.8	Logan	1989	03	19	10	07	55.8	37.73500	-82.06400	1.9	md	Instrumental	<NULL>	<NULL>
55	1991-04-22T01:01:20.270Z	Greenbrier	1991	04	22	01	01	20.270	37.941000	-80.207000	3.50	mblg	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/usp0004qn8/
56	1991-06-28T18:34:51.920Z	Kanawha	1991	06	28	18	34	51.920	38.276000	-81.668000	3.20	mblg	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/usp0004thc/
57	1992-03-29T20:16:48.2	Mercer	1992	03	29	20	16	48.2	37.31400	-81.14900	1.4	md	Instrumental	<NULL>	<NULL>
58	1992-05-06T21:20:23.9	Fayette	1992	05	06	21	20	23.9	38.11800	-81.06900	2.3	md	Instrumental	<NULL>	<NULL>
59	1992-11-24T02:26:50.7	Summers	1992	11	24	02	26	50.7	37.45700	-80.88400	1.2	md	Instrumental	<NULL>	<NULL>
60	1994-02-04T07:40:32.4	Nicholas	1994	02	04	07	40	32.4	38.23600	-80.75900	2.1	md	Instrumental	<NULL>	<NULL>

Map Num	Time (event ID)	County	UTC Year	UTC Month	UTC Day	UTC Hour	UTC Minute	UTC Seconds	Latitude	Longitude	Magnitude	Magnitude Type	Recorded	MMI	Event URL
61	1994-06-19T08:36:41.3	Nicholas	1994	06	19	08	36	41.3	38.33900	-80.64000	1.7	md	Instrumental	<NULL>	<NULL>
62	1995-11-15T10:29:24.8	Raleigh	1995	11	15	10	29	24.8	37.71700	-81.04300	2.6	md	Instrumental	<NULL>	<NULL>
63	1995-12-28T23:48:30.4	Fayette	1995	12	28	23	48	30.4	38.08400	-80.96800	2.5	md	Instrumental	<NULL>	<NULL>
64	1996-08-11T09:11:21.3	Greenbrier	1996	08	11	09	11	21.3	37.73100	-80.62800	2.1	mc	Instrumental	<NULL>	<NULL>
65	1997-02-22T14:32:33.1	Fayette	1997	02	22	14	32	33.1	37.92100	-81.02700	2.0	mc	Instrumental	<NULL>	<NULL>
66	1997-03-15T05:56:36.4	Webster	1997	03	15	05	56	36.4	38.34700	-80.48400	1.8	md	Instrumental	<NULL>	<NULL>
67	1998-10-02T10:01:06.9	Kanawha	1998	10	02	10	01	06.9	38.06800	-81.46600	2.5	md	Instrumental	<NULL>	<NULL>
68	2000-10-16T17:56:13.8	Braxton	2000	10	16	17	56	13.8	38.63600	-80.92000	2.5	md	Instrumental	<NULL>	<NULL>
69	2001-12-04T21:15:13.9	Summers	2001	12	04	21	15	13.9	37.72600	-80.75200	3.1	mb	Instrumental	<NULL>	<NULL>
70	2002-03-27T08:25:03.3	Mingo	2002	03	27	08	25	03.3	37.75300	-82.17100	2.1	md	Instrumental	<NULL>	<NULL>
71	2006-07-11T12:01:43.100Z	Greenbrier	2006	07	11	12	01	43.100	37.882167	-80.641333	2.60	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se606219/
72	2008-01-29T01:04:20.700Z	Monroe	2008	01	29	01	04	20.700	37.544833	-80.509833	2.40	mlg	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se606830/
73	2009-04-11T18:11:09.070Z	Summers	2009	04	11	18	11	09.070	37.513333	-80.895667	2.40	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se607139/
74	2010-04-04T09:19:14.010Z	Braxton	2010	04	04	09	19	14.010	38.599000	-80.916167	3.40	mlg	Instrumental	5	https://earthquake.usgs.gov/earthquakes/eventpage/se608185/
75	2010-04-29T01:36:21.260Z	Braxton	2010	04	29	01	36	21.260	38.685667	-80.814833	2.60	mlg	Instrumental	4	https://earthquake.usgs.gov/earthquakes/eventpage/se608194/
76	2010-04-29T12:38:53.430Z	Braxton	2010	04	29	12	38	53.430	38.664833	-80.856167	2.70	mlg	Instrumental	3	https://earthquake.usgs.gov/earthquakes/eventpage/se608196/
77	2010-04-29T23:26:39.470Z	Braxton	2010	04	29	23	26	39.470	38.722000	-80.803000	2.50	mblg	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/usp000hc39/
78	2010-05-07T10:26:03.540Z	Braxton	2010	05	07	10	26	03.540	38.602333	-80.912167	2.60	mlg	Instrumental	3	https://earthquake.usgs.gov/earthquakes/eventpage/se608197/
79	2010-05-08T03:03:00.620Z	Braxton	2010	05	08	03	03	00.620	38.623000	-80.911333	2.40	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se608198/
80	2010-07-24T09:15:44.130Z	Braxton	2010	07	24	09	15	44.130	38.675333	-80.820167	2.40	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se608209/
81	2010-07-25T03:48:35.550Z	Braxton	2010	07	25	03	48	35.550	38.679167	-80.797167	2.20	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se608210/
82	2010-08-15T04:38:47.380Z	Lewis	2010	08	15	04	38	47.380	38.818333	-80.429833	2.50	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se608213/
83	2010-08-21T03:16:21.990Z	Upshur	2010	08	21	03	16	21.990	38.792500	-80.397667	2.50	md	Instrumental	3	https://earthquake.usgs.gov/earthquakes/eventpage/se608214/
84	2010-08-26T04:22:15.190Z	Raleigh	2010	08	26	04	22	15.190	37.748333	-81.204667	2.40	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se608215/
85	2010-08-26T04:24:55.390Z	Raleigh	2010	08	26	04	24	55.390	37.727333	-81.204333	2.20	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se608216/
86	2010-09-13T15:08:46.470Z	Lincoln	2010	09	13	15	08	46.470	38.099833	-82.034000	2.40	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se608218/
87	2011-08-25T05:59:13.760Z	Greenbrier	2011	08	25	05	59	13.760	37.916000	-80.215333	2.70	md	Instrumental	4	https://earthquake.usgs.gov/earthquakes/eventpage/se609219/
88	2012-01-10T19:38:58.660Z	Braxton	2012	01	10	19	38	58.660	38.566833	-80.893833	2.80	mlg	Instrumental	4	https://earthquake.usgs.gov/earthquakes/eventpage/se609646/
89	2012-03-16T15:05:53.570Z	Kanawha	2012	03	16	15	05	53.570	38.234000	-81.748000	2.60	mblg	Instrumental	3	https://earthquake.usgs.gov/earthquakes/eventpage/usp000jgbk/
90	2013-03-31T14:01:24.030Z	Braxton	2013	03	31	14	01	24.030	38.645000	-80.833167	3.40	mw	Instrumental	5	https://earthquake.usgs.gov/earthquakes/eventpage/se610164/
91	2013-05-29T21:06:11.100Z	Kanawha	2013	05	29	21	06	11.100	38.365333	-81.275667	2.26	ml	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/ld60041041/
92	2013-07-20T11:38:46.180Z	Gilmer	2013	07	20	11	38	46.180	38.895667	-80.887000	2.70	mlg	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se610199/
93	2013-07-30T06:09:04.850Z	Gilmer	2013	07	30	06	09	04.850	38.839333	-80.908667	2.80	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se610203/
94	2013-08-16T11:02:21.040Z	Gilmer	2013	08	16	11	02	21.040	38.841500	-80.938667	2.60	mlg	Instrumental	3	https://earthquake.usgs.gov/earthquakes/eventpage/se610207/
95	2013-10-13T09:20:58.550Z	Braxton	2013	10	13	09	20	58.550	38.701167	-80.824167	2.20	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se610225/
96	2013-10-19T08:41:57.430Z	Greenbrier	2013	10	19	08	41	57.430	37.747667	-80.643333	2.20	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se610227/
97	2014-04-14T17:44:27.380Z	Clay	2014	04	14	17	44	27.380	38.453000	-80.889500	2.10	ml	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/ld60066331/
98	2014-06-06T22:15:40.790Z	Jackson	2014	06	06	22	15	40.790	38.643833	-81.585500	2.60	md	Instrumental	3	https://earthquake.usgs.gov/earthquakes/eventpage/se610630/
99	2016-01-17T19:12:49.050Z	Jefferson	2016	01	17	19	12	49.050	39.319333	-77.828333	3.03	ml	Instrumental	1	https://earthquake.usgs.gov/earthquakes/eventpage/ld60108801/
100	2016-08-06T12:39:14.210Z	Mingo	2016	08	06	12	39	14.210	37.863000	-82.128833	2.31	md	Instrumental	1	https://earthquake.usgs.gov/earthquakes/eventpage/se60029113/
101	2016-12-01T01:27:04.780Z	Roane	2016	12	01	01	27	04.780	38.760833	-81.485333	2.51	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se60032413/
102	2017-06-21T08:01:32.720Z	Kanawha	2017	06	21	08	01	32.720	38.199500	-81.398500	2.70	md	Instrumental	4	https://earthquake.usgs.gov/earthquakes/eventpage/se60172362/
103	2017-08-13T06:52:15.080Z	Webster	2017	08	13	06	52	15.080	38.345833	-80.568500	2.01	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se60042903/
104	2017-09-13T17:33:10.930Z	Monroe	2017	09	13	17	33	10.930	37.472833	-80.703000	3.20	md	Instrumental	4	https://earthquake.usgs.gov/earthquakes/eventpage/se60179327/
105	2019-03-04T07:41:54.780Z	Greenbrier	2019	03	04	07	41	54.780	37.838167	-80.704167	2.61	md	Instrumental	2	https://earthquake.usgs.gov/earthquakes/eventpage/se60076828/
106	2020-07-29T00:36:35.820Z	Pocahontas	2020	07	29	00	36	35.820	38.222333	-79.911500	2.43	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se60322771/
107	2020-07-30T05:57:13.780Z	Pocahontas	2020	07	30	05	57	13.780	38.222000	-79.908333	2.38	md	Instrumental	4	https://earthquake.usgs.gov/earthquakes/eventpage/se60323026/
108	2021-12-07T10:06:15.620Z	Monroe	2021	12	07	10	06	15.620	37.512000	-80.388500	1.86	md	Instrumental	2	https://earthquake.usgs.gov/earthquakes/eventpage/se60139853/
109	2022-08-10T00:36:34.020Z	Pocahontas	2022	08	10	00	36	34.020	38.160667	-80.013167	2.04	md	Instrumental	2	https://earthquake.usgs.gov/earthquakes/eventpage/se60158843/
110	2023-02-17T21:54:06.190	Mason	2023	02	17	21	54	06.190	38.917000	-82.043000	2.50	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se60500438/
111	2024-02-10T10:24:49.840Z	Nicholas	2024	02	10	10	24	49.840	38.2928333	-80.5381667	2.29	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se60501603/

Data as of 2/16/2024. For a more detailed listing, please download the West Virginia Earthquake spreadsheet/workbook from <http://www.wvgs.wvnet.edu/www/earthquakes/seismic.html>.

If you view this map and data as a PDF, you can click any of the blue hyperlinked text to view further information on a website.

Some definition of terms are provided with this map. Please consult the West Virginia Earthquake Catalog 202402.xlsx spreadsheet/workbook for complete definitions.




Some Definitions and Explanations:

- **County:** the name of the county where the epicenter was located, derived from spatial selection.
- Dates and times are in Coordinated Universal Time (UTC) for Year, Month, Day, Hours (HH), Minutes (MM) and Seconds (SS). (For Eastern Standard Time, the offset is - 5 hours).
- **Magnitude (Mag):** Magnitude numbers indicative of an earthquake's relative size and is the measured maximum motion as recorded by a seismograph. The numbers are pulled from various sources; the primary source whenever possible.
- **Recorded:** refers to the means by which magnitudes were recorded: if they were reported as "felt" (Historical) or recorded via scientific instrumentation (Instrumental) as retrieved from Source1 or Source2.
- **Latitude and Longitude** values are expressed in decimal degrees for the northern and western hemispheres, respectively.
- **MMI:** The Modified Mercalli Intensity scale for epicenter intensity, usually designated with Roman numerals. Visit USGS at <https://www.usgs.gov/programs/earthquake-hazards/modified-mercalli-intensity-scale> for further information.
- **MagnitudeType:** Magnitude type code; the method used in measuring magnitudes (e.g., *Mb* for "body-wave", *Mc* for "coda amplitude", *Md* for "coda duration").

For other or more detailed earthquake and seismological definitions, please visit the USGS (<https://earthquake.usgs.gov/learn/glossary/>).

Sources (Source1 and Source2):

- USGS ENS – [United States Geological Survey, Earthquake Hazards](#) (A Primary Source)
- VTSSO – [Virginia Tech Seismological Observatory](#) (A Secondary Source)
- ANSS – [Advanced National Seismic System](#)
- CERI – [Center for Earthquake Research and Information](#)
- LDEO – [Lamont-Doherty Earth Observatory](#)
- Wheeler I-2737 – Wheeler, Russell L., [Earthquakes In and Near the Northeastern United States, 1638-1998](#) (Used only as reference here)



Northeastern United States and southeastern Canadian earthquakes from 1990 to 2011.
Image courtesy of the Lamont-Doherty Earth Observatory (Won-Young Kim)
of Columbia University, New York. Used by permission.



West Virginia Geological and
Economic Survey
<https://www.wvgs.wvnet.edu/>

RESERVOIR STUDY OF THE WILLIAM KAUFMAN LEASE CLOVER-RUSH RUN OILFIELD, ROANE COUNTY, W. VA.

By Karl-Heinz Frohne

* * * * * report of investigations 6992



UNITED STATES DEPARTMENT OF THE INTERIOR
Stewart L. Udall, Secretary

BUREAU OF MINES
Walter R. Hibbard, Jr., Director

This publication has been cataloged as follows:

Frohne, Karl-Heinz

Reservoir study of the William Kaufman lease, Clover-Rush Run oilfield, Roane County, West Virginia. [Washington] U.S. Dept. of the Interior, Bureau of Mines [1967]

17 p. illus., tables. (U. S. Bureau of Mines. Report of investigations 6992)

Includes bibliography.

1. Oil fields--West Virginia--Roane County. 2. Secondary oil recovery. 3. Oil field flooding. I. Title. (Series)

TN23.U7 no. 6992 622.06173

U. S. Dept. of the Int. Library

CONTENTS

	<u>Page</u>
Abstract.....	1
Introduction.....	1
Acknowledgments.....	2
General geology.....	2
Location and topography.....	2
Area structure and stratigraphy.....	2
Field development and lease history.....	4
Development of Clover-Rush Run oilfield.....	4
History of William Kaufman lease.....	4
Coring and logging operations.....	5
Reservoir data.....	5
Structure.....	5
Lithology.....	6
Core analysis.....	7
Log analysis.....	7
Reservoir limits.....	8
Reservoir temperature and pressure.....	8
Permeability.....	9
Reservoir-fluid saturations.....	9
Reservoir-fluid properties.....	10
Reservoir performance.....	10
Primary-performance prediction.....	10
Secondary recovery.....	10
Waterflood prediction.....	10
Gas-injection project.....	11
Summary.....	12
References.....	13
Appendix A.--Core analysis data for Kaufman well P-7.....	14
Appendix B.--Recommended analyses for pressure-volume-temperature samples at pressures below original reservoir pressures.....	15
Appendix C.--Pressure-volume-temperature analysis adjustment procedure..	16

ILLUSTRATIONS

<u>Fig.</u>		
1.	Oil-productive areas in Roane County, W. Va., and the William Kaufman lease in the Glover-Rush Run oilfield.....	3
2.	Generalized geologic column of subsurface formations, Glover-Rush Run oilfield.....	4
3.	Structure contour map on top of Big Injun sand, William Kaufman lease, Glover-Rush Run oilfield.....	5
4.	Isopachous map of the Big Injun sand, William Kaufman lease, Glover-Rush Run oilfield.....	6
5.	Capillary pressure versus water saturation for the Big Injun sand in Kaufman well P-7, Glover-Rush Run oilfield.....	9

ILLUSTRATIONS --Continued

<u>Fig.</u>	<u>Page</u>
6. Production decline curve for the William Kaufman lease, Clover-Rush Run oilfield.....	11
7. Oil and water relative permeability curve for the Big Injun sand in Kaufman well P-7, Clover-Rush Run oilfield.....	11

TABLES

A-1. Core analysis results, Kaufman well P-7.....	14
C-1. Original and adjusted pressure-volume-temperature analyses data, Kaufman well P-7.....	17

RESERVOIR STUDY OF THE WILLIAM KAUFMAN LEASE, CLOVER-RUSH RUN OILFIELD, ROANE COUNTY, W. VA.

by

Karl-Heinz Frohne¹

ABSTRACT

This report presents the findings of a study of a portion of the Clover-Rush Run oilfield located in Roane County, W. Va. The study was made to investigate the possibilities of secondary oil recovery in the Big Injun sandstone underlying the William Kaufman lease. Reservoir properties, original reserves, and primary oil recovery are also presented.

The investigation is based on a core analysis and related laboratory tests, well records, field production data, and subsurface information from the Kaufman property. A theoretical primary oil recovery of 9.7 percent of original oil in place is predicted for the reservoir.

A waterflood performance prediction of a hypothetical pilot area was made by use of a computer. The prediction showed that, based on laboratory oil-water relative permeability curves, the water-injection time needed to initiate oil production is excessive and that the stabilized water-injection and corresponding oil-production rates are very low. This precludes waterflooding the reservoir on an economic basis.

A prediction for secondary oil recovery by gas injection was attempted but could not be completed because essential reservoir data were not available. In July 1965, the lease operator initiated, and is currently conducting, a gas-injection program, but there had been no increase in oil production up to November 1966.

INTRODUCTION

Production records and well logs show that primary oil production from the Big Injun sand has been by solution-gas drive in the Clover-Rush Run oilfield. Solution gas is the most inefficient of natural drives and can be

¹ Petroleum research engineer, Morgantown Petroleum Research Laboratory, Bureau of Mines, Morgantown, W. Va.

expected to recover only 5 to 25 percent (2)² of oil in place. Primary oil recovery from Appalachian area reservoirs is usually in the lower end of this range because of the very low permeability of the hydrocarbon-bearing formations, thus a large part of the oil is unrecovered.

In order to aid the reclamation of this valuable resource, the Bureau of Mines is currently engaged in evaluating methods of increasing the secondary recovery of oil from selected Appalachian area reservoirs. The work, of which this report is a part, is being carried out under the Bureau's Reservoir Evaluation Project by utilizing detailed core analyses and other field data to perform reservoir evaluations and provide secondary recovery recommendations. The plans and objectives of the project have been described in detail in another publication (1).

Even though one of the older Kaufman wells produced from the Big Lime formation, the only zone of consequence underlying the lease is the Big Injun sandstone which is the main area of interest of this report. At the present time, the lease operator is injecting natural gas into the Big Injun formation in order to stimulate oil recovery. This project is described in more detail later in the report.

A preliminary report on the Kaufman lease and the well cored by the Bureau has been published (6).

ACKNOWLEDGMENTS

The cooperation of the Pennzoil Co., operator of the William Kaufman lease, in providing well records, logs, and other data for this report is acknowledged.

GENERAL GEOLOGY

Location and Topography

The Clover-Rush Run oilfield is located in Smithfield and Spencer Districts, Roane County, W. Va. (fig. 1). The area topography is typical of the Appalachian Plateau. Outcropping rocks belong to either the Dunkard Series of the Lower Permian Period or the Monongahela Series of the Pennsylvania Period (5). The rugged terrain, formed by stream erosion of the plateau, consists mainly of narrow V-shaped valleys and steep ridges, although a few bottom lands and flat-topped hills can be found. Maximum elevation differences are on the order of 600 feet.

Area Structure and Stratigraphy

The Clover-Rush Run oilfield lies on the western flank of the Arches Fork anticline, and the Big Injun sand strikes north 30° east (4). In the Kaufman lease area, the sand dips to the northwest at about 70 feet per mile.

²Underlined numbers in parentheses refer to items in the list of references at the end of this report.




FIGURE 1. - Oil-Productive Areas in Roane County, W. Va., and the William Kaufman Lease in the Clover-Rush Run Oilfield.

A generalized geologic column for Roane County illustrates the stratigraphy of the area (fig. 2). Below the outcropping Dunkard and Monongahela formations lie the intermingled sandstones, limestones, shales, and coal seams of the Pennsylvanian Period. Next come the limestones, sands, and shales of the Mississippian Period, including the basal Greenbrier limestone and dolomite and the Keener and Big Injun sandstones which were cored in well P-7 on the William Kaufman lease.

GENERALIZED GEOLOGIC COLUMN			
SYSTEM	FORMATION OR GROUP	ROCK COLUMN	DRILLERS' TERMS
PERMIAN	DUNKARD		WASHINGTON COAL
	MONONGAHELA		
			PITTSBURGH COAL
	CONEMAUGH		BIG DUNKARD SAND UPPER FREEPORT COAL
	ALLEGHENY		BURNING SPRINGS SAND
	POTTSVILLE		SALT OR ROSEDALE GAS SAND
MISSISSIPPIAN			ROSEDALE SALT SAND
	MAUCH CHUNK		MAXTON SAND
	GREENBRIER		LITTLE LIME BIG LIME
	POCONO		"KEENER" SAND BIG INJUN SAND SQUAW SAND
			WEIR SAND
			BEREA SAND

FIGURE 2. - Generalized Geologic Column of Subsurface Formations, Clover-Rush Run Oilfield.

FIELD DEVELOPMENT AND LEASE HISTORY

Development of Clover-Rush Run Oilfield

The original discovery well for the Clover-Rush Run oilfield was Heasley and Co. well 1, drilled on the L. D. Chambers lease in 1909. An oil-productive area of about 4,200 acres had been outlined by 1926 through development drilling, and by 1961 approximately 350 wells had been completed within the original field limits (fig. 1).

In the summer of 1961 a development boom began; about 60 new wells were drilled, and approximately 1,600 new productive acres were added to the northeastern side of the field by the summer of 1964. A large part of this drilling activity took place on the Kaufman lease.

Initial production from the old wells within the original field boundaries ranged from 2 to 40 barrels of oil per day. The use of hydraulic fracturing then raised the initial oil-production rates of the new development wells to a range of 15 to 250 barrels per day.

History of William Kaufman Lease

The present Kaufman lease (fig. 3) consists of 700 acres and was originally part of a larger Heasley and Co. holding. Sometime between 1909 and 1918, three oil wells were drilled within the lease area. About 1918, the Carter Oil Co. bought the lease and drilled three more producing wells. Next, the Hope Construction and Refining Co. leased the property. By 1920, Hope had also drilled three wells, each of which initially produced less than five barrels of oil per day. Finally the South Penn Oil Co., now the Pennzoil Co., bought the Kaufman lease from Hope in 1943 and completed two new oil wells by 1962.




FIGURE 3. - Structure Contour Map on Top of Big Injun Sand, William Kaufman Lease, Clover-Rush Run Oilfield.

Co. and the Bureau of Mines. The 3½-inch-diameter core was taken with rotary tools using a low-water-loss bentonite water-base mud. The cored interval extended from 2,131 to 2,212 feet with 100-percent recovery.

A group of well logs, including guard, spontaneous potential, 16- and 64-inch normals, continuous velocity, gamma ray-neutron, and caliper, was run after coring operations were completed. The log curves covering the cored interval have been previously published (6).

RESERVOIR DATA

Structure

The Big Injun sandstone underlying the Kaufman lease is at an average depth of 2,200 feet. The reservoir is bounded on the downdip western edge of the field by water and updip by a permeability pinchout which cuts across the northeastern corner of the Kaufman property. The sand ranges in gross thickness from 50 feet on the downdip side of the field to 15 feet updip, and averages 24 feet under the Kaufman lease. Structure and isopachous maps of the Big Injun sand are shown in figures 3 and 4, respectively.

All of the producing wells on the Kaufman lease except one of the wells drilled by South Penn had been abandoned by the summer of 1962 when a new flurry of development activity hit the lease. This drilling program produced 24 new oil wells in the Big Injun sandstone by July 1964 when development was stopped. A permeability pinchout in the formation to the northeast limits the new field addition. The Kaufman property is situated in this area of low to zero permeability, and lease wells had only slight shows of oil on initial completion. After fracturing, however, the wells produced 15 to 50 barrels of oil per day.

CORING AND LOGGING OPERATIONS

Kaufman lease well P-7 was cored in September 1963 by personnel of the Pennzoil




FIGURE 4. - Isopachous Map of the Big Injun Sand, William Kaufman Lease, Clover-Rush Run Oilfield.

Lithology

The cored interval in Kaufman well P-7 included the basal Greenbrier limestone and the Keener and Big Injun sandstone formations. The Greenbrier, locally called Big Lime, is light gray to gray brown, is slightly sandy and oolitic, and contains traces of glauconite (6). The basal section consists of light gray to tan, granular, calcareous, and glauconitic dolomite bottomed by a conglomerate of calcium carbonate, cemented quartz pebbles, and pieces of limestone.

The conglomerate grades into what is known locally as the Keener sandstone which extends from 2,168 to 2,182 feet. This is a white, medium- to coarse-grained, calcareous sandstone with a quartz pebble, limestone fragment, and clay material conglomerate at the bottom.

The Keener is immediately followed by the oil-productive Big Injun, a light-gray, fine-grained, subgraywacke sandstone that covers the interval 2,182 to 2,206 feet. The formation is glauconitic, very slightly calcareous, and contains traces of mica and argillaceous material. The argillaceous matter consists of illite and kaolinite which, together with montmorillonite, coat the quartz grains and occupy some of the pore spaces. The quartz grains are poorly sorted and loosely bonded, primarily by the coating clay material.

Core Analysis

The Kaufman lease contains 800 acres, 567 of which are considered oil productive based on logs and production records of wells. Kaufman well P-7, located near the center of the productive area and one of the best producers on the lease, has a total sand thickness of 24 feet for the Big Injun.

Using 0.1 millidarcy as a limiting minimum permeability, only 12.5 feet, or 52 percent of the total interval of well P-7, are considered effective net sand. This factor has been applied to the effective area gross sand volume of the lease, as determined from the isopachous map, to give an areally weighted average net sand thickness of 12.7 feet.

Core data for the Big Injun sand in Kaufman well P-7 are summarized below:

	Interval	
	Effective	Total
Thickness.....feet..	12.5	24.0
Air permeability..... millidarcy..	.8	.5
Porosity.....percent..	15.2	12.7
Saturation:		
Oil.....do..	8.7	7.4
Water.....do..	65.1	68.0

Complete core analysis data for the portion of the cored interval, which includes the Keener and Big Injun sands, are presented in table A-1.

Log Analysis

Quantitative analyses of the logs run in Kaufman well P-7 gave no conclusive results for the Big Injun reservoir. Water saturations calculated from guard log resistivities and core porosities gave an average value of 25 percent for the gross sand interval. This is much lower than the established area saturation of approximately 50 percent. A possible explanation for the low reading is that fresh-water-mud filtrate may have invaded the logged interval.

Porosities for the Big Injun sandstone were calculated from both neutron and velocity logs. The average neutron log value of 9.5 percent is lower than the core analysis figure of 12.7 percent, which may be due to the presence of free gas saturation in the formation. The velocity log, however, gave a value of 21.7 percent. This high porosity may be the result of velocity log signal attenuation, or cycle skipping; also due to a free-gas saturation.

The caliper log showed that the borehole was very uniform and in-gage through the Big Injun interval, indicating a uniformly hard formation.

Reservoir Limits

As mentioned previously, only 567 acres of the 800-acre Kaufman property are considered commercially oil productive. The remaining 233 acres (fig. 4) have not been assigned reserves. This is based on Kaufman well P-3, the only well drilled on this part of the lease. The exact location of this well is not known, but its approximate position is shown in figure 1. No formal records are available for well P-3, but operating personnel believe that the well was plugged and abandoned shortly after completion. Only a few quarts of oil were bailed out after the well was shot with nitroglycerin.

The eastern side of the commercially nonproductive area is formed arbitrarily by the lease line, and the western and southern sides are based on one-half well spacing from the adjacent row of Kaufman lease wells. During 1964 and 1965, the M & M Drilling Co. of Spencer, W. Va., drilled and completed four gas wells (fig. 1) about 900 feet east of the Kaufman lease. The wells had estimated initial open flows of 1 million cubic feet per day, and oil production ranged from a show to 20 barrels per day.

In view of this production to the east, only a test well, completed with modern techniques in the portion of the lease now considered nonproductive, will determine if the formation underlying this part of the Kaufman property contains any producible oil reserves.

Reservoir Temperature and Pressure

On May 1, 1964, several bottom-hole surveys were taken in Kaufman well P-7. One of the measurements was a reservoir temperature survey which recorded a formation temperature of 74° F for the Big Injun sand.

Leasewide bottom-hole pressure surveys were conducted on three occasions on wells on the Kaufman property. Tests run in November 1963, gave an areally weighted average pressure of 462 psig for the Big Injun sand; in June 1964, the pressure was 379 psig; and in May 1965, it had dropped to 268 psig.

Since the formation in the lease area had been tapped as early as 1909 when reservoir-pressure surveys were unheard of, an original formation pressure had to be estimated. Using established area pressure gradients applicable to the Big Injun sandstone, the original formation pressure was estimated as 700 psig. The original crude oil is assumed to have been saturated at the initial reservoir pressure of 700 psig.

Permeability

Permeability measurements were made in the laboratory on sample plugs cut at 1-foot intervals from the core material from Kaufman well P-7. The average air permeabilities of the gross and net effective intervals of the Big Injun sandstone are 0.5 and 0.8 millidarcy, respectively. These values illustrate the extreme tightness of the sand, especially since well P-7 is considered the best oil producer on the lease. Core analysis results, including a complete list of permeabilities, are given in table A-1.

Reservoir-Fluid Saturations

Oil and water saturations were also measured at 1-foot intervals along the core. Average oil and water saturations of the effective net interval are 8.7 and 65.1 percent, respectively. These values cannot be considered representative since the well was cored with a fresh-water-base drilling mud, and because filtrate invasion and solution-gas expansion undoubtedly took place during coring.

Analysis of the electric log gave an average water saturation of 25 percent over the gross sand interval. This value, also, may be too low because of mud filtrate invasion of the logged formation.




FIGURE 5.- Capillary Pressure Versus Water Saturation for the Big Injun Sand in Kaufman Well P-7, Clover-Rush Run Oilfield.

Finally, a graph of capillary pressure versus water saturation (fig. 5) prepared from laboratory test data shows an irreducible water saturation of 51 percent. This value is in agreement with established saturations of the Big Injun sandstone in the area and is used in this report.

To date, no water has been produced from the Kaufman lease, and the 51-percent saturation is considered immobile and equal to the original reservoir water saturation. The original oil saturation would then be 49 percent, based on the assumption that the reservoir was initially 100 percent liquid filled.

Reservoir-Fluid Properties

Because the area under study has been produced since 1909, no direct analysis of the original reservoir fluids is available. However, a reservoir-fluid sample taken from Kaufman well P-7 in May 1964, when the bottom-hole sampling pressure of the well was 483 psig, was analyzed. By using a technique reported by Clark (1), and several assumed factors, this fluid analysis has been adjusted to represent the original reservoir fluid.

An outline for pressure-volume-temperature analysis tests necessary to fully utilize the above adjustment procedure is given in appendix B. The outline applies where the fluid sampling pressure is lower than the original reservoir pressure. The adjustment procedure and original and adjusted PVT analysis data for Kaufman well P-7 are given in appendix C.

In May 1964, the stock-tank crude oil gravity was 48.3° API at 60° F and the crude oil viscosity was 2.43 centipoises at 77° F.

RESERVOIR PERFORMANCE

Primary-Performance Prediction

The primary-recovery mechanism of the Big Injun sandstone under the Kaufman property is a dissolved-gas or depletion drive. This production method is inherently the most inefficient natural drive and, in the Appalachian area, will usually produce only about 5 to 25 percent of the oil in the reservoir.

The crude oil originally in place was calculated volumetrically, using core, electric log, and fluid analysis data, and was found to be 3,291,000 stock-tank barrels, or 457 barrels per acre-foot. A prediction of primary recovery was then made by analysis (3) of the production-decline curve (fig. 6) for the Kaufman lease. Overall primary recovery over the producing life from the original reservoir pressure of 700 psig to theoretical lease abandonment conditions--10 barrels of oil per day--was calculated to be 319,000 stock-tank barrels of oil. This represents a recovery of 9.7 percent of the oil in place, or 44 barrels per acre-foot, by primary solution-gas drive. Theoretical abandonment conditions would be reached in April 1970.

Secondary Recovery

Waterflood Prediction

A computer prediction for theoretical secondary oil recovery by waterflooding the Big Injun sandstone under the Kaufman property was made. The hypothetical pilot area consisted of a pattern of four 5-spots totaling 23 acres. An essential part of the prediction is based on the oil-water relative permeability curves obtained in the laboratory (fig. 7). As can be seen from the curves, the relative permeability to oil at initial conditions is good. This may explain the initial completion gages of 15 to 50 barrels of oil per day after fracturing. The relative permeability to water, however, stays very low through the laboratory test range of water saturations.




FIGURE 6. - Production Decline Curve for the William Kaufman Lease, Clover-Rush Run Oilfield.




FIGURE 7. - Oil and Water Relative Permeability Curve for the Big Injun Sand in Kaufman Well P-7, Clover-Rush Run Oilfield.

Due to this low relative water permeability, the predicted time required to fill the initial gas saturation space in the pilot area with water and for oil production to begin is 17 years. After fill-up, the stabilized water-injection rate reached was less than one-half barrel per well per day, and the oil-production rates were correspondingly low. These low water-injection and oil-production rates preclude waterflooding the lease on an economic basis under present-day reservoir technology.

Gas-Injection Project

A prediction of secondary-recovery performance by gas injection could not be made because of the absence of essential data, such as a gas-oil relative permeability relationship. Several attempts to determine a K_g/K_o curve in the laboratory failed because of the tightness of the core samples. Reasonable theoretical K_g/K_o curves could not be estimated for the same reason.

At the present time, the lease operator is conducting a gas-injection program on the property. The project was started July 1, 1965, with the reinjection of lease-produced gas into four wells (fig. 3). Lease injection volumes have averaged 400,000 to 500,000 cubic feet per day since the project was begun.

To date, there has been gas breakthrough in several producing wells, including well P-7. The rapidity with which breakthrough occurred in some wells seems to indicate at least partial communication between injection and producing wells. The communication may possibly be through joints or hydraulically induced fractures. An east-west trend in the direction of communication has also been observed.

After 14 months of gas injection, no production increase was noted. In the last few months, however, the rate of decline of oil production has been partially arrested. A program to decrease the high producing gas-oil ratios in order to conserve reservoir energy was recently initiated by selectively choking back some producers.

SUMMARY

Because of the inherent inefficiency of the solution-gas drive, primary recovery will be only a fraction of the oil reserves in the Big Injun sand, and more than 90 percent of the oil will be left behind in the reservoir. Secondary recovery by waterflooding is precluded by the relative oil-water permeability characteristics of the sand, and a prediction of secondary recovery by gas injection could not be made because essential reservoir data were not available. In order to stimulate oil production, the Kaufman lease operator is currently reinjecting natural gas into the producing formation.

REFERENCES

1. Clark, Norman J. Adjusting Oil Sample Data for Reservoir Studies. J. Petrol. Technol., v. 14, No. 2, February 1962, pp. 143-149.
2. Cole, Frank W. Reservoir Engineering Manual. Gulf Publishing Co., Houston, Tex., 1961, pp. 34-35.
3. Guerrero, E. T. How to Determine Performance and Ultimate Recovery by Exponential Decline Curve Analysis. Oil and Gas J., v. 59, No. 21, May 22, 1961, pp. 86-87.
4. Haught, Oscar L. Map of Wirt, Roane and Calhoun Counties Showing Oil and Gas Fields. W. Va. Geol. and Econ. Survey, 1958.
5. Hennen, R. V. Wirt, Roane, and Calhoun Counties. W. Va. Geol. Survey County Repts., 1911, pp. 507, 519-520.
6. Overbey, William K., Jr., and Donald M. Evans. Appalachian Region Oilfield Reservoir Investigations, Basal Greenbrier Limestone and Dolomite and "Keener" and Big Injun Sands, Clover-Rush Run Field, Smithfield District, Roane County, W. Va. Producers Monthly, v. 29, No. 5, May 1965, pp. 22-24.
7. Wasson, James A., Harry R. Johnson, and Dean W. Boley. Secondary Oil Recovery Possibilities--Cow Run Sand, Burning Springs Pool, Wirt County, W. Va. BuMines Rept. of Inv. 6460, 1964, 57 pp.

APPENDIX A.--CORE ANALYSIS DATA FOR KAUFMAN WELL P-7

TABLE A-1. - Core analysis results, Kaufman well P-7

Sample	Depth, ft	Air permeability, md	Porosity, pct	Fluid saturation, percent pore space		Oil content, bbl/acre-ft	Salinity, equivalent NaCl, ppm
				Oil	Water		
1,304	2,140.0	<0.1	0.1	(1)	(1)	(1)	(1)
1,305	2,141.0	<1	.6	-	-	-	-
1,306	2,142.0	<1	.6	-	-	-	-
1,307	2,148.9	<1	.1	-	-	-	-
1,308	2,150.4	<1	4.9	-	-	-	-
1,309	2,151.0	<1	5.1	-	-	-	-
1,310	2,151.4	<1	4.5	-	-	-	200,000
1,311	2,152.6	<1	6.3	-	-	-	-
1,312	2,161.0	<1	5.4	-	-	-	194,000
1,313	2,165.0	<1	.4	-	-	-	200,000
1,314	2,165.6	.5	1.7	-	-	-	159,000
1,315	2,166.0	<1	1.5	-	-	-	-
1,316	2,166.4	<1	1.5	-	-	-	-
1,317	2,167.0	<1	2.1	-	-	-	-
1,318	2,167.4	<1	1.6	-	-	-	-
1,319	2,168.0	<1	1.9	-	-	-	-
1,320	2,168.5	<1	.6	-	-	-	146,000
1,321	2,169.0	.2	3.2	-	-	-	-
1,322	2,169.6	.3	3.5	8.8	17.1	23	-
1,323	2,170.2	.2	5.4	4.3	27.8	18	-
1,324	2,170.9	.2	6.3	1.8	16.9	9	-
1,325	2,171.5	.1	6.1	4.0	31.8	19	13,000
1,326	2,172.0	.5	8.1	-	-	-	-
1,327	2,172.5	.3	5.7	-	-	-	-
1,328	2,173.0	.3	5.3	-	-	-	-
1,329	2,174.0	.2	5.3	21.4	12.8	90	317,000
1,330	2,175.0	<1	4.0	4.9	75.1	-	-
1,331	2,175.5	<1	2.6	-	-	-	-
1,332	2,177.0	.5	2.4	-	-	-	-
1,333	2,177.8	<1	1.8	-	-	-	116,000
1,334	2,178.2	.1	11.6	-	-	-	-
1,335	2,179.0	.8	11.6	5.7	63.5	52	-
1,336	2,179.4	1.7	11.9	.1	52.0	1	-
1,337	2,180.0	<1	3.5	-	-	-	-
1,338	2,180.5	.6	12.7	-	-	-	178,000
1,339	2,181.0	<1	2.9	-	-	-	-
1,340	2,182.0	.1	12.4	3.5	70.1	35	-
1,341	2,182.5	.4	14.8	-	-	-	-
1,342	2,183.0	.2	11.9	-	-	-	-
1,343	2,184.0	<1	7.8	-	-	-	176,000
1,344	2,185.0	.1	13.3	2.1	73.9	22	-
1,345	2,186.0	.1	11.5	2.1	85.2	20	-
1,346	2,187.0	<1	2.6	-	-	-	188,000
1,347	2,188.0	<1	2.6	-	-	-	-
1,348	2,189.0	.2	13.5	3.1	69.9	34	-
1,349	2,190.0	<1	12.0	3.2	77.0	31	190,000
1,350	2,191.0	.4	14.3	14.3	56.7	160	-
1,351	2,192.0	<1	5.2	4.6	80.7	19	-
1,352	2,193.0	.5	16.5	9.6	61.3	124	200,000
1,353	2,194.0	1.0	16.5	11.0	61.5	142	-
1,354	2,195.0	.6	16.5	8.7	61.4	113	-
1,355	2,196.0	1.2	15.4	8.6	67.2	104	188,000
1,356	2,197.0	1.1	15.5	8.8	67.9	106	-
1,357	2,198.0	1.0	15.6	9.4	64.8	115	-
1,358	2,199.0	.5	15.2	9.2	68.5	109	184,000
1,359	2,200.0	.8	16.4	8.9	61.9	115	-
1,360	2,201.0	1.1	15.0	10.3	63.9	120	-
1,361	2,201.7	1.8	15.5	8.0	64.6	97	183,000
1,362	2,209.0	.1	13.1	-	-	-	-
1,363	2,212.0	.1	10.2	-	-	-	-
Average	-	.4	9.3	7.1	58.1	70	159,000

No test run.

APPENDIX B.--RECOMMENDED ANALYSES FOR PRESSURE-VOLUME-TEMPERATURE SAMPLES
AT PRESSURES BELOW ORIGINAL RESERVOIR PRESSURE

The following tests are considered necessary for maximum use of pressure-volume-temperature (PVT) data in reservoir calculations:

(If the PVT sample is saturated, record test data relative to oil at reservoir temperature and pressure at sampling time; if not saturated, relate the data to oil at saturation pressure and reservoir temperature.)

1. Differential liberation at reservoir temperature at different pressures, including liberated gas, gas specific gravity and compressibility, and oil shrinkage factors.
2. Flash separation of sample oil in 0, 25, 50, and 100 psig separators, recording separator GOR, oil shrinkage, and oil API gravity.
3. Pressure-volume relationship at reservoir temperature, including thermal expansion.
4. Oil viscosity at various pressures, and oil compressibility over several pressure ranges.

The foregoing PVT analysis data can then be adjusted to original reservoir conditions for use in reservoir calculations (1).

APPENDIX C. ---PRESSURE-VOLUME-TEMPERATURE ANALYSIS ADJUSTMENT PROCEDURE

Given a PVT analysis taken at a pressure lower than initial conditions, the procedure and equations outlined below (1) can be used to adjust the PVT data to original reservoir conditions.

- Given
- P_i = estimated original reservoir pressure = 700 psig,
 - P_s = reservoir pressure at PVT sampling time = 468 psig,
 - P = some lower pressure = 400 psig,
 - T_r = reservoir temperature = 74° F,
 - G_{1s} = differentially liberated gas from P_s to P
= 25 scf per bbl of saturated oil at P_s , T_r ,
 - G_1 = adjusted gas value, scf per bbl of saturated oil at P_i , T_r ,
 - B_o/B_{os} = differential shrinkage factor, bbl saturated oil at P per bbl saturated oil at P_s , T_r ,
 - B_o/B_{oi} = adjusted differential shrinkage factor, bbl saturated oil at P per bbl saturated oil at P_i , T_r ,
 - B_o = adjusted formation volume factor, bbl saturated oil at P per bbl stock-tank oil,
 - SF = adjusted flash shrinkage factor, stb oil per bbl initial reservoir oil,
 - CGV = corrective gas volume, cu ft gas per bbl oil at P_s , T_r ,
 - COV = corrective oil volume, bbl oil at P_i , T_r per bbl oil at P_s , T_r .

Find

$$\begin{aligned}
 CGV &= \frac{P_i - P}{P_s - P} (G_{1s}) & (1) \\
 &= \frac{700 - 468}{468 - 400} (25) \\
 &= 85 \text{ scf,}
 \end{aligned}$$

$$\begin{aligned}
 \text{COV} &= 1 + \left[\left(\frac{P_1 - P_s}{P_s - P} \right) \left[(B_o/B_{os} \text{ at } P_s) - (B_o/B_{os} \text{ at } P) \right] \right] \quad (2) \\
 &= 1 + \left[\left(\frac{700 - 468}{468 - 400} \right) [1.0000 - 0.9920] \right] \\
 &= 1.027 \text{ bbl at } p_1, T_r / \text{bbl at } p_s, T_r,
 \end{aligned}$$

$$G_1 = \frac{G_{1s} + \text{COV}}{\text{COV}}, \quad (3)$$

$$B_o/B_{oi} = \frac{B_o/B_{os}}{\text{COV}}, \quad (4)$$

$$B_o = \frac{B_o/B_{oi}}{SF} \quad (5)$$

This adjustment procedure is applied to Kaufman well P-7 in table C-1.

TABLE C-1. - Original and adjusted pressure-volume-temperature analyses data, Kaufman well P-7

Reservoir pressure, psig ¹	G _{1s} ¹	G ₁ ²	B _o /B _{os} ¹	B _o /B _{oi} ²	B _o ²
700.....	-	0	-	1.000	1.264
468.....	4	87	1.0000	.974	1.231
450.....	10	92	.9976	.971	1.228
400.....	29	111	.9920	.966	1.221
300.....	68	149	.9752	.950	1.201
200.....	112	192	.9556	.930	1.176
100.....	166	244	.9306	.906	1.145
0.....	340	414	.8193	.798	1.009

¹Original PVT analysis data.

²Adjusted values.

Section 9

Operating Requirements

Section No. 9

The current operating conditions of this disposal well are:

Average daily volume – 2 bbl.

Maximum daily rate- 50 bbl.

Average daily injection pressure 380 psig

Maximum injection pressure – 1000 psig

2. The attached Appendix G lists the wells served by this disposal well
3. The injection fluid was sampled and analyzed for the required constituents. A copy of the analysis is enclosed in Fig No. 10.
4. Currently no additives are utilized in the injection fluid.
5. The tubing / casing annulus is filled with fresh water and packer fluid (corrosion inhibitor (1 gal /1000 gal fresh water)). The MSDS for Baker CRW 1321 (packer fluid) is attached in Fig No. 11.
6. In the event of the discovery of a well failure the injection well will immediately be shut in. The surface casing in this injection well is set at 174' and cemented to surface. The depth of this casing is well below any USDW in the area. If there is a failure in the injection string (tubing) there will still be three levels of protection between the injection fluid and any USDW. These three layers are the 4 ½" casing, 8 5/8" casing, and the cement outside of the 8 5/8" casing. The tubing / casing annulus is shut in with approximately 25 psig held. The well tender checks this pressure when he visits the well. Any failure will be quickly noticed and the well shut in. In the event of a mechanical integrity failure that cannot be repaired immediately the produced water will either be disposed of in a commercial disposal well or the producing wells shut in until the well can be repaired.

Area Permit Wells

Make as many copies as necessary and include page numbers as appropriate.

	Appendix G		
	Wells Serviced by Injection Wells		
API #	Operator	Well No.	Producing Formation
47-087-03022	Delta Helix Energy, LLC	1	Big Injun
47-087-01955	Delta Helix Energy, LLC	6	Big Injun
47-087-04492	Delta Helix Energy, LLC	601	Big Injun
47-087-02435	Delta Helix Energy, LLC	4	Devonian Shale
47-087-03050	Delta Helix Energy, LLC	1	Big Injun
47-087-02436	Delta Helix Energy, LLC	5	Big Injun
47-087-02994	Delta Helix Energy, LLC	6	Big Injun
47-087-03032	Delta Helix Energy, LLC	7	Big Injun
47-087-03247	Delta Helix Energy, LLC	8	Big Injun
47-087-03035	Delta Helix Energy, LLC	10	Big Injun
47-087-03033	Delta Helix Energy, LLC	11	Big Injun
47-087-02993	Delta Helix Energy, LLC	15	Big Injun
47-087-02438	Delta Helix Energy, LLC	17	Big Injun
47-087-02439	Delta Helix Energy, LLC	18	Big Injun
47-087-00913	Delta Helix Energy, LLC	21	Big Injun
47-087-01076	Delta Helix Energy, LLC	23	Big Injun
47-087-03076	Delta Helix Energy, LLC	2	Big Injun
47-087-02980	Delta Helix Energy, LLC	3	Big Injun
47-087-03075	Delta Helix Energy, LLC	4	Big Injun
47-087-02995	Delta Helix Energy, LLC	14	Big Injun
47-087-01872	Delta Helix Energy, LLC	16	Big Injun
47-087-01927	Delta Helix Energy, LLC	17	Big Injun
47-087-01962	Delta Helix Energy, LLC	18	Big Injun
47-087-01953	Delta Helix Energy, LLC	19	Big Injun
47-087-00970	Delta Helix Energy, LLC	W-2	Big Injun
47-087-00971	Delta Helix Energy, LLC	W-3	Big Injun
47-087-00978	Delta Helix Energy, LLC	W-4	Big Injun
47-087-00984	Delta Helix Energy, LLC	W-5	Big Injun
47-087-00987	Delta Helix Energy, LLC	W-6	Big Injun
47-087-00988	Delta Helix Energy, LLC	W-8	Big Injun
47-087-00992	Delta Helix Energy, LLC	W-10	Big Injun
47-087-00993	Delta Helix Energy, LLC	W-11	Big Injun
47-087-00994	Delta Helix Energy, LLC	W-12	Big Injun
47-087-00995	Delta Helix Energy, LLC	W-13	Big Injun
47-087-00996	Delta Helix Energy, LLC	W-14	Big Injun
47-087-01004	Delta Helix Energy, LLC	W-15	Big Injun
47-087-01032	Delta Helix Energy, LLC	W-16	Big Injun
47-087-01053	Delta Helix Energy, LLC	W-17	Big Injun
47-087-01055	Delta Helix Energy, LLC	W-18	Big Injun
47-087-01068	Delta Helix Energy, LLC	W-20	Big Injun

	Appendix G		
	Wells Serviced by Injection Wells		
API #	Operator	Well No.	Producing Formation
47-087-01079	Delta Helix Energy, LLC	W-21	Big Injun
47-087-02981	Delta Helix Energy, LLC	4	Big Injun
47-087-00894	Delta Helix Energy, LLC	5	Big Injun
47-087-00909	Delta Helix Energy, LLC	6	Big Injun
47-087-00963	Delta Helix Energy, LLC	7	Big Injun
47-087-01923	Delta Helix Energy, LLC	29	Big Injun
47-087-04489	Delta Helix Energy, LLC	604	Big Injun
47-087-04490	Delta Helix Energy, LLC	605	Big Injun
47-087-04491	Delta Helix Energy, LLC	606	Big Injun
47-087-02578	Delta Helix Energy, LLC	3	Devonian Shale
47-087-03040	Delta Helix Energy, LLC	1	Big Injun
47-087-00027	Delta Helix Energy, LLC	2	Big Injun
47-087-03041	Delta Helix Energy, LLC	3	Big Injun
47-087-01026	Delta Helix Energy, LLC	5	Big Injun
47-087-01095	Delta Helix Energy, LLC	6	Big Injun
47-087-01096	Delta Helix Energy, LLC	7	Big Injun
47-087-04493	Delta Helix Energy, LLC	602	Big Injun
47-087-00565	Delta Helix Energy, LLC	2	Big Injun
47-087-02743	Delta Helix Energy, LLC	3	Big Injun
47-087-03061	Delta Helix Energy, LLC	6	Big Injun
47-087-03030	Delta Helix Energy, LLC	10	Big Injun
47-087-03047	Delta Helix Energy, LLC	11	Big Injun
47-087-02988	Delta Helix Energy, LLC	12	Big Injun
47-087-03013	Delta Helix Energy, LLC	13	Big Injun
47-087-03053	Delta Helix Energy, LLC	14	Big Injun
47-087-03048	Delta Helix Energy, LLC	15	Big Injun
47-087-03045	Delta Helix Energy, LLC	17	Big Injun
47-087-03029	Delta Helix Energy, LLC	19	Big Injun
47-087-03031	Delta Helix Energy, LLC	23	Big Injun
47-087-02986	Delta Helix Energy, LLC	24	Big Injun
47-087-00889	Delta Helix Energy, LLC	26	Big Injun
47-087-01027	Delta Helix Energy, LLC	27	Big Injun
47-087-01072	Delta Helix Energy, LLC	28	Big Injun
47-087-01086	Delta Helix Energy, LLC	29	Big Injun
47-087-01873	Delta Helix Energy, LLC	31	Big Injun
47-087-01954	Delta Helix Energy, LLC	32	Big Injun
47-087-02082	Delta Helix Energy, LLC	33	Big Injun

4708700985

Kaufman W-7 & W-19 Injection / Production Facility Quarterly Inspection

To be performed first day of each calendar quarter

Date 10-23-24

Person performing inspection Dakota C.

Produced water tanks

Gas vents ✓

Gas Blanket supply, regulator, piping N/A

Produced water Injection Pump

Suction/discharge piping ✓

Bypass Regulator & line ✓

Water meter ✓

Pressure recorder ✓

Separator

Vessel ✓

Piping ✓

Dump Valves ✓

Regulator ✓

Oil Storage tanks

Tanks ✓

Piping ✓

Items needing attention:

Copies to Forman and Parkersburg office

STEP RATE TEST

1987

Step Rate Test 1987 (for W-7 and W-19)

RECEIVED
JAN 04 1988

DIVISION OF OIL & GAS
DEPARTMENT OF ENERGY

UIC PERMIT UIC2DO870985

WELLHEAD PRESSURE INCREASE JUSTIFICATION

W. M. KAUFMAN NO. W-7

CLOVER FIELD - BIG INJUN RESERVOIR

PENNZOIL PRODUCTS COMPANY

EXPLORATION & PRODUCTION DIVISION

NOEL W. PUTSCHER

DECEMBER 29, 1987

INTRODUCTION

The purpose of this report is to provide test data to the West Virginia Department of Energy, Division of Oil & Gas, which justifies increasing wellhead injection pressure on Roane 0985 from 694 psig to 1000 psig. The West Virginia Department of Energy recently issued an Underground Injection Control permit for Roane 0985 which limited surface pressure to 694 psig. Pennzoil Products Company, operator of subject well, performed a step-rate test to determine the pressure at which the Big Injun would part in the subject well.

DISCUSSION

A step-rate injectivity test is normally used to estimate fracture pressure in an injection well.¹ Fluid is injected at a series of increasing rates, with each rate preferably lasting the same length of time. In relatively low permeability formations ($k < 5$ md) each injection rate should last about 1 hour; 30 minute injection times are adequate for formations with permeability exceeding 10 md. As few as four rates may be used, but normally six, seven or eight rates are preferred. The analysis consists of plotting injection pressure at the end of each rate vs injection rate. It is preferable to plot bottom-hole pressure, but surface pressure may be used if it is positive throughout the test and friction effects are not significant. The plot should have two straight line segments. The break in the line indicates formation fracture pressure.

TEST RESULTS

On December 16, 1987, a step-rate test was run on Roane 0985. The initial pressure was 545 psi and was increased to 1160 psig, with five points in between. With each rate increase the pressure was read after at least one hour had passed. The results of this test are attached and the parting pressure was found to be 1104 psig. Pennzoil is requesting permission to inject into subject well at a wellhead pressure of 1000 psig.

1 Robert C. Earlougher, Jr., Advances in Well Test Analysis Monograph Series, Society of Petroleum Engineers of AIME, Dallas (1977), Vol. 5, Chapter 7.

STEP RATE TEST
W. M. Kaufman W-7
Clover Field
12/16/87


<u>WHP Press.</u> <u>(psig)</u>	<u>Rate (BPD)</u>
545	49
625	51
840	89
975	114
1040	126
1120	176
1160	269

Step Rate Test
W. M. Kaufman W-7
Clover Field
12/16/87

NWP

46 0700
Wellhead Press. (psig)

10 X 10 TO THE INCH • 7 X 10 INCHES
KEUFFEL & ESSER CO. MADE IN U.S.A.



MIT

4708700985



west virginia department of environmental protection

Office of Oil and Gas
601 57th Street
Charleston, WV 25304
(304) 926-0450
fax: (304) 926-0452

Austin Caperton, Cabinet Secretary
www.dep.wv.gov

By Email Transmission

October 5, 2023

HG Energy LLC
Attn: Roger Heldman
5260 Dupont Road
Parkersburg WV 26101

**Re: Mechanical Integrity Test Approvals and Authorization for Injection
UIC Permit 2D08700985 (Wm Kaufman W-7)**

Roger:

Attached is the approved WR-37 Mechanical Integrity Test Record (MITs) for the above referenced disposal well. The permitted injection pressure for this well is 883 psi. The permitted test pressure is 1325 psi (883 x 1.5). This MIT was performed at a test pressure of 1160 psi. The well is approved for a revised injection pressure of 773 psi (1160 / 1.5) and must be retested at 1325 psi to regain the full permitted injection pressure of 883 psi. If you have any questions, please contact Andrew Lockwood via email at Andrew.L.Lockwood@wv.gov or by phone at (304) 926-0499 ext. 41104.

Respectfully,

A handwritten signature in blue ink, appearing to read 'Charles T. Brewer', is written above the printed name.

Charles T. Brewer
Assistant Chief of Permitting
WVDEP Office of Oil & Gas

4708700985

WR-37
12/23/19

**WV DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS
PRE-OPERATION CERTIFICATE FOR LIQUID INJECTION
MECHANICAL INTEGRITY TEST RECORD**

MIT Date: 8/21/23

Operator's Well Name / #: Wm Kaufman W-7

API#: 47-087 - 00985002

UIC Permit #: 2D0487

Field Name (2R only):

RECEIVED
Office Of Oil and Gas

AUG 23 2023

WELL OPERATOR HG Energy LLC

Address: 5260 Dupont Rd
Parkersburg, WV 26101

DESIGNATED AGENT Diane White

Address: 5260 Dupont Rd
Parkersburg, WV 26101WV Department of
Environmental Protection

INJECTION FORMATION Big Injun Depth 2141 feet (top) to 2170 feet (bottom)
Perforation Interval 2163-2166 or Open Hole Interval

INJECTION PERMIT TYPE

☐ 2D Commercial Disposal ☒ 2D Non-Commercial Disposal ☐ 2R Area Permit (EOR) ☐ 3S Solution Mining

INJECTATE TYPE (Check all that apply):

☒ Produced Water ☐ Fresh Water ☐ Completion Flowback Water ☐ Tank & Pipeline Residuals

☐ Drilling Waste Liquids ☐ Solution Mining Waste ☐ Gas (2R) ☐ Other (Specify)

Additives (ie. biocides, inhibitors, etc.) Bactericides and other chemicals as necessary to maintain water quality

WELL CONSTRUCTION / CASING PROGRAM

CASING OR TUBING TYPE	SIZE	GRADE	WEIGHT PER FT.	NEW	USED	FOOTAGE USED IN DRILLING	FOOTAGE LEFT IN WELL	CEMENT USED
CONDUCTOR								
FRESH WATER	8 5/8	LS	28	X		172	172	25 sks
COAL								
INTERMEDIATE								
PRODUCTION	4 1/2	K-55	9.5	X		2219	2219	65 cu ft
TUBING	2 3/8	J-55	4.6	X		2170	2170	
LINERS								

PACKER	TYPE: tension	SIZE: 4x2	DEPTH: 2170
--------	---------------	-----------	-------------

MECHANICAL INTEGRITY TEST TYPE☒ Standard Annulus Pressure TestIs Test Annulus Filled? ☒ Yes ☐ No If Yes, Specify Fluid Type? fresh water and packer fluid☐ Pump Line Test ☐ Other (Specify)

MAXIMUM PERMITTED WELLHEAD INJECTION PRESSURE 1000 psi MIT PRESSURE 1100 psi

MECHANICAL INTEGRITY TEST DESCRIPTION

Pressure tested tubing / casing annulus to 1160 psig for 32 minutes. Chart attached

(2R Area Permits: If multiple pump lines are tested together, please list wells serviced by the tested pump lines.)

WR-37
12/23/19

API#: 47-087 - 00985002

NOTE:

- If the well and the pump line are tested together the MIT pressure must be 1.5 times the maximum permitted injection pressure held for a minimum of 20 minutes with no more than a 5% loss.
- If the well is tested separately, the MIT pressure must be 1.5 times the maximum permitted injection pressure held for a minimum of 20 minutes with no more than a 5% loss.
- If the pump line is tested separately, the MIT pressure shall be the maximum permitted injection pressure plus 100 psi held for a minimum of 20 minutes with no more than a 5% loss. Multiple pump lines can be tested together.
- All MITs must be witnessed by a state inspector. A valid recording chart containing the inspector's signature must accompany this completed form.
- All MITs that fail must be submitted using this form and chart.
- Submit all MIT required documentation to OOG within 30 days of test.
- The mechanical integrity of this well must be demonstrated at least 5 years from this test date and each time work is completed on the well or pump line to continue injection.

The undersigned certify:

The MIT was performed on 8/21/23

The well and/or pump line:

☒ demonstrated mechanical integrity or ☐ failed to demonstrate mechanical integrity.The MIT was witnessed by Joe Taylor, Inspector WVDEP - Office of Oil and Gas.H G Energy LLC

Permit Holder Company Name

8/22/23

Date

Roger Heldman

Agent of Responsible Party (Print Name)


SignatureOperations Manager

Title

-----Office of Oil and Gas Use Only:-----

THIS WELL IS AUTHORIZED FOR INJECTION

UP TO A MAXIMUM WELLHEAD INJECTION PRESSURE OF 580 psi


Special Conditions:

773Permitted injection pressure is 883 psi. Permitted test pressure is 1325 psi (883 x 1.5).This MIT was performed at 1160 psi. This well is approved for a revised injection pressure of 773 psi (1160 / 1.5) and must be retested at 1325 psi to regain full injection pressure of 883 psi.
UIC Program Manager
WVDEP-Office of Oil and Gas

Date

10/5/22

4708700985



4708700985

FIGURE # 10

W M Kaufman W-7 (2D0870095) & W M Kaufman W-19 (2D08701056)
Injection fluid

INJECTATE ANALYSES


Paramater	units	
Chloride	mg/L	125,000
Bromide	mg/L	1,030
Strontium	mg/L	515
Barium	mg/L	174
Iron	mg/L	45.3
Total Dissolved Solids	mg/L	202,000
pH	SI Units	5.62
Specific Gravity		1.132
Manganese	mg/L	1.8
Aluminum	mg/L	0.29
Arsenic	mg/L	0.20
Sodium	mg/L	46,100
Calcium	mg/L	15,300
Sulfate	mg/L	5,000
Radium 226	pCi/L	2.54
Radium 228	pCi/L	11
Gross Alpha	pCi/L	1,685
Gross Beta	pCi/L	1,067

Delta Helix

TABLE 1B. Chemical water quality for station (KPW) associated with ~~HSE~~ Energy's Kaufman Water. Kirk Environmental, LLP., October 31, 2024.

PARAMETER	SAMPLING STATION KAUFMAN WATER (KPW)
Field Water Temperature (°C)	18.5
Field Dissolved Oxygen (mg/L)	2.44
Field pH (SI Units)	5.62
Field Conductivity (mS)	> 150
DRO (C10-C28)	6.4
ORO (C20-C40)	< 4.0
TPH (C06-C10)	1420
Aluminum (mg/L)	0.29
Arsenic (mg/L)	< 0.20
Barium (mg/L)	174
Calcium (mg/L)	15300
Total Iron (mg/L)	45.3
Manganese (mg/L)	1.8
Sodium (mg/L)	46100
Strontium (mg/L)	515
Benzene (ug/L)	157
Toluene (ug/L)	79.9
Ethylbenzene (ug/L)	3.3
Xylene Total (ug/L)	53.6
TDS (mg/L)	202000
TSS (mg/L)	90.0
Chloride (mg/L)	125000
Bromide (mg/L)	1030
Sulfate (mg/L)	< 5000
TOC (mg/L)	66.7
Gross Alpha (pCi/L)	1,685
Gross Beta (pCi/L)	1,067
Radium-226 (pCi/L)	2.54
Radium-228 (pCi/L)	11.0
56	1.132

Kaufman W-7 & W19 Injectate



GEOCHEMICAL TESTING

Environmental and Energy Analysis

2005 N. Center Ave.
Somerset, PA 15501

814/443-1671
814/445-6666
FAX: 814/445-6729

Thursday, November 7, 2024

Beth Johnson
REIC A DIVISION OF PACE ANALYTICAL
SERVICES LLC
PO BOX 286
225 INDUSTRIAL PARK ROA
BEAVER, WV 25813

Order No.: G2411144

Dear Beth Johnson:

Geochemical Testing received 1 sample(s) on 11/5/2024 for the analyses presented in the following report.

There were no problems with sample receipt protocols and analyses met the TNI/NELAC, EPA, and laboratory specifications except where noted in the Case Narrative or Laboratory Results.

If you have any questions regarding these tests results, please feel free to call.

Sincerely,

Joelle Streczywilk
Environmental Laboratory Manager

Leslie A. Nemeth
Project Manager



Glossary (continued)

- 1 Spike recovery limits are not applicable when the sample concentration exceeds the spike concentration by a factor of four or greater.
- B1 Dilution water blank exceeded method criterion.
- C1 CCV recovery above the acceptance limits. Results may be biased high.
- C2 CCV recovery below the acceptance limits. Results may be biased low.
- C3 ICV recovery above the acceptance limits. Results may be biased high.
- C4 ICV recovery below the acceptance limits. Results may be biased low.
- C5 Positive values verified by second column confirmation.
- C6 Confirmation analysis by another detector or chromatographic column was not performed.
- D1 The analysis did not meet the minimum DO depletion of at least 2 mg/L.
- D2 The analysis did not meet the minimum residual DO of at least 1 mg/L.
- D3 Sample required dilution due to a matrix interference.
- D4 Sample was diluted in the extraction steps due to marked matrix interferences.
- D5 Sample required dilution due to a chloride interference.
- D6 Sample was diluted and the reporting limits were raised to achieve method compliant internal standard recovery.
- D7 Sample was digested at a dilution due to the formation of a post-digestion precipitate.
- 8 Sample was digested at a dilution to achieve method compliant matrix spike recovery.
- D9 Sample was digested at a dilution to meet method compliant digestion criteria.
- E2 Unable to obtain a stable weight within specified limits due to sample matrix. Value is estimated.
- F1 Fecal sample tested positive for residual chlorine.
- H1 Due to under-depletion from the initial dilutions for BOD, the sample was reanalyzed outside the hold time.
- H2 Due to over-depletion from the initial dilutions for BOD, the sample was reanalyzed outside the hold time.
- H3 Sample was re-analyzed outside of hold time due to error during original analysis.
- H4 The Nitrite result used to report Nitrate was analyzed past the 48-hour holding time.
- I1 Internal standard recovery above method acceptance limits. Results are estimated.
- I2 Internal standard recovery was below method acceptance limits. Results are estimated.
- IP One of the instrument performance checks () did not meet the acceptance criteria.
- L1 LCS above the acceptance limits. Result may be biased high.
- L2 LCS below the acceptance limits. Result may be biased low.
- L3 Analyte was spiked into the LCS, but was not recovered.
- M1 Matrix Spike recovery above the acceptance limits.
- M2 Matrix Spike recovery below the acceptance limits.
- 4 The matrix spike failed high for the surrogate.
- M5 The matrix spike failed low for the surrogate.
- M6 The reporting limits were raised due to sample matrix interference.
- M7 Recovery for matrix spike could not be quantified due to matrix interference.
- M8 Analyte was spiked into the MS, but was not recovered.
- M9 Analyte concentration was determined by the method of standard addition (MSA).
- N1 The lab does not hold accreditation from PA-DEP for this parameter by this method.
- N2 PADEP does not accredit labs for this analyte by this method.
- N3 The lab is accredited for this method in West Virginia, but not in PA (its primary accrediting body).
- N4 PADEP does not accredit labs for this analyte by this method in drinking water.
- O1 The flashpoint tester cannot detect below 50 degrees F.
- O2 Result is temperature of the sample when flame observed. No flash observed. Result qualified.
- O3 The reporting limits were raised due to the high concentration of non-target compounds.
- O4 Sample was received with headspace.
- O5 Sample was received in incorrect container and is not compliant with 40CFR136 Table II.
- O6 Insufficient sample volume was received to comply with the method.
- P1 The pH of the sample was >2 and is not compliant with 40CFR136 Table II.
- P2 Sample contained residual chlorine and is not compliant with 40CFR136 Table II.
- P3 The pH of the sample was <10 and is not compliant with 40CFR136 Table II.
- P4 Field preservation does not meet EPA or method recommendations for this analysis.
- P5 Acid preservation may not be appropriate for the analysis of 2-Chloroethylvinyl ether.
- P6 Sample required additional preservative upon receipt.
- P7 The sample was received unpreserved.
- P8 The pH of the sample was < 9 and is not compliant with 40 CFR136 Table II.
- R Relative Percent Difference (RPD) was above the control limit.
- R1 RPD above control limits between matrix spike and MS duplicates.
- R2 RPD above the control limit between duplicates.
- R3 RSD above the control limit between replicates.
- R4 RPD above control limits between Inorganic Carbon check and spike.
- R5 RPD above control limits between control sample and control sample duplicates.
- S2 Surrogate recovery in the blank was below the control limit.
- S3 Surrogate recovery in the blank was above the control limit.
- S4 Surrogate recovery in the LCS is above the control limit.
- S5 Surrogate recovery in the LCS is below the control limit.
- SR Analyte recovery was outside the accepted recovery limits and above the control limit for RPD.
- T3 Target analyte found in trip/field blank.
- TC The MS tune check (tailing factor) did not meet the acceptance criteria.

Geochemical Testing

Date: 07-Nov-24

CLIENT: REIC A DIVISION OF PACE ANALYTIC

Project:

Lab Order: G2411144

CASE NARRATIVE

No problems were encountered during analysis of this workorder, except if noted in this report.

Under West Virginia's Laboratory Certification Program, Geochemical Testing's Laboratory Certificate I.D. is 141.

Glossary:

H - Method Hold Time exceeded and is not compliant with 40CFR136 Table II.

U - The analyte was not detected at or above the listed concentration, which is below the laboratory quantitation limit.

B - Analyte detected in the associated Method Blank

Q1 - See case narrative ND - Not Detected

MCL - Contaminant Limit J - Indicates an estimated value.

Q - Qualifier QL - Quantitation Limit DF - Dilution Factor

S - Surrogate Recovery outside accepted recovery limits

T - Sample received above required temperature and is not compliant with 40CFR136 Table II.

T1 - Sample received above required temperature

MDA - Minimum Detectable Activity.

** - Value exceeds Action Limit

TICs - Tentatively Identified Compounds.

E - Value above quantitation range



4708700985

SG

Laboratory Results

Geochemical Testing

Date: 07-Nov-24

CLIENT:	REIC A DIVISION OF PACE ANALYTIC	Client Sample ID:	30730511003
Lab Order:	G2411144		
Project:		Collection Date:	10/31/2024 10:50:00 AM
Lab ID:	G2411144-001	Sampled By:	Pace
Matrix:	AQUEOUS	Date Received:	11/5/2024 9:50:34 AM

KPW

Analyses	Result	Q	MDL	PQL	Units	DF	Date Prepared	Date Analyzed
SPECIFIC GRAVITY								
Specific Gravity	1.132		0.3000	0.300		1		11/06/24 8:07 AM

Delta Heli

TABLE 1C. Chemical water quality for stations (UKS) and (LKS) associated with ~~HE~~ Energy's
Kaufman Sites. Kirk Environmental, LLP., October 31, 2024.

PARAMETER	SAMPLING STATION	
	UKS	LKS
Field Water Temperature (°C)	13.0	12.8
Field Dissolved Oxygen (mg/L)	6.16	2.24
Field pH (SI Units)	7.32	6.54
Field Conductivity (µS)	632.4	351.5
Stream Flow (ft³/s)	< 1 gpm	0.0
DR0 (C10-C28)	< 0.19	< 0.20
OR0 (C20-C40)	< 0.38	< 0.40
TPH (C06-C10)	< 200	< 200
Aluminum (mg/L)	0.087	< 0.020
Arsenic (mg/L)	< 0.020	< 0.020
Barium (mg/L)	0.19	0.22
Calcium (mg/L)	54.6	28.5
Total Iron (mg/L)	0.13	0.17
Manganese (mg/L)	0.16	0.40
Sodium (mg/L)	20.1	10.3
Strontium (mg/L)	0.35	0.21
Benzene (ug/L)	< 1.0	< 1.0
Toluene (ug/L)	< 1.0	< 1.0
Ethylbenzene (ug/L)	< 1.0	< 1.0
Xylene Total (ug/L)	< 3.0	< 3.0
TDS (mg/L)	247	150
TSS (mg/L)	15.0	15.0
Chloride (mg/L)	13.4	35.7
Bromide (mg/L)	< 0.10	0.13
Sulfate (mg/L)	28.8	10.9
TOC (mg/L)	4.2	4.0

UKS - upper stream sample

LKS - lower stream sample



Sample: KPW

Lab ID: 30730511003

Collected: 10/31/24 10:50

Matrix: Water

Page 2 of 1

Method	Parameters	Results	Units	Report Limit	Analyzed	Qualifiers
EPA 200.7	Arsenic	ND	mg/L	0.20	11/05/24 13:38	
EPA 200.7	Barium	174	mg/L	0.50	11/05/24 13:40	
EPA 200.7	Calcium	15300	mg/L	50.0	11/05/24 13:40	
EPA 200.7	Iron	45.3	mg/L	0.50	11/05/24 13:38	
EPA 200.7	Manganese	1.8	mg/L	0.050	11/05/24 13:38	
EPA 200.7	Sodium	46100	mg/L	500	11/06/24 18:23	
EPA 200.7	Strontium	515	mg/L	10.0	11/06/24 18:23	N2
SM 2540C-2015	Total Dissolved Solids	202000	mg/L	1000	11/01/24 18:20	
SM 2540D-2015	Total Suspended Solids	90.0	mg/L	5.0	11/01/24 11:16	
EPA 300.0, Rev 2.1	Bromide	1030	mg/L	100	11/20/24 22:08	
EPA 300.0, Rev 2.1	Chloride	125000	mg/L	1000	11/20/24 22:08	
EPA 300.0, Rev 2.1	Sulfate	ND	mg/L	5000	11/20/24 22:08	D3
SM 5310B-2014	Total Organic Carbon	66.7	mg/L	1.0	11/05/24 21:44	
	Collected By	EK			11/01/24 10:04	
	Field pH	5.62	Std. Units		11/01/24 10:04	
	Field Temperature, C	18.5	deg C		11/01/24 10:04	
	Field Specific Conductance	>150 ms	umhos/cm		11/01/24 10:04	
	Oxygen, Dissolved	2.44	mg/L		11/01/24 10:04	
EPA 8015C	TPH (C10-C28)	6.4	mg/L	2.0	11/11/24 21:14	
EPA 8015C	TPH (C28-C40)	ND	mg/L	4.0	11/11/24 21:14	CH
EPA 8015C	TPH (C06-C10)	1420	ug/L	200	11/04/24 17:16	
EPA 8260D	Benzene	157	ug/L	1.0	11/04/24 15:48	
EPA 8260D	Ethylbenzene	3.3	ug/L	1.0	11/04/24 15:48	
EPA 8260D	Toluene	79.9	ug/L	1.0	11/04/24 15:48	
EPA 8260D	Xylene (Total)	53.6	ug/L	3.0	11/04/24 15:48	

Sample: UKS		Lab ID: 30730511004	Collected: 10/31/24 11:20	Matrix: Water		
Method	Parameters	Results	Units	Report Limit	Analyzed	Qualifiers
EPA 200.7	Aluminum	0.087	mg/L	0.020	11/04/24 17:14	
EPA 200.7	Arsenic	ND	mg/L	0.020	11/04/24 17:14	
EPA 200.7	Barium	0.19	mg/L	0.0050	11/04/24 17:14	
EPA 200.7	Calcium	54.6	mg/L	0.50	11/04/24 17:14	
EPA 200.7	Iron	0.13	mg/L	0.050	11/04/24 17:14	
EPA 200.7	Manganese	0.16	mg/L	0.0050	11/04/24 17:14	
EPA 200.7	Sodium	20.1	mg/L	0.50	11/04/24 17:14	
EPA 200.7	Strontium	0.35	mg/L	0.010	11/04/24 17:14	N2
SM 2540C-2015	Total Dissolved Solids	247	mg/L	10.0	11/01/24 20:10	
SM 2540D-2015	Total Suspended Solids	15.0	mg/L	2.5	11/01/24 11:16	
EPA 300.0, Rev 2.1	Bromide	ND	mg/L	0.10	11/20/24 22:28	
EPA 300.0, Rev 2.1	Chloride	13.4	mg/L	1.0	11/20/24 22:28	
EPA 300.0, Rev 2.1	Sulfate	28.8	mg/L	5.0	11/20/24 22:28	
SM 5310B-2014	Total Organic Carbon	4.2	mg/L	1.0	11/05/24 22:35	
	Collected By	EK			11/01/24 10:07	
	Field pH	7.32	Std. Units		11/01/24 10:07	
	Field Temperature, C	13.0	deg C		11/01/24 10:07	
	Field Specific Conductance	632.4	umhos/cm		11/01/24 10:07	
	Oxygen, Dissolved	6.16	mg/L		11/01/24 10:07	
	Flow	<1 gpm			11/01/24 10:07	
EPA 8015C	TPH (C10-C28)	ND	mg/L	0.19	11/07/24 04:55	
EPA 8015C	TPH (C28-C40)	ND	mg/L	0.38	11/07/24 04:55	
EPA 8015C	TPH (C06-C10)	ND	ug/L	200	11/04/24 17:52	
EPA 8260D	Benzene	ND	ug/L	1.0	11/04/24 14:57	
EPA 8260D	Ethylbenzene	ND	ug/L	1.0	11/04/24 14:57	
EPA 8260D	Toluene	ND	ug/L	1.0	11/04/24 14:57	
EPA 8260D	Xylene (Total)	ND	ug/L	3.0	11/04/24 14:57	



Sample: LKS		Lab ID: 30730511005	Collected: 10/31/24 12:20		Matrix: Water		
Method	Parameters	Results	Units	Report Limit	Analyzed	Qualifiers	
EPA 200.7	Aluminum	ND	mg/L	0.020	11/04/24 17:16		
EPA 200.7	Arsenic	ND	mg/L	0.020	11/04/24 17:16		
EPA 200.7	Barium	0.22	mg/L	0.0050	11/04/24 17:16		
EPA 200.7	Calcium	28.5	mg/L	0.50	11/04/24 17:16		
EPA 200.7	Iron	0.17	mg/L	0.050	11/04/24 17:16		
EPA 200.7	Manganese	0.40	mg/L	0.0050	11/04/24 17:16		
EPA 200.7	Sodium	10.3	mg/L	0.50	11/04/24 17:16		
EPA 200.7	Strontium	0.21	mg/L	0.010	11/04/24 17:16		
SM 2540C-2015	Total Dissolved Solids	150	mg/L	10.0	11/01/24 20:11		
SM 2540D-2015	Total Suspended Solids	15.0	mg/L	2.5	11/01/24 11:16		
EPA 300.0, Rev 2.1	Bromide	0.13	mg/L	0.10	11/20/24 12:55		
EPA 300.0, Rev 2.1	Chloride	35.7	mg/L	1.0	11/20/24 12:55		
EPA 300.0, Rev 2.1	Sulfate	10.9	mg/L	5.0	11/20/24 12:55		
SM 5310B-2014	Total Organic Carbon	4.0	mg/L	1.0	11/05/24 22:52		
	Collected By	EK			11/01/24 10:08		
	Field pH	6.54	Std. Units		11/01/24 10:08		
	Field Temperature, C	12.8	deg C		11/01/24 10:08		
	Field Specific Conductance	351.5	umhos/cm		11/01/24 10:08		
	Oxygen, Dissolved	2.24	mg/L		11/01/24 10:08		
	Flow	0.0			11/01/24 10:08		
EPA 8015C	TPH (C10-C28)	ND	mg/L	0.20	11/07/24 05:19		
EPA 8015C	TPH (C28-C40)	ND	mg/L	0.40	11/07/24 05:19		
EPA 8015C	TPH (C06-C10)	ND	ug/L	200	11/04/24 18:10		
EPA 8260D	Benzene	ND	ug/L	1.0	11/04/24 15:22		
EPA 8260D	Ethylbenzene	ND	ug/L	1.0	11/04/24 15:22		
EPA 8260D	Toluene	ND	ug/L	1.0	11/04/24 15:22		
EPA 8260D	Xylene (Total)	ND	ug/L	3.0	11/04/24 15:22		

Sample: TRIP BLANK		Lab ID: 30730511006	Collected: 10/31/24 00:00		Matrix: Water		
Method	Parameters	Results	Units	Report Limit	Analyzed	Qualifiers	
EPA 8015C	TPH (C06-C10)	ND	ug/L	200	11/04/24 18:28		
EPA 8260D	Benzene	ND	ug/L	1.0	11/04/24 14:31		
EPA 8260D	Ethylbenzene	ND	ug/L	1.0	11/04/24 14:31		
EPA 8260D	Toluene	ND	ug/L	1.0	11/04/24 14:31		
EPA 8260D	Xylene (Total)	ND	ug/L	3.0	11/04/24 14:31		

Sample: KPWW		Lab ID: 30730511003	Collected: 10/31/24 10:50	Matrix: Water			
PWS:	Site ID:	Sample Type:					
Parameters	Method	Act ± Unc (MDC)	Carr Trac	Units	Analyzed	CAS No.	Qual
Gross Alpha	EPA 900.0	329 ± 886 (1,685)		pCi/L	11/21/24 19:12	12587-46-1	
		C:NA T:NA					
Gross Beta	EPA 900.0	670 ± 606 (1,067)		pCi/L	11/21/24 19:12	12587-47-2	
		C:NA T:NA					
Radium-226	EPA 903.1	490 ± 70.7 (2.54)		pCi/L	11/21/24 15:14	13982-63-3	
		C:NA T:100%					
Radium-228	EPA 904.0	347 ± 65.1 (11.0)		pCi/L	11/18/24 15:11	15262-20-1	
		C:84% T:93%					

SAMPLE QUALIFIERS

Sample: 3441786

[1] Post-analysis pH measurement indicates pH > 2.

Sample: 3441787

[1] Post-analysis pH measurement indicates pH > 2.

ANALYTE QUALIFIERS

CH The continuing calibration for this compound is outside of Pace Analytical acceptance limits. The results may be biased high.

D3 Sample was diluted due to the presence of high levels of non-target analytes or other matrix interference.



ANALYTE QUALIFIERS

- N2 The lab does not hold NELAC/TNI accreditation for this parameter but other accreditations/certifications may apply. A complete list of accreditations/certifications is available upon request.
- S4 Surrogate recovery not evaluated against control limits due to sample dilution.

Reviewed by:

Beth Johnson

Beth Johnson
(800)999-0105
beth.johnson@pacelabs.com

Pace Analytical Services Pennsylvania

1638 Roseytown Rd Suites 2,3&4, Greensburg, PA 15601
ANAB DOD-ELAP Rad Accreditation #: L2417
ANABISO/IEC 17025:2017 Rad Cert#: L24170
Alabama Certification #: 41590
Arizona Certification #: AZ0734
Arkansas Certification
California Certification #: 2950
Colorado Certification #: PA01547
Connecticut Certification #: PH-0694
EPA Region 4 DW Rad
Florida/TNI Certification #: E87683
Georgia Certification #: C040
Guam Certification
Hawaii Certification
Idaho Certification
Illinois Certification
Indiana Certification
Iowa Certification #: 391
Kansas Certification #: E-10358
Kentucky Certification #: KY90133
KY WW Permit #: KY0098221
KY WW Permit #: KY0000221
Louisiana DHH/TNI Certification #: LA010
Louisiana DEQ/TNI Certification #: 04086
Maine Certification #: 2023021
Maryland Certification #: 308
Massachusetts Certification #: M-PA1457
Michigan/PADEP Certification #: 9991

Pace Analytical Services Beaver

225 Industrial Park Road, Beaver, WV 25813
Virginia VELAP 460148
West Virginia DEP 060
West Virginia DHHR 00412CM

Missouri Certification #: 235
Montana Certification #: Cert0082
Nebraska Certification #: NE-OS-29-14
Nevada Certification #: PA014572023-03
New Hampshire/TNI Certification #: 297622
New Jersey/TNI Certification #: PA051
New Mexico Certification #: PA01457
New York/TNI Certification #: 10888
North Carolina Certification #: 42706
North Dakota Certification #: R-190
Ohio EPA Rad Approval: #41249
Oregon/TNI Certification #: PA200002-015
Pennsylvania/TNI Certification #: 65-00282
Puerto Rico Certification #: PA01457
Rhode Island Certification #: 65-00282
South Dakota Certification
Tennessee Certification #: TN02867
Texas/TNI Certification #: T104704188-22-18
Utah/TNI Certification #: PA014572223-14
USDA Soil Permit #: 525-23-67-77263
Vermont Dept. of Health: ID# VT-0282
Virgin Island/PADEP Certification
Virginia/VELAP Certification #: 460198
Washington Certification #: C868
West Virginia DEP Certification #: 143
West Virginia DHHR Certification #: 9964C
Wisconsin Approve List for Rad

North Carolina DEQ 466
Kentucky Wastewater Certification KY90039
Pennsylvania DEP 68-00839

Pace Analytical										CHAIN-OF-CUSTODY Analytical Request Document									
Company: Kirk Environmental										Chain-of-Custody is a LEGAL DOCUMENT - Complete all relevant fields									
Address:										Billing Information:									
Report To: Ed J. Kirk										Email To:									
Copy To: Crystal Briner										Site Collection Info/Address:									
Customer Project Name/Number: Kawarman sites										State: / County/City: / Time Zone Collected: [] PT [] MT [] CT [] ET									
Phone:										Site/Facility ID #:									
Email:										Compliance Monitoring? ☒ Yes ☐ No									
Collected By (print): Ed J. Kirk										DW PWS ID #:									
Collected By (signature): Ed J. Kirk										DW Location Code:									
Turnaround Date Required: normal										Immediately Packed on Ice: ☒ Yes ☐ No									
Sample Disposal: ☒ Same Day ☐ Next Day ☐ 13 Day ☐ 14 Day ☐ 15 Day										Field Filtered (if applicable): ☒ Yes ☐ No									
Dispose as appropriate ☐ Return ☐ Archive: ☐ Hold: ☐										Analysis:									
* Matrix Codes (Insert in Matrix box below): Drinking Water (DW), Ground Water (GW), Wastewater (WW), Product (P), Soil/Solid (SL), Oil (OL), Wipe (WP), Air (AR), Tissue (TS), Bioassay (B), Vapor (V), Other (OT)																			
Customer Sample ID										Res # of Ctns									
Matrix *										Composite End									
Comp / Grab										Date Time									
Collected (or Composite Start)										Date Time									
KRW										10/31/24 1050									
Customer Remarks / Special Conditions / Possible Hazards:																			
DD 2.44 mg/L Temp 18.5°C																			
Cond > 150 ms																			
pH 5.62																			
Relinquished by/Company: (Signature)										Received by/Company: (Signature)									
Relinquished by/Company: (Signature)										Received by/Company: (Signature)									
Relinquished by/Company: (Signature)										Received by/Company: (Signature)									

LAB USE ONLY - Affix Workorder/Login Label Here or List Pace Workorder Number or MUE Login Number Here									
Container Preservative Type **									
Lab Project Manager:									
Preservative Types: (1) nitric acid, (2) sulfuric acid, (3) hydrochloric acid, (4) sodium hydroxide, (5) zinc acetate, (6) methanol, (7) sodium bisulfate, (8) sodium thiosulfate, (9) hexane, (A) ascorbic acid, (B) ammonium sulfate, (C) ammonium hydroxide, (D) TSP, (U) Unpreserved, (O) Other									
Analyses:									
Lab Sample Receipt Checkpoints:									
Custodian Seal: present/absent Y/N NA Custodian Signature: present Y/N NA Bottled/Intact Y/N NA Corrected Volume Y/N NA Samples Resealed on Ice Y/N NA Vol. Wash Bottle Acceptable Y/N NA Vol. Residuals Sealed Y/N NA Samples Unholding Time Y/N NA Residual Chlorine Present Y/N NA On Site Y/N NA Sample pH Acceptable Y/N NA pH Stable Y/N NA Surfactant Present Y/N NA Dead Acetate Strips Y/N NA Lab Sample Comments:									
NON-COMPLIANCE									
HOLDING NOT FILLED									
Lab Sample Temperature Info:									
Temp Blank Received Y/N NA									
Therm ID: 210									
Cooler Temp/Blank Receipt: 14 bc									
Cooler Temp/Receipt Factor: 10 bc									
Cooler Temp/Receipt Temp: 14 bc									
Comments:									
Temp Blank Received Y/N NA									
HCL MeOH TSP Other									
Non-Compliance(s) Page 6 of 27									
YES / NO of:									

WO#: 30730511

PM: BMJ

Due Date: 12/13/24

CLIENT: BV-KIRKENV

LIMS30 Lab Sample Condition Upon Receipt (West Virginia)

Courier: ☐ Fed Ex ☐ UPS ☐ USPS ☒ Client ☐ 3rd Party Courier ☐ Pace ☐ Other

Tracking #:

Custody Seal on Cooler/Box/Containers Present: ☐ yes ☒ no

Seals intact: ☐ yes ☐ no

Thermometer Used

26

Type of Ice: ☒ Wet ☐ Blue ☐ None

Cooler Temperature

Observed Temp

0.4 °C

Correction Factor: 0 °C

Final Temp: 0.4 °C

Thermal Preservation Requirement Met Yes ☒ No ☐

pH paper Lot#

204524

Date and Initials of person examining

contents: 10/31/24 (J-NP)

	Yes	No	N/A	
Chain of Custody Present:	☒	☐	☐	1.
Chain of Custody Filled Out:	☒	☐	☐	2. # of ctns missing on 2 COCs
Chain of Custody Relinquished:	☒	☐	☐	3.
Sampler Name & Signature on COC:	☒	☐	☐	4.
Sample Labels match COC:	☒	☐	☐	5.
-Includes date/time/ID				
Matrix: WT				
Samples Arrived within Hold Time:	☒	☐	☐	6.
Short Hold Time Analysis (<72hr remaining):	☒	☐	☐	7.
Rush Turn Around Time Requested:	☒	☐	☐	8.
Sufficient Volume:	☒	☐	☐	9.
Correct Containers Used:	☒	☐	☐	10.
-Pace Containers Used:	☒	☐	☐	
Containers Intact:	☒	☐	☐	11.
Orthophosphate field filtered:	☒	☐	☐	12.
Hex Cr Aqueous sample field filtered:	☒	☐	☐	13.
-pH adjusted within 24 hours? (If yes, indicate acid lot #)				
Filtered volume received for Dissolved tests:	☒	☐	☐	14.
All containers have been checked for chemical preservation:	☒	☐	☐	15.
exceptions: VOA, coliform, O&G, LLMercury, Non-aqueous matrix				
All containers meet method/chemical preservation requirements:	☒	☐	☐	Initial when completed: ZC Date: 11/1/24
Headspace in VOA Vials:	☒	☐	☐	Tests not preserved:
Trip Blank Present:	☒	☐	☐	16.
				17.
				Initial when completed: ZC Date: 11/1/24

Comments:

*PM review is documented electronically in LIMS, when the Project Manager closes the SRF Review schedule in LIMS. The status may be reviewed in the Status section of the Workorder Edit Screen.

	DC# Title: ENV-FRM-GBUR-0088 v07 Sample Condition Upon Receipt-Greensburg
	Effective Date: 01/04/2024

Client Name: Kirk Env.

Project #: 30703051

Courier: ☐ Fed Ex ☐ UPS ☐ USPS ☐ Client ☐ Commercial ☐ Pace ☒ Other

Nice

Initial / Date

Tracking Number: 00000000

Examined By: UB 11-4-24

Custody Seal on Cooler/Box Present: ☒ Yes ☐ No

Seals Intact: ☒ Yes ☐ No

Thermometer Used: 14

Type of Ice: Net Blue None

Labeled By: UB 11-4-24

Tempered By: UB 11-4-24

Cooler Temperature: Observed Temp 2.9 °C

Correction Factor: -0.5 °C

Final Temp: 2.4 °C

Temp should be above freezing to 6°C

Comments:	Yes	No	NA	pH paper Lot#	D.P.D. Residual Chlorine Lot #
Chain of Custody Present	☒			<u>100001</u>	
Chain of Custody Filled Out:	☒				
-Were client corrections present on COC		☒			
Chain of Custody Relinquished	☒				
Sampler Name & Signature on COC:	☒				
Sample Labels match COC:	☒				
-Includes date/time/ID					
Matrix: <u>WT</u>					
Samples Arrived within Hold Time:	☒				
Short Hold Time Analysis (<72hr remaining):		☒			
Rush Turn Around Time Requested:		☒			
Sufficient Volume:	☒				
Correct Containers Used:	☒				
-Pace Containers Used		☒			
Containers Intact:	☒				
Orthophosphate field filtered:			☒		
Hex Cr Aqueous samples field filtered:			☒		
Organic Samples checked for dichlorination			☒		
Filtered volume received for dissolved tests:			☒		
All containers checked for preservation:	☒				
exceptions: VOA, coliform, TOC, O&G, Phenolics, Radon, non-aqueous matrix					
All containers meet method preservation requirements:	☒			Initial when completed <u>UB</u>	Date/Time of Preservation
				Lot# of added Preservative	
8260C/D: Headspace in VOA Vials (> 6mm)			☒		
624.1: Headspace in VOA Vials (0mm)			☒		
Radon: Headspace in RAD Vials (0mm)			☒		
Trip Blank Present:			☒		
					Trip blank custody seal present? YES or NO
Rad Samples Screened <.05 mrem/hr.	☒			Initial when completed <u>UB</u>	Date: <u>11-4-24</u> Survey Meter SN: <u>2014100</u>
Comments:					

Note: For NC compliance samples with discrepancies, a copy of this form must be sent to the DEHNR Certification office. PM Review is documented electronically in LIMS through the SRF Review schedule in the Workorder Edit Screen.

Qualtrax ID: 55680

Page 1 of 1

Page 12 of 27

WO#: 30730511

PN: BMJ

Due Date: 12/13/24

CLIENT: BV-KIRKENV

LIMS30 Lab Sample Condition Upon Receipt (West Virginia)

Courier: ☐ Fed Ex ☐ UPS ☐ USPS ☒ Client ☐ 3rd Party Courier ☐ Pace ☐ Other _____

Tracking #: _____

Custody Seal on Cooler/Box/Containers Present: ☐ yes ☒ no

Seals intact: ☐ yes ☐ no

Thermometer Used

26

Type of Ice: ☒ Wet ☐ Blue ☐ None

Cooler Temperature

Observed Temp

0.4

°C

Correction Factor: 0

°C

Final Temp: 0.4

°C

Thermal Preservation Requirement Met Yes ☒ No ☐

pH paper Lot#

204524

Date and Initials of person examining

contents: 10/31/24 (J-NP)

	Yes	No	N/A	
Chain of Custody Present:	☒	☐	☐	1.
Chain of Custody Filled Out:	☒	☐	☐	2. # of ctns missing on 2 COCs
Chain of Custody Relinquished:	☒	☐	☐	3.
Sampler Name & Signature on COC:	☒	☐	☐	4.
Sample Labels match COC:	☒	☐	☐	5.
-Includes date/time/ID				
Matrix: WT				
Samples Arrived within Hold Time:	☒	☐	☐	6.
Short Hold Time Analysis (<72hr remaining):	☒	☐	☐	7.
Rush Turn Around Time Requested:	☒	☐	☐	8.
Sufficient Volume:	☒	☐	☐	9.
Correct Containers Used:	☒	☐	☐	10.
-Pace Containers Used:	☒	☐	☐	
Containers Intact:	☒	☐	☐	11.
Orthophosphate field filtered:	☒	☐	☐	12.
Hex Cr Aqueous sample field filtered:	☒	☐	☐	13.
-pH adjusted within 24 hours? (if yes, indicate acid lot #)	☒	☐	☐	
Filtered volume received for Dissolved tests:	☒	☐	☐	14.
All containers have been checked for chemical preservation:	☒	☐	☐	15.
exceptions: VOA, coliform, O&G, LLMercury, Non-aqueous matrix				
All containers meet method/chemical preservation requirements:	☒	☐	☐	Initial when completed: ZC
				Date: 11/1/24
Tests not preserved:				
Headspace in VOA Vials:	☒	☐	☐	16.
Trip Blank Present:	☒	☐	☐	17.
				Initial when completed: ZC
				Date: 11/1/24

Comments:

*PM review is documented electronically in LIMS, when the Project Manager closes the SRF Review schedule in LIMS. The status may be reviewed in the Status section of the Workorder Edit Screen.



Pace Analytical Services, LLC
P.O. Box 907
Madisonville, KY 42431
270.821.7375
www.pacelabs.com

Certificate of Analysis 4113738

Beth Johnson
Pace Analytical Services LLC Beaver
225 Industrial Park Rd
Beaver, WV 25813

Customer ID: 44-102122
Report Printed: 11/20/2024 15:12

Project Name	WV SDWA Beth Johnson	Workorder	4113738
--------------	----------------------	-----------	---------

Dear Beth Johnson

Enclosed are the analytical results for samples received by the laboratory 11/12/2024 10:58.

The results relate to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services LLC Kentucky - Madisonville

If you have any questions concerning this report, please feel free to contact me.



#460210 Madisonville, KY
#460291 Pikeville, KY
#E871136 Englewood, OH

This page is included as part of the Analytical Report and must be retained as a permanent record thereof.

Melissia Brown, Project Coordinator



Pace Analytical Services, LLC
P.O. Box 907
Madisonville, KY 42431
270.821.7375
www.pacelabs.com

SAMPLE SUMMARY

Lab ID	Client Sample ID/Alias	Matrix	Date Collected	Date Received	Sampled By
4113738-01	DBP Sample/30732801001 48 Union Camp Rd	Drinking Water	11/08/2024 10:03	11/12/2024 10:58	Julia Childers
4113738-02	DBP Sample/30732801002 48 Union Camp Rd	Drinking Water	11/08/2024 10:03	11/12/2024 10:58	Julia Childers
4113738-03	DBP Sample/30732801003 292 Koons Run Rd	Drinking Water	11/08/2024 10:53	11/12/2024 10:58	Julia Childers
4113738-04	DBP Sample/30732801004 292 Koons Run Rd	Drinking Water	11/08/2024 10:53	11/12/2024 10:58	Julia Childers
4113738-05	DBP Sample/30732801005 Trip Blank	Drinking Water	11/08/2024 10:03	11/12/2024 10:58	Julia Childers

Work Order Comments:

The individual THM / HAA components are rounded then reported.

The total THM / HAA values are calculated from the sum of actual values for the individual analytes. This value is then rounded. It is possible for the total value not to match the sum of the individual components.

If this data is used for regulatory purposes, the total values will be the actual sum of the individual analytes.



Pace Analytical Services, LLC
P.O. Box 907
Madisonville, KY 42431
270.821.7375
www.pacelabs.com

ANALYTICAL RESULTS

Lab Sample ID: 4113738-01

Description: DBP Sample 30732801001 48 Union Camp Rd

Sample Collection Date Time: 11/08/2024 10:03

Sample Received Date Time: 11/12/2024 10:58

Matrix: Drinking Water

Discharge/Site No:

Regulatory ID: WV3301706

Volatile Organic Compounds Madisonville

Analyte	Result	Flag	Units	MRL	MDL	Method	Prepared	Analyzed	Analyst
Total Trihalomethanes	0.071		mg/L	0.001	0.0005	EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 09:45	CLM
Bromodichloromethane	0.012		mg/L	0.001	0.0005	EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 09:45	CLM
Bromoform	ND	U	mg/L	0.001		EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 09:45	CLM
Chloroform	0.058		mg/L	0.001	0.0005	EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 09:45	CLM
Dibromochloromethane	0.002		mg/L	0.001	0.0005	EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 09:45	CLM

ANALYTICAL RESULTS

Lab Sample ID: 4113738-02

Description: DBP Sample 30732801002 48 Union Camp Rd

Sample Collection Date Time: 11/08/2024 10:03

Sample Received Date Time: 11/12/2024 10:58

Matrix: Drinking Water

Discharge/Site No:

Regulatory ID: WV3301706

Gas Chromatography Madisonville

Analyte	Result	Flag	Units	MRL	MDL	Method	Prepared	Analyzed	Analyst
Bromoacetic Acid	ND	U	mg/L	0.001		EPA 552.3	11/14/2024 08:45	11/14/2024 22:55	CDD
Dibromoacetic Acid	ND	U	mg/L	0.001		EPA 552.3	11/14/2024 08:45	11/14/2024 22:55	CDD
Dichloroacetic Acid	0.006		mg/L	0.001	0.0005	EPA 552.3	11/14/2024 08:45	11/14/2024 22:55	CDD
Monochloroacetic Acid	ND	U	mg/L	0.001		EPA 552.3	11/14/2024 08:45	11/14/2024 22:55	CDD
Trichloroacetic Acid	0.018		mg/L	0.001	0.0005	EPA 552.3	11/14/2024 08:45	11/14/2024 22:55	CDD
Total HAA5	0.024		mg/L	0.001	0.0005	EPA 552.3	11/14/2024 08:45	11/14/2024 22:55	CDD

Surrogate: 2,3-Dibromopropionic acid 107 % 70-130 11/14/2024 08:45 11/14/2024 22:55 CDD EPA 552.3



Pace Analytical Services, LLC
P.O. Box 907
Madisonville, KY 42431
270.821.7375
www.pacelabs.com

ANALYTICAL RESULTS

Lab Sample ID: 4113738-03

Description: DBP Sample 30732801003 292 Koons Run Rd

Sample Collection Date Time: 11/08/2024 10:53

Sample Received Date Time: 11/12/2024 10:58

Matrix: Drinking Water

Discharge/Site No:

Regulatory ID: WV3301706

Volatile Organic Compounds Madisonville

Analyte	Result	Flag	Units	MRL	MDL	Method	Prepared	Analyzed	Analyst
Total Trihalomethanes	0.048		mg/L	0.001	0.0005	EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 10:17	CLM
Bromodichloromethane	0.010		mg/L	0.001	0.0005	EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 10:17	CLM
Bromoform	ND	u	mg/L	0.001		EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 10:17	CLM
Chloroform	0.037		mg/L	0.001	0.0005	EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 10:17	CLM
Dibromochloromethane	0.001		mg/L	0.001	0.0005	EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 10:17	CLM

ANALYTICAL RESULTS

Lab Sample ID: 4113738-04

Description: DBP Sample 30732801004 292 Koons Run Rd

Sample Collection Date Time: 11/08/2024 10:53

Sample Received Date Time: 11/12/2024 10:58

Matrix: Drinking Water

Discharge/Site No:

Regulatory ID: WV3301706

Gas Chromatography Madisonville

Analyte	Result	Flag	Units	MRL	MDL	Method	Prepared	Analyzed	Analyst
Bromoacetic Acid	ND	u	mg/L	0.001		EPA 552.3	11/14/2024 08:45	11/14/2024 23:13	CDD
Dibromoacetic Acid	ND	u	mg/L	0.001		EPA 552.3	11/14/2024 08:45	11/14/2024 23:13	CDD
Dichloroacetic Acid	0.012		mg/L	0.001	0.0005	EPA 552.3	11/14/2024 08:45	11/14/2024 23:13	CDD
Monochloroacetic Acid	ND	u	mg/L	0.001		EPA 552.3	11/14/2024 08:45	11/14/2024 23:13	CDD
Trichloroacetic Acid	0.015		mg/L	0.001	0.0005	EPA 552.3	11/14/2024 08:45	11/14/2024 23:13	CDD
Total HAA5	0.027		mg/L	0.001	0.0005	EPA 552.3	11/14/2024 08:45	11/14/2024 23:13	CDD

Surrogate: 2,3-Dibromopropionic aci 104 % 70-130 11/14/2024 08:45 11/14/2024 23:13 CDD EPA 552.3



Pace Analytical Services, LLC
P.O. Box 907
Madisonville, KY 42431
270.821.7375
www.pacelabs.com

ANALYTICAL RESULTS

Lab Sample ID: 4113738-05
Description: DBP Sample 30732801005 Trip Blank

Sample Collection Date Time: 11/08/2024 10:03
Sample Received Date Time: 11/12/2024 10:58

Matrix: Drinking Water

Discharge/Site No:

Regulatory ID: WV3301706

Volatile Organic Compounds Madisonville

Analyte	Result	Flag	Units	MRL	MDL	Method	Prepared	Analyzed	Analyst
Total Trihalomethanes	ND	U	mg/L	0.001		EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 10:49	CLM
Bromodichloromethane	ND	U	mg/L	0.001		EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 10:49	CLM
Bromoform	ND	U	mg/L	0.001		EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 10:49	CLM
Chloroform	ND	U	mg/L	0.001		EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 10:49	CLM
Dibromochloromethane	ND	U	mg/L	0.001		EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 10:49	CLM

Notes for work order 4113738

- Samples collected by PACE personnel are done so in accordance with procedures set forth in PACE field services SOPs.
- Results contained in this report are only representative of the samples received.
- PACE does not provide interpretation of these results unless otherwise stated.
- All Waste Water analyses comply with methodology requirements of 40 CFR Part 136.
- All Drinking Water analyses comply with methodology requirements of 40 CFR Part 141.
- Unless otherwise noted, all quantitative results for soils are reported on a dry weight basis.
- The Chain of Custody document is included as part of this report.
- All Library Search analytes should be regarded as tentative identification based on the presumptive evidence of the mass spectra.
- Concentrations reported are estimated values.

Qualifiers

- M1 Matrix spike recovery was high; the method control sample recovery was acceptable.
- U Target analyte was analyzed for, but was below detection limit (the value associated with the qualifier is the laboratory method detection limit in our LIMS system).
- Y5 MS/MSD RPD exceeded the method control limit.

Standard Qualifiers/Acronyms

- MDL Method Detection Limit
- MRL Minimum Reporting Limit
- ND Not Detected
- LCS Laboratory Control Sample
- MS Matrix Spike
- MSD Matrix Spike Duplicate
- DUP Sample Duplicate
- % Rec Percent Recovery
- RPD Relative Percent Difference
- > Greater than
- < Less than



Pace Analytical Services, LLC
P.O. Box 907
Madisonville, KY 42431
270.821.7375
www.pacelabs.com

Volatile Organic Compounds Madisonville - Quality Control

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC Limits	RPD Limit	Notes
---------	--------	-----------------	-------	-------------	---------------	-------------	-----------	-------

Batch BDK1449 - VOC - Prep

Blank (BDK1449-BLK1)

Prepared: 11/14/2024 11:15, Analyzed: 11/15/2024 7:38

Total Trihalomethanes	ND	0.001	mg/L					U
Total Trihalomethanes	ND	0.001	mg/L					U
Bromodichloromethane	ND	0.001	mg/L					U
Bromodichloromethane	ND	0.001	mg/L					U
Bromoform	ND	0.001	mg/L					U
Bromoform	ND	0.001	mg/L					U
Chloroform	ND	0.001	mg/L					U
Chloroform	ND	0.001	mg/L					U
Dibromochloromethane	ND	0.001	mg/L					U
Dibromochloromethane	ND	0.001	mg/L					U

Surrogate: Bromofluorobenzene	0.0251		mg/L	0.0250	101	70-130	
Surrogate: Bromofluorobenzene	0.0251		mg/L	0.0250	101	70-130	
Surrogate: Toluene-d8	0.0254		mg/L	0.0250	102	70-130	
Surrogate: Toluene-d8	0.0254		mg/L	0.0250	102	70-130	
Surrogate: 1,2-Dichlorobenzene-d4	0.0254		mg/L	0.0250	102	70-130	
Surrogate: 1,2-Dichlorobenzene-d4	0.0254		mg/L	0.0250	102	70-130	

LCS (BDK1449-BS1)

Prepared: 11/14/2024 11:15, Analyzed: 11/15/2024 7:06

Bromodichloromethane	0.025	0.001	mg/L	0.0250	100	70-130	
Bromodichloromethane	0.025	0.001	mg/L	0.0250	100	70-130	
Bromoform	0.025	0.001	mg/L	0.0250	98.1	70-130	
Bromoform	0.025	0.001	mg/L	0.0250	98.1	70-130	
Chloroform	0.024	0.001	mg/L	0.0250	97.7	70-130	
Chloroform	0.024	0.001	mg/L	0.0250	97.7	70-130	
Dibromochloromethane	0.024	0.001	mg/L	0.0250	96.0	70-130	
Dibromochloromethane	0.024	0.001	mg/L	0.0250	96.0	70-130	

Surrogate: Bromofluorobenzene	0.0255		mg/L	0.0250	102	70-130	
Surrogate: Bromofluorobenzene	0.0255		mg/L	0.0250	102	70-130	
Surrogate: Toluene-d8	0.0256		mg/L	0.0250	102	70-130	
Surrogate: Toluene-d8	0.0256		mg/L	0.0250	102	70-130	
Surrogate: 1,2-Dichlorobenzene-d4	0.0250		mg/L	0.0250	99.8	70-130	
Surrogate: 1,2-Dichlorobenzene-d4	0.0250		mg/L	0.0250	99.8	70-130	



Pace Analytical Services, LLC
P.O. Box 907
Madisonville, KY 42431
270.821.7375
www.pacelabs.com

Volatile Organic Compounds Madisonville - Quality Control

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	-----------------	-------	-------------	---------------	------	-------------	-----	-----------	-------

Batch BDK1449 - VOC - Prep

Matrix Spike (BDK1449-MS1)

Source: 4113747-01

Prepared: 11/14/2024 11:15, Analyzed: 11/15/2024 18:18

Bromodichloromethane	0.032	0.001	mg/L	0.0250	0.006	106	65-135			
Bromodichloromethane	0.032	0.001	mg/L	0.0250	0.006	106	65-135			
Bromoform	0.025	0.001	mg/L	0.0250	ND	98.8	65-135			
Bromoform	0.025	0.001	mg/L	0.0250	ND	98.8	65-135			
Chloroform	0.060	0.001	mg/L	0.0250	0.033	105	65-135			
Chloroform	0.060	0.001	mg/L	0.0250	0.033	105	65-135			
Dibromochloromethane	0.026	0.001	mg/L	0.0250	ND	102	65-135			
Dibromochloromethane	0.026	0.001	mg/L	0.0250	0.0006	99.8	65-135			

Surrogate: Bromofluorobenzene	0.0257		mg/L	0.0250		103	65-135			
Surrogate: Bromofluorobenzene	0.0257		mg/L	0.0250		103	65-135			
Surrogate: Toluene-d8	0.0255		mg/L	0.0250		102	65-135			
Surrogate: Toluene-d8	0.0255		mg/L	0.0250		102	65-135			
Surrogate: 1,2-Dichlorobenzene-d4	0.0254		mg/L	0.0250		102	70-130			
Surrogate: 1,2-Dichlorobenzene-d4	0.0254		mg/L	0.0250		102	70-130			

Matrix Spike Dup (BDK1449-MSD1)

Source: 4113747-01

Prepared: 11/14/2024 11:15, Analyzed: 11/15/2024 18:50

Bromodichloromethane	0.033	0.001	mg/L	0.0250	0.006	109	65-135	2.48	30	
Bromodichloromethane	0.033	0.001	mg/L	0.0250	0.006	109	65-135	2.48	30	
Bromoform	0.024	0.001	mg/L	0.0250	ND	97.8	65-135	1.02	30	
Bromoform	0.024	0.001	mg/L	0.0250	ND	97.8	65-135	1.02	30	
Chloroform	0.061	0.001	mg/L	0.0250	0.033	108	65-135	1.53	30	
Chloroform	0.061	0.001	mg/L	0.0250	0.033	108	65-135	1.53	30	
Dibromochloromethane	0.026	0.001	mg/L	0.0250	ND	104	65-135	1.40	30	
Dibromochloromethane	0.026	0.001	mg/L	0.0250	0.0006	101	65-135	1.40	30	

Surrogate: Bromofluorobenzene	0.0259		mg/L	0.0250		104	65-135			
Surrogate: Bromofluorobenzene	0.0259		mg/L	0.0250		104	65-135			
Surrogate: Toluene-d8	0.0257		mg/L	0.0250		103	65-135			
Surrogate: Toluene-d8	0.0257		mg/L	0.0250		103	65-135			
Surrogate: 1,2-Dichlorobenzene-d4	0.0251		mg/L	0.0250		100	70-130			
Surrogate: 1,2-Dichlorobenzene-d4	0.0251		mg/L	0.0250		100	70-130			



Pace Analytical Services, LLC
P.O. Box 907
Madisonville, KY 42431
270.821.7375
www.pacelabs.com

Gas Chromatography Madisonville - Quality Control


HPLC/MS/MS Method Performance Quality Control										
Analyte	Reporting			Spike Level	Source Result	%REC		RPD	Limit	Notes
	Result	Limit	Units			%REC	Limits			
Batch BDK1272 - 552.3 Extraction HAA										
Blank (BDK1272-BLK1)										
Prepared: 11/14/2024 8:45, Analyzed: 11/14/2024 18:26										
Bromoacetic Acid	ND	0.001	mg/L							U
Dibromoacetic Acid	ND	0.001	mg/L							U
Dichloroacetic Acid	ND	0.001	mg/L							U
Monochloroacetic Acid	ND	0.001	mg/L							U
Trichloroacetic Acid	ND	0.001	mg/L							U
Total HAA5	ND	0.001	mg/L							U
Surrogate: 2,3-Dibromopropionic acid 0.00973 mg/L 0.0100 97.3 70-130										
LCS (BDK1272-BS1)										
Prepared: 11/14/2024 8:45, Analyzed: 11/14/2024 19:02										
Bromoacetic Acid	0.023	0.001	mg/L	0.0250		92.2	70-130			
Dibromoacetic Acid	0.025	0.001	mg/L	0.0250		98.1	70-130			
Dichloroacetic Acid	0.023	0.001	mg/L	0.0250		92.0	70-130			
Monochloroacetic Acid	0.023	0.001	mg/L	0.0250		93.8	70-130			
Trichloroacetic Acid	0.024	0.001	mg/L	0.0250		97.6	70-130			
Total HAA5	0.118	0.001	mg/L	0.125		94.7	70-130			
Surrogate: 2,3-Dibromopropionic acid 0.0100 mg/L 0.0100 100 70-130										
Matrix Spike (BDK1272-MS1) Source: 4113713-01										
Prepared: 11/14/2024 8:45, Analyzed: 11/15/2024 1:53										
Bromoacetic Acid	0.084	0.001	mg/L	0.0250	ND	255	70-130			M1, Y5
Dibromoacetic Acid	0.024	0.001	mg/L	0.0250	ND	96.6	70-130			
Dichloroacetic Acid	0.059	0.001	mg/L	0.0250	0.035	98.9	70-130			
Monochloroacetic Acid	0.029	0.001	mg/L	0.0250	0.001	113	70-130			
Trichloroacetic Acid	0.079	0.001	mg/L	0.0250	0.053	106	70-130			
Total HAA5	0.256	0.001	mg/L	0.125	0.089	134	70-130			M1
Surrogate: 2,3-Dibromopropionic acid 0.00995 mg/L 0.0100 99.5 70-130										
Matrix Spike (BDK1272-MS2) Source: 4113714-01										
Prepared: 11/14/2024 8:45, Analyzed: 11/15/2024 2:29										
Bromoacetic Acid	0.032	0.001	mg/L	0.0250	ND	126	70-130			
Dibromoacetic Acid	0.025	0.001	mg/L	0.0250	ND	98.6	70-130			
Dichloroacetic Acid	0.042	0.001	mg/L	0.0250	0.017	97.5	70-130			
Monochloroacetic Acid	0.030	0.001	mg/L	0.0250	ND	122	70-130			
Trichloroacetic Acid	0.045	0.001	mg/L	0.0250	0.021	98.4	70-130			
Total HAA5	0.174	0.001	mg/L	0.125	0.038	108	70-130			
Surrogate: 2,3-Dibromopropionic acid 0.0103 mg/L 0.0100 103 70-130										



Pace Analytical Services, LLC
P.O. Box 907
Madisonville, KY 42431
270.821.7375
www.pacelabs.com

Gas Chromatography Madisonville - Quality Control

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	Limit	RPD	Limit	Notes
Batch BDK1272 - 552.3 Extraction HAA										
Matrix Spike Dup (BDK1272-MSD1) Source: 4113713-01										
Prepared: 11/14/2024 8:45, Analyzed: 11/15/2024 2:11										
Bromoacetic Acid	0.023	0.001	mg/L	0.0250	ND	93.7	70-130	92.5	30	Y5
Dibromoacetic Acid	0.026	0.001	mg/L	0.0250	ND	104	70-130	7.69	30	
Dichloroacetic Acid	0.061	0.001	mg/L	0.0250	0.035	106	70-130	2.91	30	
Monochloroacetic Acid	0.030	0.001	mg/L	0.0250	0.001	117	70-130	3.14	30	
Trichloroacetic Acid	0.082	0.001	mg/L	0.0250	0.053	118	70-130	3.91	30	
Total HAA5	0.223	0.001	mg/L	0.125	0.089	108	70-130	13.6	30	
Surrogate: 2,3-Dibromopropionic acid	0.0107		mg/L	0.0100		107	70-130			
Matrix Spike Dup (BDK1272-MSD2) Source: 4113714-01										
Prepared: 11/14/2024 8:45, Analyzed: 11/15/2024 2:47										
Bromoacetic Acid	0.033	0.001	mg/L	0.0250	ND	131	70-130	4.07	30	M1
Dibromoacetic Acid	0.025	0.001	mg/L	0.0250	ND	98.5	70-130	0.0406	30	
Dichloroacetic Acid	0.042	0.001	mg/L	0.0250	0.017	99.8	70-130	1.40	30	
Monochloroacetic Acid	0.032	0.001	mg/L	0.0250	ND	127	70-130	4.46	30	
Trichloroacetic Acid	0.045	0.001	mg/L	0.0250	0.021	99.1	70-130	0.398	30	
Total HAA5	0.177	0.001	mg/L	0.125	0.038	111	70-130	1.97	30	
Surrogate: 2,3-Dibromopropionic acid	0.0106		mg/L	0.0100		106	70-130			



Analyte	Certifications
---------	----------------

Page 10 of 14



Pace Analytical Services, LLC
P.O. Box 907
Madisonville, KY 42431
270.821.7375
www.pacelabs.com

Sample Acceptance Checklist for Work Order 4113738	
Shipped By: UPS	Temperature: 2.80° Celcius
Condition	
Check if Custody Seals are Present/Intact	☐
Check if Custody Signatures are Present	☒
Check if Collector Signature Present	☒
Check if bottles are intact	☒
Check if bottles are correct	☒
Check if bottles have sufficient volume	☒
Check if samples received on ice	☒
Check if VOA headspace is acceptable	☒
Check if samples received in holding time.	☒
Check if samples are preserved properly	☒

Internal Transfer Chain of Custody

4113738

Pace



Workorder: 30732801 Workorder Name: WV3301706 State Of Origin: WV Rush Multiplier: ☒ X Samples Pre-Logged into eCOC: ☐ Cert. Needed: ☒ Yes ☐ No Owner Received Date: 11/8/2024 Results Requested By: 11/25/2024

Report To: Beth Johnson
Pace Analytical Madisonville
825 Industrial Rd
Madisonville, KY 42431
Phone (270)824-2211

Item	Sample ID	Sample Type	Collect Date/Time	Lab ID	Matrix	Preserved Containers			Trip Blank	WV DW HAAS	WV DW THM	LAB USE ONLY			
						Other	Mec					S2THM1	S2HAA1	S2THM2	S2HAA2
1	48 UNION CAMP RD	PS	11/8/2024 10:03	30732801001	Drinking		3				X				
2	48 UNION CAMP RD	PS	11/8/2024 10:03	30732801002	Drinking	3				X					
3	292 KOONS RUN RD	PS	11/8/2024 10:53	30732801003	Drinking		3			X					
4	292 KOONS RUN RD	PS	11/8/2024 10:53	30732801004	Drinking	3				X					
5	TRIP BLANK	PS	11/8/2024 00:00	30732801005	Water		1		X						

Transfers	Released By	Date/Time	Received By	Date/Time	Comments
1	f 11-11-24	11/8/24	[Signature]	11-12-24	WV3301706
2				1058	RT DS001 EM
3					

Cooler Temperature on Receipt °C Custody Seal Y or N Received on Ice Y or N Samples Intact Y or N

***In order to maintain client confidentiality, location/name of the sampling site, sampler's name and signature may not be provided on this COC document.

Thermometer Serial Number
230753815
240381205
Temperatures 8°C



Ship To:
Pace Analytical Madisonville
825 Industrial Rd
Madisonville, KY 42431
Phone (270)824-2211

INTER_LABORATORY WORK ORDER # 30732801

(To be completed by sending lab)

Sending Project No	30732801
Receiving Project No	
Check Box for Consolidated Invoice	☐
Date Prepared	11/11/24
REQUESTED COMPLETION DATE	11/25/2024

Sending Region	IR30-Pittsburgh	Sending Project Mgr.	Beth Johnson
Receiving Region	IR44-Madisonville	External Client	GREATER HARRISON COUNTY PSD
State of Sample Origin	WV	QC Deliverable	PACKAGEEDD

All questions should be addressed to sending project manager.

Requested Reportable Units _____ Report Wet or Dry Weight? Wet Cert. Needed _____

WORK REQUESTED						
Method Description	Container Type	Quantity of Containers	Preservative	Quantity of Samples	Acode	Acode Desc
WV DW HAA5	DG74		Other	2	SI-30MSSV	SUB PASI MSS
Trip Blank	VG9C		MeCl	1	SI-34MSV	SUB PASI MSV
WV DW TTHM	VG9C		MeCl	2	SI-34MSV	SUB PASI MSV

Special Requirements: Report F, QC Lmts, MDLs, Reg Lmts (F), West Virginia CMDP (1667)

FOR ANALYTICAL WORK COMPLETED THIS SECTION ALSO

Return Samples to Sending Region: ☐ Yes ☒ No

DISPOSITION of FORM

Original sent to the receiving lab - Copy kept at the sending lab.

When work completed; Original sent to the ABM at the receiving laboratory. Copies are made to corporate as needed.

Peace Analytical

Company: Greater Harrison Co. PSD
Address: 151 Peninsula Park Ave
PO BOX 190 West Milford WV 26451
Report To: Julia Childers jchilders@ghpsd.com
Copy To: Brenda Lout
Brenda.ghpsd@gmail.com
Customer Project Name/Number:

Billing Information:
151 Peninsula Park Ave
West Milford WV 26451
Email To: jchilders@ghpsd.com
Site Collection Info/Address:
Status: County/City: Time Zone Collected:
Site/Facility ID #: Compliance Monitoring?
Purchase Order #: DW PWS ID #3301706
Quote #: Immediately Packed on Ice:
Collected By (signature): Julia Childers
Sample Disposal:
[X] Dispose as appropriate
[] Return
[] Archival
[] Hold
* Matrix Codes (Insert in Matrix box below): Drinking Water (DW), Ground Water (GW), Wastewater (WW), Product IP, Solid (SI), Oil (OI), Waste (WP), Air (AR), Tissue (TS), Biosolids (B), Vapor (V), Other (OT)

Customer Sample ID Matrix * Comp / Grab Date Time Composite End Date Time Res O Cns

48 Union Camp Rd	DW	Grab	11/8/2024	10:34	11/8/2024	10:34	1	G	X
292 Koans Run Rd	DW	Grab	11/8/2024	05:34	11/8/2024	05:34	1	G	X
ATCIP Slake							1		

Customer Remarks / Special Conditions / Possible Hazards:

Type of Ice Used: Wet Blue Dry None
Packaging Material Used: Reddham sample(s) screened (<500 qum): - Y - N A

Relinquished by/Company (Signature) Julia Childers
Date/Time: 11-8-24 12:24 PM
Relinquished by/Company (Signature) BMM / PACE
Date/Time: 11/8/24 14:00
Relinquished by/Company (Signature)
Date/Time: 11/8/24 16:02

Received by/Company (Signature) BMM / PACE
Date/Time: 11/8/24 13:22
Received by/Company (Signature)
Date/Time: 11/8/24 14:00
Received by/Company (Signature)
Date/Time: 11/8/24 16:02

CHAIN-OF-CUSTODY Analytical Request Document

Submitting a sample via this chain of custody constitutes acknowledgment and acceptance of the Peace Terms and Conditions found at: <https://www.peaceanalytical.com/terms-and-conditions>
Chain-of-Custody is a LEGAL DOCUMENT - Complete all relevant fields

Company: Greater Harrison Co. PSD
Address: 151 Peninsula Park Ave
PO BOX 190 West Milford WV 26451
Report To: Julia Childers jchilders@ghpsd.com
Copy To: Brenda Lout
Brenda.ghpsd@gmail.com
Customer Project Name/Number:

Lab Profile/Line:
Lab Sample Receipt Checklist:
Custody Seals Present/Intact Y N NA
Collector Signature Present Y N NA
Bottles Intact Y N NA
Correct Bottles Y N NA
Sufficient Volume Y N NA
Samples Received on Ice Y N NA
Vial - Headspace Acceptable Y N NA
USDA Regulated Soils Y N NA
Samples in Holding Time Y N NA
Residual Chlorine Present Y N NA
Cl Strips: Y N NA
Sample pH Acceptable Y N NA
pH Strips: Y N NA
Sulfide Present Y N NA
Lead Acetate Strips: Y N NA
LAB USE ONLY:
Lab Sample # / Comments:

Preservative Type: (1) Nitric (2) Methanol (3) Sodium Hydroxide (4) Sodium Thiosulfate (5) Ascorbic Acid (6) Ammonium Sulfide (7) Ammonium Hydroxide (8) TSP (9) Unpreserved (10) Other

Analysis:
THM & HAAS

Lab Sample Temperature Info:
Temp Blank Received: Y N NA
Therm ID: Y N NA
Cooler 1 Temp Upon Receipt: 1.0
Cooler 1 Therm Corr. Factor: 0.0
Cooler 1 Corrected Temp: 1.0
Comments: 11/8/24 11:24

Lab Sample Temperature Info:
Temp Blank Received: Y N NA
Therm ID: Y N NA
Cooler 1 Temp Upon Receipt: 1.0
Cooler 1 Therm Corr. Factor: 0.0
Cooler 1 Corrected Temp: 1.0
Comments: 11/8/24 11:24

Lab Sample Temperature Info:
Temp Blank Received: Y N NA
Therm ID: Y N NA
Cooler 1 Temp Upon Receipt: 1.0
Cooler 1 Therm Corr. Factor: 0.0
Cooler 1 Corrected Temp: 1.0
Comments: 11/8/24 11:24

Lab Sample Temperature Info:
Temp Blank Received: Y N NA
Therm ID: Y N NA
Cooler 1 Temp Upon Receipt: 1.0
Cooler 1 Therm Corr. Factor: 0.0
Cooler 1 Corrected Temp: 1.0
Comments: 11/8/24 11:24

MSDS Sheets for additives

Fig No 11
Packer Fluid

Section 1. Identification

Product name : CRW132 CORROSION INHIBITOR
Product code : CRW132

Relevant identified uses of the substance or mixture and uses advised against

Identified uses : Corrosion Inhibitor.

Print date : 1/16/2020

Validation date : 1/16/2020

Version : 4.01

Supplier's details : Baker Petrolite LLC
12645 W. Airport Blvd.
Sugar Land, TX 77478
For Product Information/SDSs Call: 800-231-3606
(8:00 a.m. - 5:00 p.m. CST, Monday - Friday) 281-276-5400

Emergency telephone number (with hours of operation) : CHEMTREC: 800-424-9300 (U.S. 24 hour)
Baker Petrolite: 800-231-3606
(001)281-276-5400
CHEMTREC Int'l 01-703-527-3887 (International 24 hour)

Section 2. Hazards identification

OSHA/HCS status : This material is considered hazardous by the OSHA Hazard Communication Standard (29 CFR 1910.1200).

Classification of the substance or mixture : FLAMMABLE LIQUIDS - Category 3
ACUTE TOXICITY (oral) - Category 4
ACUTE TOXICITY (dermal) - Category 4
ACUTE TOXICITY (inhalation) - Category 4
SKIN IRRITATION - Category 2
SERIOUS EYE DAMAGE - Category 1
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (optic nerve) - Category 1
AQUATIC HAZARD (ACUTE) - Category 2

GHS label elements

Hazard pictograms :



Signal word : Danger

Hazard statements : Flammable liquid and vapor.
Harmful if swallowed, in contact with skin or if inhaled.
Causes serious eye damage.
Causes skin irritation.
Causes damage to organs. (optic nerve)
Toxic to aquatic life.

Precautionary statements

Section 2. Hazards identification

- Prevention** : Wear protective gloves: > 8 hours (breakthrough time): Nitrile or Neoprene gloves. 4H gloves.. Wear eye or face protection. Wear protective clothing. Keep away from heat, hot surfaces, sparks, open flames and other ignition sources. No smoking. Use explosion-proof electrical, ventilating, lighting and all material-handling equipment. Use only non-sparking tools. Take precautionary measures against static discharge. Keep container tightly closed. Use only outdoors or in a well-ventilated area. Avoid release to the environment. Do not breathe vapor. Do not eat, drink or smoke when using this product. Wash hands thoroughly after handling.
- Response** : IF exposed: Call a POISON CENTER or physician. IF INHALED: Remove person to fresh air and keep comfortable for breathing. Call a POISON CENTER or physician if you feel unwell. IF SWALLOWED: Call a POISON CENTER or physician if you feel unwell. Rinse mouth. IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water or shower. IF ON SKIN: Wash with plenty of soap and water. Call a POISON CENTER or physician if you feel unwell. Take off contaminated clothing and wash it before reuse. If skin irritation occurs: Get medical attention. IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. Immediately call a POISON CENTER or physician.
- Storage** : Store locked up. Store in a well-ventilated place. Keep cool.
- Disposal** : Dispose of contents and container in accordance with all local, regional, national and international regulations.
- Supplemental label elements** : Avoid contact with skin and clothing. Wash thoroughly after handling.
- Hazards not otherwise classified** : Prolonged or repeated contact may dry skin and cause irritation.

Section 3. Composition/information on ingredients

Substance/mixture : Mixture

Ingredient name	%	CAS number
Methanol	20 - 30	67-56-1
Quaternary ammonium compounds	5 - 10	Trade secret.
Alkylpyridine salts	5 - 10	Trade secret.
Ammonium bisulfite	1 - 5	10192-30-0

Section 4. First aid measures

Description of necessary first aid measures

- Eye contact** : Get medical attention immediately. Call a poison center or physician. Immediately flush the eye(s) continuously with lukewarm, gently flowing water for at least 20-60 minutes while holding the eyelid(s) open. Check for and remove any contact lenses. Chemical burns must be treated promptly by a physician.
- Inhalation** : Remove victim to fresh air and keep at rest in a position comfortable for breathing. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. In case of inhalation of decomposition products in a fire, symptoms may be delayed. The exposed person may need to be kept under medical surveillance for 48 hours.
- Skin contact** : Get medical attention immediately. Call a poison center or physician. Wash affected area with soap and mild detergent for at least 20 - 60 minutes. Wash skin thoroughly with soap and water or use recognized skin cleanser. Remove contaminated clothing and shoes. Wash contaminated clothing thoroughly with water before removing it, or wear gloves. Chemical burns must be treated promptly by a physician. Wash clothing before reuse. Clean shoes thoroughly before reuse.

Section 4. First aid measures

- Ingestion** : Wash out mouth with water. If material has been swallowed and the exposed person is conscious, give small quantities of water to drink. Do not induce vomiting unless directed to do so by medical personnel. If vomiting occurs, the head should be kept low so that vomit does not enter the lungs. Never give anything by mouth to an unconscious person. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway.

Most important symptoms/effects, acute and delayed

Potential acute health effects

- Eye contact** : Causes serious eye damage.
Inhalation : Harmful if inhaled.
Skin contact : Harmful in contact with skin. Causes skin irritation. Defatting to the skin.
Ingestion : Harmful if swallowed.

Over-exposure signs/symptoms

- Eye contact** : pain, watering, redness
Inhalation : No specific data.
Skin contact : pain or irritation, redness, dryness, cracking, blistering may occur
Ingestion : stomach pains

Indication of immediate medical attention and special treatment needed, if necessary

- Notes to physician** : In case of inhalation of decomposition products in a fire, symptoms may be delayed. The exposed person may need to be kept under medical surveillance for 48 hours.
Specific treatments : No specific treatment.
Protection of first-aiders : No action shall be taken involving any personal risk or without suitable training. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Wash contaminated clothing thoroughly with water before removing it, or wear gloves.

See toxicological information (Section 11)

Section 5. Fire-fighting measures

Extinguishing media

- Suitable extinguishing media** : Use dry chemical, CO₂, alcohol-resistant foam or water spray (fog).
Unsuitable extinguishing media : Do not use water jet.

- Specific hazards arising from the chemical** : Flammable liquid and vapor. Runoff to sewer may create fire or explosion hazard. In a fire or if heated, a pressure increase will occur and the container may burst, with the risk of a subsequent explosion. The vapor/gas is heavier than air and will spread along the ground. Vapors may accumulate in low or confined areas or travel a considerable distance to a source of ignition and flash back. This material is toxic to aquatic life. Fire water contaminated with this material must be contained and prevented from being discharged to any waterway, sewer or drain.

- Hazardous thermal decomposition products** : carbon dioxide, carbon monoxide, nitrogen oxides, sulfur oxides, halogenated compounds

Section 5. Fire-fighting measures

- Special protective actions for fire-fighters** : Promptly isolate the scene by removing all persons from the vicinity of the incident if there is a fire. No action shall be taken involving any personal risk or without suitable training. Move containers from fire area if this can be done without risk. Use water spray to keep fire-exposed containers cool.
- Special protective equipment for fire-fighters** : Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode.

Section 6. Accidental release measures

Personal precautions, protective equipment and emergency procedures

- For non-emergency personnel** : No action shall be taken involving any personal risk or without suitable training. Evacuate surrounding areas. Keep unnecessary and unprotected personnel from entering. Do not touch or walk through spilled material. Shut off all ignition sources. No flames, smoking or flames in hazard area. Do not breathe vapor or mist. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment.
- For emergency responders** : If specialized clothing is required to deal with the spillage, take note of any information in Section 8 on suitable and unsuitable materials. See also the information in "For non-emergency personnel".
- Environmental precautions** : Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers. Inform the relevant authorities if the product has caused environmental pollution (sewers, waterways, soil or air). Water polluting material. May be harmful to the environment if released in large quantities.

Methods and materials for containment and cleaning up

- Small spill** : Stop leak if without risk. Move containers from spill area. Use spark-proof tools and explosion-proof equipment. Dilute with water and mop up if water-soluble. Alternatively, or if water-insoluble, absorb with an inert dry material and place in an appropriate waste disposal container. Dispose of via a licensed waste disposal contractor.
- Large spill** : Stop leak if without risk. Move containers from spill area. Use spark-proof tools and explosion-proof equipment. Approach release from upwind. Prevent entry into sewers, water courses, basements or confined areas. Wash spillages into an effluent treatment plant or proceed as follows. Contain and collect spillage with non-combustible, absorbent material e.g. sand, earth, vermiculite or diatomaceous earth and place in container for disposal according to local regulations (see Section 13). Dispose of via a licensed waste disposal contractor. Contaminated absorbent material may pose the same hazard as the spilled product. Note: see Section 1 for emergency contact information and Section 13 for waste disposal.

If RQ (Reportable Quantity) is exceeded, report to National Spill Response Office at 1-800-424-8802.

Section 7. Handling and storage

Precautions for safe handling

- Protective measures** : Put on appropriate personal protective equipment (see Section 8). Do not get in eyes or on skin or clothing. Do not breathe vapor or mist. Do not ingest. Avoid release to the environment. Use only with adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Do not enter storage areas and confined spaces unless adequately ventilated. Keep in the original container or an approved alternative made from a compatible material, kept tightly closed when not in use. Store and use away from heat, sparks, open flame or any other ignition source. Use explosion-proof electrical (ventilating, lighting and material handling) equipment. Use only non-sparking tools. Take precautionary measures against electrostatic discharges. Empty containers retain product residue and can be hazardous. Do not reuse container.

Section 7. Handling and storage

Advice on general occupational hygiene : Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Remove contaminated clothing and protective equipment before entering eating areas. See also Section 8 for additional information on hygiene measures.

Conditions for safe storage, including any incompatibilities : Store in accordance with local regulations. Store in a segregated and approved area. Store in original container protected from direct sunlight in a dry, cool and well-ventilated area, away from incompatible materials (see Section 10) and food and drink. Store locked up. Eliminate all ignition sources. Separate from oxidizing materials. Keep container tightly closed and sealed until ready for use. Containers that have been opened must be carefully resealed and kept upright to prevent leakage. Do not store in unlabeled containers. Use appropriate containment to avoid environmental contamination. See Section 10 for incompatible materials before handling or use.

Section 8. Exposure controls/personal protection

Control parameters

Occupational exposure limits

Ingredient name	Exposure limits
Methanol	ACGIH TLV (United States, 3/2018). Absorbed through skin. STEL: 328 mg/m³, 0 times per shift, 15 minutes. STEL: 250 ppm, 0 times per shift, 15 minutes. TWA: 262 mg/m³, 0 times per shift, 8 hours. TWA: 200 ppm, 0 times per shift, 8 hours. NIOSH REL (United States, 10/2016). Absorbed through skin. STEL: 325 mg/m³, 0 times per shift, 15 minutes. STEL: 250 ppm, 0 times per shift, 15 minutes. TWA: 260 mg/m³, 0 times per shift, 10 hours. TWA: 200 ppm, 0 times per shift, 10 hours. OSHA PEL (United States, 5/2018). TWA: 260 mg/m³, 0 times per shift, 8 hours. TWA: 200 ppm, 0 times per shift, 8 hours. OSHA PEL 1989 (United States, 3/1989). Absorbed through skin. STEL: 325 mg/m³, 0 times per shift, 15 minutes. STEL: 250 ppm, 0 times per shift, 15 minutes. TWA: 260 mg/m³, 0 times per shift, 8 hours. TWA: 200 ppm, 0 times per shift, 8 hours.
Quaternary ammonium compounds	None.
Alkylpyridine salts	None.
Ammonium bisulfite	None.

Consult local authorities for acceptable exposure limits.

If OSHA permissible exposure levels are shown above they are the OSHA 1989 levels or are from subsequent OSHA regulatory actions. Although the 1989 levels have been vacated the 11th Circuit Court of Appeals, Baker Hughes recommends that these lower exposure levels be observed as reasonable worker protection.

Appropriate engineering controls : Use only with adequate ventilation. Use process enclosures, local exhaust ventilation or other engineering controls to keep worker exposure to airborne contaminants below any recommended or statutory limits. The engineering controls also need to keep gas, vapor or dust concentrations below any lower explosive limits. Use explosion-proof ventilation equipment.

Section 8. Exposure controls/personal protection

Individual protection measures

- Hygiene measures** : Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Wash contaminated clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.
- Eye/face protection** : Wear chemical safety goggles. When transferring material wear face-shield in addition to chemical safety goggles. If inhalation hazards exist, a full-face respirator may be required instead.
- Hand protection** : Chemical-resistant gloves: Nitrile or Neoprene gloves. 4H gloves.
- Skin protection** : Wear long sleeves and chemical resistant apron to prevent repeated or prolonged skin contact.
- Respiratory protection** : If a risk assessment indicates it is necessary, use a properly fitted supplied air respirator complying with an approved standard. Respirator selection must be based on known or anticipated exposure levels, the hazards of the product and the safe working limits of the selected respirator.

Section 9. Physical and chemical properties

Appearance

- Physical state** : Liquid.
- Color** : Amber. [Dark]
- Odor** : Pungent. Amine-like.
- Odor threshold** : Not available.
- pH** : 4 to 5
- : Neat - without dilution.
- Melting/freezing point** : Not available.
- Boiling point** : Not available.
- Initial Boiling Point** : Not available.
- Flash point** : Closed cup: 31.1°C (88°F) [PMCC]
- Burning time** : Not applicable.
- Burning rate** : Not applicable.
- Evaporation rate** : Not available.
- Flammability (solid, gas)** : Highly flammable in the presence of the following materials or conditions: open flames, sparks and static discharge and heat.
- Lower and upper explosive (flammable) limits** : Not available.
- Vapor pressure** : 45.5 kPa (341.3 mm Hg, 6.6 psig) @ 54.4°C, 130 F (Reid)
- Vapor density** : >1 [Air = 1]
- Relative density** : 0.97 (15.6°C)
- Density** : 8.08 (lbs/gal)
- Solubility in water** : Soluble
- Partition coefficient: n-octanol/water** : Not available.
- Auto-ignition temperature** : Not available.
- Decomposition temperature** : Not available.
- Viscosity** : Dynamic (15.6°C): 8 cP
- VOC** : Not available.
- Pour Point** : -40°C (-40°F)

Section 10. Stability and reactivity

- Reactivity** : No specific test data related to reactivity available for this product or its ingredients.
- Chemical stability** : The product is stable.
- Possibility of hazardous reactions** : Under normal conditions of storage and use, hazardous reactions will not occur.
- Conditions to avoid** : Avoid all possible sources of ignition (spark or flame). Do not pressurize, cut, weld, braze, solder, drill, grind or expose containers to heat or sources of ignition. Do not allow vapor to accumulate in low or confined areas.
- Incompatible materials** : Reactive or incompatible with the following materials: oxidizing materials and reducing materials.
Methanol is incompatible and may react with acetyl bromide, alkyl aluminum solutions, beryllium hydride, boron trichloride, nitric acid, cyanuric chloride, dichloromethane, diethylzinc, metals (granulated forms of aluminum and magnesium – including aluminum and zinc salts), phosphorus III oxide, and potassium tert-butoxide.
- Hazardous decomposition products** : Under normal conditions of storage and use, hazardous decomposition products should not be produced.

Section 11. Toxicological information

Information on toxicological effects

Acute toxicity

Product/Ingredient name	Result	Species	Dose	Exposure
Methanol	LC50 Inhalation Gas.	Rat	145000 ppm	1 hours
	LC50 Inhalation Gas.	Rat	64000 ppm	4 hours
	LD50 Dermal	Rabbit	15800 mg/kg	-
	LD50 Oral	Human	500 mg/kg	-
	LD50 Oral	Rat	5600 mg/kg	-

Irritation/Corrosion

No applicable toxicity data

Sensitization

No applicable toxicity data

Mutagenicity

No applicable toxicity data

Carcinogenicity

No applicable toxicity data

Reproductive toxicity

No applicable toxicity data

Teratogenicity

No applicable toxicity data

Specific target organ toxicity (single exposure)

Name	Category	Route of exposure	Target organs
Methanol	Category 1	Oral	optic nerve

Section 11. Toxicological information

Specific target organ toxicity (repeated exposure)

Not applicable.

Aspiration hazard

Not available.

Information on the likely routes of exposure : Routes of entry anticipated: Dermal, Inhalation.

Potential acute health effects

Eye contact : Causes serious eye damage.
Inhalation : Harmful if inhaled.
Skin contact : Harmful in contact with skin. Causes skin irritation. Defatting to the skin.
Ingestion : Harmful if swallowed.

Potential chronic health effects

General : Prolonged or repeated contact can defat the skin and lead to irritation, cracking and/or dermatitis.
Carcinogenicity : No known significant effects or critical hazards.
Mutagenicity : No known significant effects or critical hazards.
Teratogenicity : No known significant effects or critical hazards.
Developmental effects : No known significant effects or critical hazards.
Fertility effects : No known significant effects or critical hazards.

Numerical measures of toxicity

Acute toxicity estimates

Route	ATE value
Oral	321.6 mg/kg
Dermal	1003.3 mg/kg
Inhalation (vapors)	10.03 mg/l

Section 12. Ecological information

Toxicity

Product/ingredient name	Result	Species	Exposure
CRW132 CORROSION INHIBITOR	Acute EC50 16.912 mg/l Marine water	Algae - Ulva pertusa	96 hours
	Acute EC50 10000000 µg/l Fresh water	Daphnia - Daphnia magna	48 hours
	Acute LC50 2500000 µg/l Marine water	Crustaceans - Crangon crangon	48 hours
	Acute LC50 100 mg/l Fresh water	Fish - Pimephales promelas	96 hours
	Chronic NOEC 9.96 mg/l Marine water	Algae - Ulva pertusa	96 hours
	Acute LC50 2.61 mg/l	Daphnia	48 hours
	Acute LC50 3 ppm	Daphnia	48 hours
	Acute LC50 2.3 mg/l	Fish - Fathead minnow	96 hours
	Acute LC50 2.3 mg/l	Fish - Sheepshead minnow	96 hours

Persistence and degradability

Not available.

Section 12. Ecological information

Other adverse effects : No known significant effects or critical hazards.

Section 13. Disposal considerations

Disposal methods : Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Waste packaging should be recycled. Incineration or landfill should only be considered when recycling is not feasible. This material and its container must be disposed of in a safe way. Care should be taken when handling emptied containers that have not been cleaned or rinsed out. Vapor from product residues may create a highly flammable or explosive atmosphere inside the container. Do not cut, weld or grind used containers unless they have been cleaned thoroughly internally. Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers.

Section 14. Transport information

	DOT Classification	TDG Classification	IMDG	IATA
UN number	UN1992	UN1992	UN1992	UN1992
UN proper shipping name	FLAMMABLE LIQUID, TOXIC, N.O.S. (Contains: Methanol)	FLAMMABLE LIQUID, TOXIC, N.O.S. (Contains: Methanol)	FLAMMABLE LIQUID, TOXIC, N.O.S. (Contains: Methanol)	FLAMMABLE LIQUID, TOXIC, N.O.S. (Contains: Methanol)
Transport hazard class(es)	3 (6.1)  	3 (6.1)  	3 (6.1)  	3 (6.1)  
Packing group	III	III	III	III
Environmental hazards	No.	No.	No.	No.

Additional information

DOT Classification : **Reportable quantity** 16722.2 lbs / 7591.9 kg [2067.6 gal / 7826.7 L]. Package sizes shipped in quantities less than the product reportable quantity are not subject to the RQ (reportable quantity) transportation requirements.

TDG Classification : Product classified as per the following sections of the Transportation of Dangerous Goods Regulations: 2.18-2.19 (Class 3), 2.26-2.36 (Class 6).

IMDG : **Emergency schedules** F-E S-D

Special precautions for user : **Transport within user's premises:** always transport in closed containers that are upright and secure. Ensure that persons transporting the product know what to do in the event of an accident or spillage.

Transport in bulk according to Annex II of MARPOL and the IBC Code : Not available.

DOT Reportable Quantity Methanol, 2070 gal of this product.
Ammonium bisulfite, 24752 gal of this product.

Marine pollutant Not available.

Section 14. Transport information

North-America NAERG : 131

Section 15. Regulatory information

U.S. Federal regulations : TSCA 12(b) one-time export: No products were found.
 TSCA 12(b) annual export notification: No products were found.
 United States inventory (TSCA 8b): All components are listed or exempted.
 Clean Water Act (CWA) 307: No products were found.
 Clean Water Act (CWA) 311: ammonium hydrogensulphite

United States - Clean Air Act Section 112(b) Hazardous Air Pollutants (HAPs):

List name	Status	Ingredient name	Name on list	Conc.
United States - Clean Air Act Section 112(b) Hazardous Air Pollutants (HAPs)	Listed	Methanol	Methanol	20 - 30

SARA 302/304 : No products were found.**SARA 311/312**

Classification : Fire hazard
 Immediate (acute) health hazard

SARA 313

	Product name	CAS number	%
Supplier notification	Methanol	67-56-1	20 - 30
	Ammonium bisulfite	10192-30-0	1 - 5

California Prop. 65

⚠ WARNING: This product can expose you to methanol, which is known to the State of California to cause birth defects or other reproductive harm. For more information go to www.P65Warnings.ca.gov.

Canada

Canada (CEPA DSL): : All components are listed or exempted.

Section 16. Other information**National Fire Protection Association (U.S.A.)****History**

Date of printing : 1/16/2020

☑ Indicates information that has changed from previously issued version.

Notice to reader

NOTE: The information on this SDS is based on data which is considered to be accurate. Baker Hughes, however, makes no guarantees or warranty, either expressed or implied of the accuracy or completeness of this information.

The conditions or methods of handling, storage, use and disposal of the product are beyond our control and may be beyond our knowledge. For this and other reasons, we do not assume responsibility and expressly disclaim liability for loss, damage or expense arising out of or in any way connected with the handling, storage, use or disposal of this product.

This SDS was prepared and is to be used for this product. If the product is used as a component in another product, this SDS information may not be applicable.

Section 10

Monitoring

Section No. 10

Pressure and injection volumes are monitored daily for this injection well. These volumes and pressure are recorded by the well tender and reported to his supervisor weekly. In the event the well tender discovers an issue with the injection well or any of the associated facilities he will contact his supervisor immediately to get the issue resolved. The injection information is reported to the WVDEP monthly on Form WR-40. This process has worked successfully for the 30 years this well has been utilized as a disposal well.

Currently the vast majority of the fluid injected at this well is transported by pipeline to the storage tank that serves this injection well. A small portion of the fluid is transported by a small truck with a 500 gal tank from some of the more remote producing wells in this field to the storage tank that serves this injection well. The volumes are recorded and reported weekly. The only fluids injected at this well are those transported via pipeline or small truck from Company operated wells in this field.

Section 11

Groundwater Protection Plan

Section No. 11

Please see APPENDIX H for Ground Water Protection Plan for this facility.

APPENDIX H

GROUNDWATER PROTECTION PLAN

Facility Name: Clover Produced Water DisposalCounty: Roane

Facility Location:

Postal Service Address:	Kaufman Rd. Spencer, WV 25276		
Latitude :	38 Degrees 45' 32"	Longitude:	81 Degrees 15'45"

Contact Information:

Person:	Brad Morris
Phone Number:	681-229-1558
E-mail Address:	bmorris@topdrilling.com

Date: 12/15/24

1. A list of all operations that may contaminate the groundwater.

Tank failure / leak Pipeline failure / leak Fluids (bactericide, corrosion inhibitor, etc) transfer Stuffing box failure well completion / work over activities

2. A description of procedures and facilities used to protect groundwater quality from the list of potential contaminant sources above.

Secondary containment is installed around tanks adequate to hold the volume of the largest tank. Pipelines are routinely monitored and patrolled for leaks. Pipelines are registered with the WV 811 to minimize possibility of being damaged by others. Pressure monitoring - Shut down controls on pump. Work over fluids are properly contained and disposed of. The injection well is monitored for mechanical integrity failures and pressure tested ever five years.
--

3. List procedures to be used when designing and adding new equipment or operations.

Non corrosive materials are utilized as much as possible. Shut down controls installed on injection pump.

4. Summarize all activities at your facility that are already regulated for groundwater protection.

This facility is currently covered by an existing UIC permit No. 2D0871056. Storage tanks are registered under WV Tank regulations. Any Spills or leaks are reported to WVDEP / EPA.

5. Discuss any existing groundwater quality data for your facility or an adjacent property.

There are no known ground water quality issues in this area. Only two of the residences with in the AOR utilize water wells for domestic use. The analytical results from these two wells are enclosed with this application.

6. Provide a statement that no waste material will be used for deicing or fill material on the property unless allowed by another rule.

No waste material is or will be used for deicing or fill material.

7. Describe the groundwater protection instruction and training to be provided to the employees. Job procedures shall provide direction on how to prevent groundwater contamination.

The operators of this facility are instructed to routinely monitor tank conditions, secondary containment conditions, and patrol injection lines. They are trained yearly regarding ground water protection. Part of this training involves prevention of oil & chemical spills and the prompt clean up / remediation of any spills. Prior to the release of any storm water from secondary containment it is tested t assure that it meets guidelines for discharge.

8. Include provisions for inspections of all GPP elements and equipment. Inspections must be made quarterly at a minimum.

Secondary containment, pipelines, and injection equipment are inspected and documented a minimum of every 90 days. The injection well and producing wells are visited several times weekly. The wellheads are inspected for any indication of mechanical integrity. Any issues are addressed when discovered. The majority of the production pipelines and the injection lines are located parallel to roadways which are traveled several times weekly.

Signature: Bred A. Houn

Date: 12/15/24

Section 12

Plugging and Abandonment

Section No. 12

This injection well has surface casing set at 174' and cemented to surface. The 4 ½" casing is set at 2219' and cemented to approximately 1933'. See schematic – Fig No. 4. The well will be plugged to the standards set by WVDEP at the time it is plugged. If this well was to be plugged today it would be plugged as follows:

Plug No. 1- 2150'-2050'

Free point, cut, & POH w/ 4 1/2" casing – est 1875'

Plug No. 2 -1925'-1825' (adjusted for casing cut above)

Plug No. 3 -1060'-960'

Plug No. 4 – 225'-125' (base of surface casing)

Plug No. 5 – 100'-0'

6 % gel between cement plugs.

Section 13

Additional Bonding

Section No. 13

An additional \$5000 bond was posted at the time Delta Helix Energy LLC purchased these assets, and the bond will remain in place.

Section 14

Financial Responsibility

Section No. 14

See APPENDIX I

APPENDIX I

Requirement for Financial Responsibility to Plug/Abandon an Injection Well

In accordance with WV Code 47CSR13.13.7.g, all UIC permits shall require the permittee to maintain financial responsibility and resources to close, plug, and abandon underground injection wells in a manner prescribed by the Chief. The permittee must show evidence of financial responsibility to the Chief by submission of a surety bond, or other adequate assurance, such as a financial statement or other material acceptable to the Chief. This certification must be signed by one of the following:

1. For a corporation: by a principle corporate officer of at least the level of vice-president;
2. For a partnership or sole proprietorship: by a general partner or the proprietor, respectively;
3. For a municipality, State, Federal, or other public agency: by either a principle executive officer or ranking elected official;
4. Or a duly authorized representative in accordance with 47CSR13.13.11.b.
(A person may be duly authorized by one of the primary entities (1-3) listed above by submitting a written authorization to the Chief of the WVDEP Office of Oil and Gas designating an individual or a position having responsibility for the overall operation of the regulated facility or activity, such as the position of plant manager, operator of a well or a well field, superintendent, or position of equivalent responsibility. A duly authorized representative may thus be either a named individual or any individual occupying a named position.)

Delta Helix Energy, LLC

(Company Name)

2D08700985002

(UIC Permit Number)

I certify in accordance with 47CSR13.13.7.g., that the company/permit holder cited above will maintain financial responsibility and resources to close, plug, and abandon underground injection wells(s) in a manner prescribed by the Chief of the Office of Oil and Gas and that documents to support this requirement are on record with the same.

B Douglas Haught

(Print Name)

CEO

(Print Title)

(Signature)

12-16-24

(Date)

Section 15

Site Security Plan

Section No. 15

This injection facility is remotely located and accessed via a roadway shared with a few residences. When unattended a locked gate blocks access to this facility. Please see APPENDIX J

APPENDIX J**Site Security for Commercial Facilities**

Provide a detailed description of the method(s) utilized at the facility to restrict or prohibit illegal dumping of unauthorized waste or vandalism at the facility.

1. Complete enclosure of all wells, holding tank/pits and manifold assemblies within a chain link or other suitable fencing; and
2. Require that all gates and other entry points be locked when the facility is unattended; or
3. Providing tamper-proof seals for the master valve on each well (a "lock-out" or chain & padlock system would be more secure; however, these devices could create a potential safety hazard if the well needed to be quickly shut in due to an emergency); and
4. Installing locking caps on all valves and connections on holding tanks, unloading racks, and headers.

This is not a commercial facility

Section 16

Additional Information

Section No. 16

See APPENDIX K

APPENDIX K

Identify permit or construction approvals received
or applied for under the following programs:

Permit/approvals	ID Number
Hazardous Waste Management Program under RCRA	
NPDES Program	
Prevention of Significant Deterioration (PSD)	
Nonattainment Program	
Dredge or Fill	
NPDES/NPDES – Stormwater	
WVDEP – Office of Waste Management (OWM) – Solid Waste Facility	
WVDEP – OWM – RCRA (Hazardous Waste TSD or Transporter)	
WVDEP – OWM – UST	
CERCLA – Superfund	
WV Voluntary Remediation – Brownfields	
FIFRA – Federal Insecticide, Fungicide and Rodenticide Act	
Well Head Protection Program (WHPP)	
Underground Injection Control (UIC)	2D08700985002
Toxic Substances Control Act (TSCA)	
Best Management Plans	
Management of Used Oil	
Other Relevant Permits (Specify):	
WV DEP Tank Registrations	See Appendix B

2D08700985

Delta Helix Energy, LLC

Wells in the Area of Review

4708700985

APPENDIX C
Wells within the Area of Review

	API No.	Well No.	Well Type	Well Status	Northing	Easting	Penetrate Injection Zone	Penetrate Confining Zone	Total Vertical Depth	Surface Elevation
1	4708700878	Wines 1	Oil Prod	Active	4289856.6	476352.3	Y	Y	2273	1076
2	4708700894	Kaufman 5	Oil Prod	Active	4289879.0	476728.0	Y	Y	2281	1109
3	4708700954	Wines 3	Gas Prod	Active	4290082.6	476637.5	Y	Y	2180	1092
4	4708700984	W-5	Oil Prod	Active	4299499.9	476642.1	Y	Y	2270	1040
5	4708700985	W-7	Injector	Active	4289738.0	476780.0	Y	Y	2219	1003
6	4708700987	W-6	Gas Prod	Active	4289588.2	476357.8	Y	Y	2335	1132
7	4708700988	W-8	Oil Prod	Active	4289673.2	477190.2	Y	Y	2430	1225
8	4708701053	W-17	Oil Prod	Active	4289888.7	477092.4	Y	Y	2190	971
9	4708730190	?	Plugged	Abandoned	4289635.7	476521.2	Y	Y	2245	1052
10	4708770398	?	Unknown	Abandoned	4289564.9	476487.5	?	?	?	?
11	4708791143	?	Unknown	Abandoned	4289549.2	476326.3	?	?	?	?
12	4708791144	?	Unknown	Abandoned	4289645.6	476423.3	?	?	?	?
13	4708791145	?	Unknown	Abandoned	4289758.0	476520.2	?	?	?	?

4708700878	McKown, C. I. & Son, Inc.	2022	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700878	McKown, C. I. & Son, Inc.	2023	0	0	0	0	0	0	0	0	0	0	0	0	0	0

4708700878

Production Water Information: (Volumes in Gallons)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_WTR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700878	McKown, C. I. & Son, Inc.	2016	0												
4708700878	McKown, C. I. & Son, Inc.	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700878	McKown, C. I. & Son, Inc.	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700878	McKown, C. I. & Son, Inc.	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700878	McKown, C. I. & Son, Inc.	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700878	McKown, C. I. & Son, Inc.	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700878	McKown, C. I. & Son, Inc.	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

There is no Stratigraphy data for this well

Wireline (E-Log) Information:

* There is no Scanned/Raster Log data for this well

* There is no Digitized/LAS Log data for this well

* There is no Scanned or Digital Logs available for download

There is no Plugging data for this well

There is no Sample data for this well



4708700878

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION 34

Quadrangle Spencer

Permit No. ROA 878

WELL RECORD

Oil or Gas Well Cum
(KIND)

Company J & B Oil Co. Inc.
Address 615 1/2 Market St. Parkersburg, W. Va.
Farm Cora A. & C. H. Wine Acres 90.33
Formerly Frank Simmons Boggs Fork
Location (waters)
Well No. 4 Elev. 1076.408
District Spencer County Roane
The surface of tract is owned in fee by C. H. Wine
Address Spencer
Mineral rights are owned by
Address
Drilling commenced Feb. 16, 1962
Drilling completed April 4, 1962
Date Shot From To
With
Open Flow /10ths Water in Inch
/10ths Merc. in Inch
Volume 5,000 Cu. Ft.
Rock Pressure 120 lbs. 24 hrs.
Oil 5 gll. bbls., 1st 24 hrs.
WELL ACIDIZED

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
13	8	8	
10	472	none	Size of
8 1/4	1043	"	
6 3/4	2118	"	Depth set
5 3/16			
4 1/2	2273	2273	Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED 2273 SIZE 4 1/2 No. Ft. 3 -30-68 Date
76 sks. cement, 2 sks. aquagel DOWELL

COAL WAS ENCOUNTERED AT FEET INCHES
FEET INCHES FEET INCHES
FEET INCHES FEET INCHES

WELL FRACTURED 1700 bbls. water 80,000 lb. sand


RESULT AFTER TREATMENT 2 bbls. oil 75,000 gas

ROCK PRESSURE AFTER TREATMENT 150 lb. 24 hrs.

Fresh Water 115 Feet Salt Water 1870 Feet

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
RED			0	62			
Sand			62	87			
Slate			87	111			
Sand			111	144	water	115	
Slate			144	153			
Sand			153	176			
Slate			176	210			
Red			210	220			
Slate			220	230			
Red			230	254			
Slate			254	261			
Sand			261	269			
Slate			269	290			
Sand			290	315			
Red			315	345			
Slate			345	364			
Red			364	389			
Sand			389	392			
Slate			392	466			
Red			466	470			
Slate			470	475			
Red			475	497			
Slate			497	532			
Sand			532	583			
Slate			583	629			
RED			629	634			
Slate			634	657			
Red			657	669			

(over)



4708700878

Formation	Color	Hard or Soft	Top 34	Bottom	Oil, Gas or Water	Depth Found	Remarks
Slate			669	681			
Red			681	702			
Slate			702	715			
Sand			715	754			
Red			754	780			
Slate			780	795			
Red			795	810			
Sand			810	822			
Red			822	870			
Slate			870	905			
Red			905	955			
Slate			955	965			
Red			965	1000			
Slate			1000	1028			
Red			1028	1036			
Slate			1036	1090			
Sand			1090	1187			
Slate			1187	1230			
Sand			1230	1247			
Slate			1247	1254			
Sand			1254	1382			
Slate			1382	1444			
Sand			1444	1460			
Slate			1460	1467			
Sand			1467	1485			
Slate			1485	1544			
Sand			1544	1590			
Slate			1590	1620			
Sand			1620	1661			
Slate			1661	1695			
Sand			1695	1910			
Slate			1910	1912			
Sand			1912	1928			
Slate			1928	1931			
Sand			1931	1999			
Slate			1999	2003			
Lime			2003	2036			
Slate			2036	2038			
Lime			2038	2155			
Sand	Keener		2155	2182			
Sand	Injun		2182	2208			
Slate			2208	2210			
Sand			2210	2215			
Slate			2215	2273			
Total depth 2273							

Date April 9, 1962

APPROVED J. B. W. C. J. C. OwnerBy Jae. Altier (Title) Sup.

**"Pipeline"**

Select County: (087) Roane

Enter Permit #: 894

Get Data

Reset

Select datatypes: ☐ (Check All)☒ Location☒ Owner/Completion☒ Pay/Show/Water☐ Production☒ Stratigraphy☒ Logs☒ Plugging☒ Sample☒ Btm Hole Loc

Table Descriptions
County Code Translations
Permit-Numbering Series
Usage Notes
Contact Information
Disclaimer
WVGES Main
"Pipeline-Plus" New

WV Geological & Economic Survey:

Well: County = 87 Permit = 894 [Link to all digital records for well](#)

Kaufman 5

Report Date: Thursday, April 03, 2025 1:10:22 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX_DISTRICT	QUAD_75	LAT_DD	LON_DD	UTME	UTMN
4708700894	Roane	894	Smithfield	Spencer	38.757304	-81.267843	476728	4289879

There is no Bottom Hole Location data for this well

Owner Information:

API	CMP_DT	SUFFIX	STATUS	SURFACE_OWNER	WELL_NUM	CO_NUM	LEASE	LEASE_NUM	MINERAL_OWN	OPERATOR_AT_COMPLETION	PROP_VD	PROP_TRGT_FM	TFM
4708700894	7/25/1962	Original Loc	Completed	William Kaufman	5					South Penn Oil (S. Penn Nat. Gas)			
4708700894	-/-	Permitted		Ricky W Jarvis/Brad S Hilyer	5		WM Kaufman		HG Energy LLC et al	HG Energy, LLC			

Completion Information:

API	CMP_DT	SPUD_DT	ELEV	DATUM	FIELD	DEEPEST_FM	DEEPEST_FMT	INITIAL_CLASS	FINAL_CLASS	TYPE	RIG	CMP_MTHD	TVD	TMD	NEW_FTG	KOD	G_BEF
4708700894	7/25/1962	7/15/1962	1118	Ground Level	Civ-Rsh Rn	Price Fm & equivs	Big Injun (Price&eq)	Development Well	Development Well	Oil and Gas	unknown	Fractured	2281		2281		0
4708700894	-/-	-/-	1109	Ground Level													

Pay/Show/Water Information:

API	CMP_DT	ACTIVITY	PRODUCT	SECTION	DEPTH_TOP	FM_TOP	DEPTH_BOT	FM_BOT	G_BEF	G_AFT	O_BEF	O_AFT	WATER_QNTY
4708700894	7/25/1962	Water	Fresh Water	Vertical			124						0
4708700894	7/25/1962	Water	Fresh Water	Vertical			825						1
4708700894	7/25/1962	Water	Salt Water	Vertical			1900						0
4708700894	7/25/1962	Pay	Oil & Gas	Vertical			2282	Big Injun (Price&eq)	0	0			

Production Gas Information: (Volumes in Mcf)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_GAS	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700894	Pennzoil Company	1981	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	Pennzoil Company	1982	999	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	Pennzoil Company	1983	1,492	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	Pennzoil Products Company	1987	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	Pennzoil Products Company	1989	936	93	63	64	71	91	56	92	70	82	98	85	71
4708700894	Pennzoil Products Company	1990	871	82	64	94	72	74	66	89	82	74	103	88	83
4708700894	Pennzoil Products Company	1991	963	73	61	71	58	82	84	98	80	80	104	79	93
4708700894	Pennzoil Products Company	1992	912	93	70	63	66	81	64	80	87	60	87	74	67
4708700894	Pennzoil Products Company	1993	697	52	69	69	38	50	63	60	54	59	66	56	61
4708700894	Pennzoil Products Company	1994	610	63	52	29	51	54	57	55	59	58	38	44	49
4708700894	Pennzoil Products Company	1995	503	39	42	44	41	51	46	46	36	44	38	35	41
4708700894	Pennzoil Products Company	1996	384	21	1	55	36	36	34	37	22	33	27	41	41
4708700894	Pennzoil Products Company	1997	399	28	28	35	30	28	31	34	36	36	32	44	37
4708700894	Pennzoil Products Company	1998	378	37	52	34	40	46	20	24	21	22	20	22	14
4708700894	Pennzoil Products Company	1999	197	46	13	20	22	15	0	12	12	21	22	14	14
4708700894	East Resources, Inc.	2000	150	13	14	10	0	17	8	0	20	14	16	16	22
4708700894	East Resources, Inc.	2001	275	7	17	24	24	26	26	27	29	31	31	7	7
4708700894	East Resources, Inc.	2002	314	29	26	26	23	28	27	29	30	25	27	13	31
4708700894	East Resources, Inc.	2003	192	20	12	0	0	34	21	21	24	17	25	0	18
4708700894	East Resources, Inc.	2004	276	26	19	17	20	17	21	25	15	19	29	27	41
4708700894	East Resources, Inc.	2005	363	22	22	21	24	40	34	29	39	41	40	33	38
4708700894	East Resources, Inc.	2006	509	38	37	41	41	45	44	48	33	36	43	50	53
4708700894	East Resources, Inc.	2007	430	51	38	42	30	27	23	27	34	31	32	49	46
4708700894	East Resources, Inc.	2008	479	40	39	40	37	41	39	40	41	41	45	38	38
4708700894	East Resources, Inc.	2010	506	49	35	40	42	43	40	41	41	40	46	47	42
4708700894	East Resources, Inc.	2011	547	44	41	47	47	47	43	47	48	46	48	44	45
4708700894	HG Energy, LLC	2012	525	40	35	39	40	44	40	28	52	57	57	47	46
4708700894	HG Energy, LLC	2013	533	48	35	38	39	51	47	42	48	45	50	44	46
4708700894	HG Energy, LLC	2014	383	42	37	42	36	1	9	15	35	42	42	39	43
4708700894	HG Energy, LLC	2015	464	37	32	33	37	42	41	42	40	40	40	37	43
4708700894	HG Energy, LLC	2016	467	39	38	39	39	41	38	40	38	39	39	38	38
4708700894	HG Energy, LLC	2017	404	37	32	33	31	34	30	32	32	34	36	37	36
4708700894	HG Energy, LLC	2018	426	36	33	38	36	38	37	39	36	34	33	32	34
4708700894	HG Energy, LLC	2019	365	35	32	34	31	24	24	26	32	30	33	34	30
4708700894	HG Energy, LLC	2020	356	35	31	35	17	29	32	33	32	28	28	29	29
4708700894	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	HG Energy, LLC	2022	339	28	21	29	27	29	28	31	31	29	29	29	28
4708700894	Delta Helix Energy, LLC	2023	58	0	0	0	0	0	0	0	0	0	0	30	28
4708700894	HG Energy, LLC	2023	313	30	27	31	32	32	30	32	32	34	33	0	0

Production Oil Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_OIL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700894	Pennzoil Company	1981	440	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	Pennzoil Company	1982	307	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	Pennzoil Company	1983	444	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	Pennzoil Products Company	1987	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	Pennzoil Products Company	1989	197	16	16	18	13	17	15	18	17	18	17	16	16
4708700894	Pennzoil Products Company	1990	197	19	15	18	17	17	17	16	17	17	18	14	12
4708700894	Pennzoil Products Company	1991	190	16	12	17	16	17	15	14	18	15	18	17	15
4708700894	Pennzoil Products Company	1992	169	15	16	14	16	14	15	11	17	14	14	10	13
4708700894	Pennzoil Products Company	1993	148	14	11	10	14	13	12	13	14	12	12	12	11
4708700894	Pennzoil Products Company	1994	125	6	12	13	13	11	12	13	8	9	11	8	9
4708700894	Pennzoil Products Company	1995	89	9	8	11	10	10	7	9	8	8	9	0	0
4708700894	Pennzoil Products Company	1996	102	15	10	9	8	8	4	7	9	9	9	7	7
4708700894	Pennzoil Products Company	1997	89	8	8	8	8	9	9	6	7	7	6	6	7
4708700894	Pennzoil Products Company	1998	66	7	8	8	9	2	0	0	0	0	0	19	13
4708700894	Pennzoil Products Company	1999	31	14	14	3	0	0	0	0	0	0	0	0	0
4708700894	East Resources, Inc.	2000	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	East Resources, Inc.	2001	97	0	11	10	8	10	8	9	7	8	10	8	8
4708700894	East Resources, Inc.	2002	96	8	10	8	7	9	9	12	8	7	7	3	8
4708700894	East Resources, Inc.	2003	57	9	0	0	0	12	7	5	5	5	6	0	8
4708700894	East Resources, Inc.	2004	55	4	6	6	6	4	5	6	4	5	3	3	3
4708700894	East Resources, Inc.	2005	49	2	4	4	4	5	4	5	5	4	3	5	4
4708700894	East Resources, Inc.	2006	74	5	6	10	6	9	7	6	0	2	9	8	6
4708700894	East Resources, Inc.	2007	81	8	6	8	7	7	5	5	9	7	5	7	7
4708700894	East Resources, Inc.	2008	54	1	6	6	7	5	4	6	4	4	3	4	4
4708700894	East Resources, Inc.	2010	110	6	10	12	13	0	8	14	12	12	10	8	5
4708700894	East Resources, Inc.	2011	92	6	6	10	10	8	9	8	10	7	4	6	8
4708700894	HG Energy, LLC	2012	94	7	10	8	8	10	10	4	10	8	9	4	6
4708700894	HG Energy, LLC	2013	124	8	13	12	12	14	8	10	9	11	11	8	8
4708700894	HG Energy, LLC	2014	127	10	11	15	11	16	13	11	11	10	8	5	8
4708700894	HG Energy, LLC	2015	98	7	4	5	7	14	10	10	8	8	10	7	8
4708700894	HG Energy, LLC	2016	85	6	4	6	8	6	10	8	10	8	8	4	7
4708700894	HG Energy, LLC	2017	61	6	7	6	6	6	4	4	5	4	4	5	4
4708700894	HG Energy, LLC	2018	58	6	4	4	4	5	5	5	5	4	6	3	7
4708700894	HG Energy, LLC	2019	71	11	4	5	7	10	5	5	4	5	6	5	4
4708700894	HG Energy, LLC	2020	60	5	4	4	7	5	4	7	5	5	4	5	5
4708700894	HG Energy, LLC	2021	66	6	3	3	9	6	9	4	6	5	5	4	6
4708700894	HG Energy, LLC	2022	47	7	5	7	6	5	4	6	6	1	0	0	0
4708700894	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

4708700894	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
------------	----------------	------	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---

4708700894

Production NGL Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_NGL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700894	HG Energy, LLC	2013	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	HG Energy, LLC	2014	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	HG Energy, LLC	2015	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	HG Energy, LLC	2016	0												
4708700894	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Production Water Information: (Volumes in Gallons)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_WTR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700894	HG Energy, LLC	2016	0												
4708700894	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700894	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

There is no Stratigraphy data for this well

Wireline (E-Log) Information:

* Scanned/Raster Log Information:

API	STATUS	LOG_TOP	LOG_BOT	DEEPEST_FML	LOGS_AVAIL	SCAN	GR_TOP	GR_BOT	D_TOP	D_BOT	N_TOP	N_BOT	L_TOP	L_BOT	T_TOP	T_BOT	S_TOP	S_BOT	O_TOP	O_BOT	INCH2	IN
4708700894	Regular Entry	2195	2323		G,D,C	Y	2195	2323	2195	2323									2218	2323	N	Y

Scanned/Raster Comment: *logs: caliper

* There is no Digitized/LAS Log data for this well

Downloadable Log Images/Data: We advise you to save the scanned log or digitized log file(s) to your PC for viewing. To do so, right-click the file of interest and select the save option. Then you can direct the file to a location of your choice. Please note the scanned log images vary in size and some may take several minutes to download.

Quick Reference Guide for Log File Names For more info about WVGES scanned logs click [here](#)

geologic log types:

- d density (includes bulk density, compensated density, density, density porosity, grain density, matrix density, etc.)
- e photoelectric adsorption (PE or Pe, etc.)
- g gamma ray
- i induction (includes dual induction, medium induction, deep induction, etc.)
- l laterolog
- m dipmeter
- n neutron (includes neutron porosity, sidewall neutron—SWN, etc.)
- o other¹
- s sonic or velocity
- t temperature (includes borehole temperature, BHT, differential temperature, etc.)
- z spontaneous potential or potential

mechanical log types:

- b cement bond
- c caliper
- o other¹
- p perforation depth control or perforate

¹other logs may include, but are not limited to, such curves as audio, bit size, CCL—casing collar locator, continuous meter, directional survey, gas deflector, guard, NCTL—Nuclear Cement Top Locator, radioactive tracer, tension

There is no Plugging data for this well

There is no Sample data for this well



4708700894

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION 46

Quadrangle SPENCERPermit No. ROA-894

WELL RECORD

Oil or Gas Well Oil & Gas
(KIND)Company SOUTH PENN OIL COMPANYAddress P. O. Box 1588, Parkersburg, W. Va.Farm Hm. Kaufman Acres 800Location (waters) Millstone RunWell No. 5 Elev. 1117.84District Smithfield County RoaneThe surface of tract is owned in fee by Roy H. RhodesSpencer Auto Route Address Spencer, W. Va.Mineral rights are owned by Olive O. Oberdorf, et al.1635 Hyde Park Blvd. 1 Address Chicago 15, IllinoisDrilling commenced June 15, 1962Drilling completed July 25, 1962

Date Shot From To

With

Open Flow 10ths Water in Inch10ths Merc. in InchVolume Insufficient to Test Cu. Ft.Rock Pressure None lbs. hrs.Oil 3 Gallons bbls. 1st 24 hrs.


WELL ACIDIZED

WELL FRACTURED 7/30/62 by Halliburton CompanyRESULT AFTER TREATMENT Gas 30,000 Cu. Ft. Daily
Oil 6 Bbls. DailyROCK PRESSURE AFTER TREATMENT 350 Lbs. 3000

Fresh Water Feet

Salt Water Feet

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
ISoil			3300	3315	OIL & GAS	3300-3315	
KConductor			3315	3315			
Sand			15	60			
Red Rock			60	105			
ISlate			105	124			
ISand			124	154			
2969			154	185	Water, Fresh	124-154	3Bailer/24 Hr.
Slate			154	185			
ISand			185	236			
Red Rock			236	242			
Slate			242	277			
Red Rock			277	318			
Sand			318	394			
Red Rock			394	422			
Slate			422	446			
Red Rock			446	514			
Slate			514	543			
Red Rock			543	555			
Sand			555	570			
Red Rock			570	585			
Sand			585	664			
Slate			664	762			
Red Rock			762	784			
Slate			784	792			
Sand			792	832			
2976			832	861	Water, Fresh	825	1/4 Bbl./Hr.
Red Rock			861	879			
Sand			879	924			
Red Rock							



4708700894

Formation	Color	Hard or Soft	Top 46	Bottom	Oil, Gas or Water	Depth Found	Remarks
Slate			924	940			
Red Rock			940	955			
Slate			955	1001			
Red Rock			1001	1048			
Slate			1048	1071			
Pink Rock			1071	1081			
Slate			1081	1167			
Sand			1167	1276			
Slate			1276	1352			
Sand			1352	1480			
Slate			1480	1518			
Sand			1518	1583			
Slate			1583	1622			
Sand			1622	1687			
Slate & Shells			1687	1851			
Sand			1851	1989			
Slate & Shells			1989	2039	Water, Salt	1900	Hole Full
Sand			2039	2091			
Little Lime			2091	2115			
Slate			2115	2118			
Sand			2118	2120			
Pencil Cave			2120	2131			
Big Lime			2131	2247			
5 1/2" Casing			2247	2247	Oil	2175-2181	Show Only
Keener Sand			2247	2261			
Big Injun			2261	2288	Oil & Gas	2261-2282	Ins. to Test
Blue Lime & Slate			2288	2314			
TOTAL DEPTH				2314			
FILLED BACK WITH STONE & MUD			2314	2281			
TOTAL DEPTH				2281			Final

Date August 15, 1962

APPROVED SOUTH PENN. OIL COMPANY, Owner

By George W. Wilsman
George W. Wilsman (Title) Land Agent



Select County: (087) Roane

Enter Permit #: 954

Get Data

Reset

Select datatypes: ☐ (Check All)

☒ Location

☒ Owner/Completion☒ Pay/Show/Water☒ **Produkt**

 **Stratigraphy**

☒ Logs

✓ Plugging

 **Sample**

☒ Blm Hole Loc

[Table Descriptions](#)
[County Code Translation](#)
[Permit-Numbering Series](#)
[Usage Notes](#)
[Contact Information](#)
[Disclaimer](#)
[WVGES Main](#)
["Pipeline-Plus" Now](#)

Wines 3

WV Geological & Economic Survey:

Well: County = 87 Permit = 954 [Link to all digital records for well](#)

Report Time: Thursday, April 03, 2025 2:19:46 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX_DISTRICT	QUAD_75	QUAD_15	LAT_DD	LOD_DD	UTME	UTMN
4708700954	Roane	954	Spencer	Spencer	Spencer	38.759137	-81.268891	476637.5	4290082.6

There is no Bottom Hole Location data for this well

Owner Information:

API	CMP_DT	SUFFIX	STATUS	SURFACE_OWNER	WELL_NUM	CO_NUM	LEASE	LEASE_NUM	MINERAL_OWN	OPERATOR_AT_COMPLETION	PROP_VD	PROP_TRGT_FM	TFM_EST_PR
4708700954	8/8/1963	Original Loc	Completed	Cora & C H Wine	6					J & B Oil Co.			

Completion Information:

API	CMP_DT	SPUD_DT	ELEV	DATUM	FIELD	DEEPEST_FM	DEEPEST_FMT	INITIAL_CLASS	FINAL_CLASS	TYPE	RIG	CMP_MTHD	TVD	TMD	NEW_FTG	KOD	G_BEF
4708700954	8/8/1963	6/13/1963	1092	Ground Level	Clvr-Rsh Rn	Big Injun (Price&eq)	Big Injun (Price&eq)	Development Well	Development Well	Oil and Gas	unknown	Acid+Frac	2180		2180		0

Pay/Show/Water Information:

API	CMP_DT	ACTIVITY	PRODUCT	SECTION	DEPTH_TOP	FM_TOP	DEPTH_BOT	FM_BOT	G_BEFF	G_AFT	O_BEFF	O_AFT	WATER_QNTY
47080700954	8/8/1963	Water	Fresh Water	Vertical			120						0
47080700954	8/8/1963	Water	Salt Water	Vertical			1830						0
47080700954	8/8/1963	Pav	Oil & Gas	Vertical			2180	Big Injun (Price&eq	0	0			0

Production Gas Information: (Volumes in Mcf)

API	PRODUCING OPERATOR	PRD_YEAR	ANN_GAS	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
4708700954	J & B Drilling Operation	1983	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700954	McKown Farm	1987	34	0	0	0	0	0	0	0	8	8	6	7	5
4708700954	McKown Farm	1988	445	37	64	52	45	11	0	0	53	48	49	46	40
4708700954	McKown Farm	1989	495	43	32	44	46	47	0	38	58	55	52	51	29
4708700954	McKown Farm	1990	527	50	46	50	46	44	30	19	51	48	48	49	46
4708700954	McKown Farm	1991	466	45	40	47	44	49	33	1	38	42	41	43	43
4708700954	McKown Farm	1992	487	41	36	39	43	44	39	41	46	44	40	31	43
4708700954	McKown Farm	1993	480	39	42	44	25	39	37	65	35	37	41	39	37
4708700954	McKown, C. I. & Son, Inc.	1994	467	19	38	48	42	44	30	35	49	38	46	41	37
4708700954	McKown, C. I. & Son, Inc.	1995	517	46	44	48	40	46	44	43	36	41	45	38	46
4708700954	McKown, C. I. & Son, Inc.	1996	487	34	24	24	36	43	104	45	21	44	41	41	30
4708700954	McKown, C. I. & Son, Inc.	1997	450	34	33	31	43	34	44	39	38	25	37	44	48
4708700954	McKown, C. I. & Son, Inc.	1998	458	30	36	34	46	24	67	36	33	43	38	31	40
4708700954	McKown, C. I. & Son, Inc.	1999	502	24	32	35	33	33	15	40	81	69	73	35	32
4708700954	McKown, C. I. & Son, Inc.	2002	331	31	28	27	30	30	28	29	29	25	27	21	27
4708700954	McKown, C. I. & Son, Inc.	2004	365	29	28	30	38	33	31	30	28	28	32	29	29
4708700954	McKown, C. I. & Son, Inc.	2005	364	27	23	28	34	35	35	28	34	32	32	30	26
4708700954	McKown, C. I. & Son, Inc.	2006	319	27	23	29	24	30	29	28	27	26	28	24	24
4708700954	McKown, C. I. & Son, Inc.	2007	287	20	18	25	26	24	24	24	21	27	30	24	24
4708700954	McKown, C. I. & Son, Inc.	2008	223	21	19	21	18	24	20	21	16	11	10	21	21
4708700954	McKown, C. I. & Son, Inc.	2009	254	17	17	19	20	26	24	21	20	24	23	23	20
4708700954	McKown, C. I. & Son, Inc.	2010	229	18	16	21	23	24	20	19	19	17	20	17	15
4708700954	McKown, C. I. & Son, Inc.	2011	224	12	14	21	21	21	23	21	16	21	21	19	14
4708700954	McKown, C. I. & Son, Inc.	2013	170	10	15	19	19	18	15	10	13	15	14	17	5
4708700954	McKown, C. I. & Son, Inc.	2014	153	13	11	11	14	15	12	13	13	12	12	11	16
4708700954	McKown, C. I. & Son, Inc.	2015	187	14	13	13	13	18	19	17	18	17	16	17	12
4708700954	McKown, C. I. & Son, Inc.	2016	107	12	12	13	13	16	12	7	4	3	2	7	6
4708700954	McKown, C. I. & Son, Inc.	2017	194	13	14	18	62	12	11	12	10	8	11	12	11
4708700954	McKown, C. I. & Son, Inc.	2018	94	3	15	11	11	8	8	9	1	3	7	8	10
4708700954	McKown, C. I. & Son, Inc.	2019	75	8	8	10	9	10	5	7	6	3	1	3	5
4708700954	McKown, C. I. & Son, Inc.	2020	55	6	5	12	13	10	5	2	2	0	0	0	0
4708700954	McKown, C. I. & Son, Inc.	2021	105	0	3	15	15	13	12	11	7	7	7	8	7
4708700954	McKown, C. I. & Son, Inc.	2022	105	6	15	12	6	8	12	10	7	9	6	7	7
4708700954	McKown, C. I. & Son, Inc.	2023	40	7	4	3	3	3	4	3	3	2	3	3	3

Production Oil Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

[illegible]

Production NGL Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

[illegible]

4708700954	McKown, C. I. & Son, Inc.	2022	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700954	McKown, C. I. & Son, Inc.	2023	0	0	0	0	0	0	0	0	0	0	0	0	0	0

4708700954

Production Water Information: (Volumes in Gallons)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_WTR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700954	McKown, C. I. & Son, Inc.	2016	0												
4708700954	McKown, C. I. & Son, Inc.	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700954	McKown, C. I. & Son, Inc.	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700954	McKown, C. I. & Son, Inc.	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700954	McKown, C. I. & Son, Inc.	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700954	McKown, C. I. & Son, Inc.	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700954	McKown, C. I. & Son, Inc.	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Stratigraphy Information:

API	SUFFIX	FM	FM_QUALITY	DEPTH_TOP	DEPTH_QUALITY	THICKNESS	THICKNESS_QUALITY	ELEV	DATUM
4708700954	Original Loc	Greenbrier Group	Past WVGES Staff Geologist	2002	Reasonable	168	Reasonable	1092	Ground Level
4708700954	Original Loc	Keener	Well Record	2165	Reasonable	5	Reasonable	1092	Ground Level
4708700954	Original Loc	Big Injun (Price&eg)	Past WVGES Staff Geologist	2170	Reasonable	0	Reasonable	1092	Ground Level

Wireline (E-Log) Information:

- * There is no Scanned/Raster Log data for this well
- * There is no Digitized/LAS Log data for this well
- * There is no Scanned or Digital Logs available for download

There is no Plugging data for this well

There is no Sample data for this well

4708700954



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION 20

Rotary ☒
Spudder ☐
Cable Tools ☒

Quadrangle SpencerPermit No. ROA-954

WELL RECORD

Storage ☐Oil or Gas Well Comb.
(KIND)

Company J & B Oil Company, Inc.
Address 339 1/2 Market Street, Spencer, W. Va.
Farm Cora A. & C. H. Wines Acres 90.33

Location (waters) Boggs Fork
Well No. 6 Elev. 1091.81

District Spencer County Roane

The surface of tract is owned in fee by C. H. Wines
Spencer, W. Va. Address

Mineral rights are owned by
Address

Drilling commenced June 13, 1963Drilling completed August 8, 1963Date Shot 8/2/63 From To

With


Open Flow /10ths Water in Inch

/10ths Merc. in Inch

Volume Cu. Ft.

Rock Pressure 300 lbs. 2 1/2 hrs.Oil 15 bbls., 1st 24 hrs.WELL ACIDIZED NoWELL FRACTURED 42,000 Gals. Water - 55,000 lbs. sand500 Gals. Mud Acid - 120 lbs. J-100RESULT AFTER TREATMENT 30 bbls. oil - 40,000 cu. ft. gasROCK PRESSURE AFTER TREATMENT 300# 24 hoursFresh Water 120 Feet Salt Water 1830 Feet

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Red Mud			0	25			
Red Rock			25	70			
Slate & Shells			70	100			
Sand			100	190			
Red Rock			190	230			
Slate & Shells			230	262			
Sand			262	312			
Red Rock			312	340			
Slate & Shells			340	350			
Red Rock			350	385			
Slate & Shells			385	420			
Red Rock			420	480			
Slate & Shells			480	540			
Sand			540	580			
Slate & Shells			580	595			
Sand			595	618			
Red Rock			618	640			
Slate & Shells			640	675			
Red Rock			675	700			
Sand			700	745			
Red Rock			745	828			
Slate & Shells			828	905			
Red Rock			905	940			
Slate & Shells			940	996			
Sand			996	1012			
Slate & Shells			1012	1090			
Sand			1090	1170			
Slate & Shells			1170	1250			
Sand			1250	1345			
Slate & Shells			1345	1477			



4708700954

Formation	Color	Hard or Soft	Top 20	Bottom	Oil, Gas or Water	Depth Found	Remarks
21540 S 2H	LT		1392	1444			
Sand			1477	1500			
Slate & Shells			1500	1570			
X Lime			1570	1605			
Slate & Shells			1605	1650			
Sand			1650	1670			
Slate & Shells			1670	1783			
Sand			1783	1915			
Lime			1915	1945			
Sand			1945	1957			
Lime			1957	1990			
Sand			1990	2002			
Lime			2002	2105			
Keener Sand			2105	2170			
Sand			2170	2180			
2180 S 2H	LT		2200	2200			
2200			2210	2210			
2210 S 2H	LT		2220	2220			
2220			2230	2230			
2230 S 2H	LT		2240	2240			
2240			2250	2250			
2250 S 2H	LT		2260	2260			
2260			2270	2270			
2270 S 2H	LT		2280	2280			
2280			2290	2290			
2290 S 2H	LT		2300	2300			
2300			2310	2310			
2310 S 2H	LT		2320	2320			
2320			2330	2330			
2330 S 2H	LT		2340	2340			
2340			2350	2350			
2350 S 2H	LT		2360	2360			
2360			2370	2370			
2370 S 2H	LT		2380	2380			
2380			2390	2390			
2390 S 2H	LT		2400	2400			
2400			2410	2410			
2410 S 2H	LT		2420	2420			
2420			2430	2430			
2430 S 2H	LT		2440	2440			
2440			2450	2450			
2450 S 2H	LT		2460	2460			
2460			2470	2470			
2470 S 2H	LT		2480	2480			
2480			2490	2490			
2490 S 2H	LT		2500	2500			
2500			2510	2510			
2510 S 2H	LT		2520	2520			
2520			2530	2530			
2530 S 2H	LT		2540	2540			
2540			2550	2550			
2550 S 2H	LT		2560	2560			
2560			2570	2570			
2570 S 2H	LT		2580	2580			
2580			2590	2590			
2590 S 2H	LT		2600	2600			
2600			2610	2610			
2610 S 2H	LT		2620	2620			
2620			2630	2630			
2630 S 2H	LT		2640	2640			
2640			2650	2650			
2650 S 2H	LT		2660	2660			
2660			2670	2670			
2670 S 2H	LT		2680	2680			
2680			2690	2690			
2690 S 2H	LT		2700	2700			
2700			2710	2710			
2710 S 2H	LT		2720	2720			
2720			2730	2730			
2730 S 2H	LT		2740	2740			
2740			2750	2750			
2750 S 2H	LT		2760	2760			
2760			2770	2770			
2770 S 2H	LT		2780	2780			
2780			2790	2790			
2790 S 2H	LT		2800	2800			
2800			2810	2810			
2810 S 2H	LT		2820	2820			
2820			2830	2830			
2830 S 2H	LT		2840	2840			
2840			2850	2850			
2850 S 2H	LT		2860	2860			
2860			2870	2870			
2870 S 2H	LT		2880	2880			
2880			2890	2890			
2890 S 2H	LT		2900	2900			
2900			2910	2910			
2910 S 2H	LT		2920	2920			
2920			2930	2930			
2930 S 2H	LT		2940	2940			
2940			2950	2950			
2950 S 2H	LT		2960	2960			
2960			2970	2970			
2970 S 2H	LT		2980	2980			
2980			2990	2990			
2990 S 2H	LT		3000	3000			
3000			3010	3010			
3010 S 2H	LT		3020	3020			
3020			3030	3030			
3030 S 2H	LT		3040	3040			
3040			3050	3050			
3050 S 2H	LT		3060	3060			
3060			3070	3070			
3070 S 2H	LT		3080	3080			
3080			3090	3090			
3090 S 2H	LT		3100	3100			
3100			3110	3110			
3110 S 2H	LT		3120	3120			
3120			3130	3130			
3130 S 2H	LT		3140	3140			
3140			3150	3150			
3150 S 2H	LT		3160	3160			
3160			3170	3170			
3170 S 2H	LT		3180	3180			
3180			3190	3190			
3190 S 2H	LT		3200	3200			
3200			3210	3210			
3210 S 2H	LT		3220	3220			
3220			3230	3230			
3230 S 2H	LT		3240	3240			
3240			3250	3250			
3250 S 2H	LT		3260	3260			
3260			3270	3270			
3270 S 2H	LT		3280	3280			
3280			3290	3290			
3290 S 2H	LT		3300	3300			
3300			3310	3310			
3310 S 2H	LT		3320	3320			
3320			3330	3330			
3330 S 2H	LT		3340	3340			
3340			3350	3350			
3350 S 2H	LT		3360	3360			
3360			3370	3370			
3370 S 2H	LT		3380	3380			
3380			3390	3390			
3390 S 2H	LT		3400	3400			
3400			3410	3410			
3410 S 2H	LT		3420	3420			
3420			3430	3430			
3430 S 2H	LT		3440	3440			
3440			3450	3450			
3450 S 2H	LT		3460	3460			
3460			3470	3470			
3470 S 2H	LT		3480	3480			
3480			3490	3490			
3490 S 2H	LT		3500	3500			
3500			3510	3510			
3510 S 2H	LT		3520	3520			
3520			3530	3530			
3530 S 2H	LT		3540	3540			
3540			3550	3550			
3550 S 2H	LT		3560	3560			
3560			3570	3570			
3570 S 2H	LT		3580	3580			
3580			3590	3590			
3590 S 2H	LT		3600	3600			
3600			3610	3610			
3610 S 2H	LT		3620	3620			
3620			3630	3630			
3630 S 2H	LT		3640	3640			
3640			3650	3650			
3650 S 2H	LT		3660	3660			
3660			3670	3670			
3670 S 2H	LT		3680	3680			
3680			3690	3690			
3690 S 2H	LT		3700	3700			
3700			3710	3710			
3710 S 2H	LT		3720	3720			
3720			3730	3730			
3730 S 2H	LT		3740	3740			
3740			3750	3750			
3750 S 2H	LT		3760	3760			
3760			3770	3770			
3770 S 2H	LT		3780	3780			
3780			3790	3790			
3790 S 2H	LT		3800	3800			
3800			3810	3810			
3810 S 2H	LT		3820	3820			
3820			3830	3830			
3830 S 2H	LT		3840	3840			
3840			3850	3850			
3850 S 2H	LT		3860	3860			
3860			3870	3870			
3870 S 2H	LT		3880	3880			
3880			3890	3890			
3890 S 2H	LT		3900	3900			
3900			3910	3910			
3910 S 2H	LT		3920	3920			
3920			3930	3930			
3930 S 2H	LT		3940	3940			
3940			3950	3950			
3950 S 2H	LT		3960	3960			
3960			3970	3970			
3970 S 2H	LT		3980	3980			
3980			3990	3990			
3990 S 2H	LT		4000	4000			
4000			4010	4010			
4010 S 2H	LT		4020	4020			
4020			4030	4030			
4030 S 2H	LT		4040	4040			
4040			4050	4050			
4050 S 2H	LT		4060	4060			
4060			4070	4070			
4070 S 2H	LT		4080	4080			
4080			4090	4090			
4090 S 2H	LT		4100	4100			
4100			4110	4110			
4110 S 2H	LT		4120	4120			
4120			4130	4130			
4130 S 2H	LT		4140	4140			
4140			4150	4150			
4150 S 2H	LT		4160	4160			
4160			4170	4170			
4170 S 2H	LT		4180	4180			
4180			4190	4190			
4190 S 2H	LT		4200	4200			
4200			4210	4210			
4210 S 2H	LT		4220	4220			
4220			4230	4230			
4230 S 2H	LT		4240	4240			



"Pipeline"

Select County: (087) Roane

Select datatypes: ☐ (Check All)

Enter Permit #: 984

Get Data

Reset

☒ Location☒ Owner/Completion☒ Pay/Show/Water☐ Production☒ Stratigraphy☒ Logs☒ Plugging☒ Sample☒ Btm Hole Loc

Table Definitions
County Code Translations
Permit-Numbering Series
Usage Notes
Contact Information
Disclaimer
WVGES Main
"Pipeline-Plus" New

W-5

WV Geological & Economic Survey:

Well: County = 087 Permit = 984 [Link to all digital records for well](#)

Report Time: Thursday, April 03, 2025 2:18:40 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX_DISTRICT	QUAD_75	LAT_DD	LON_DD	UTME	UTMN
4708700984	Roane	984	Smithfield	Spencer	38.753886	-81.268819	478642.1	4289499.9

There is no Bottom Hole Location data for this well

Owner Information:

API	CMP_DT	SUFFIX	STATUS	SURFACE_OWNER	WELL_NUM	CO_NUM	LEASE	LEASE_NUM	MINERAL_OWN	OPERATOR_AT_COMPLETION	PROP_VD	PROP_TRGT_FM	TFM_EST
4708700984	10/27/1963	Original Loc	Completed	W Kaufman, E Walbrown		W-5			Alfred M Oppenheimer II	Wolf's Head Oil Refining Co., Inc.			
4708700984	12/20/1972	Worked Over	Completed	W Kaufman, H Rhodes		W-5			Alfred M Oppenheimer II	Pennzoil Company			

Completion Information:

API	CMP_DT	SPUD_DT	ELEV	DATUM	FIELD	DEEPEST FM	DEEPEST FMT	INITIAL_CLASS	FINAL_CLASS	TYPE	RIG	CMP_MTHD	TVD	TMD	NEW_FTG	KOD	G_E
4708700984	10/27/1963	10/19/1963	1040	Ground Level	Chv-Rsh Rn	Undf PRICE blw INJN	Big Injun (Price&eq)	Development Well	Development Well	Oil and Gas	Rotary	Fractured	2270			2270	
4708700984	12/20/1972	-/-	1040	Ground Level	Chv-Rsh Rn	Undf PRICE blw INJN	Big Injun (Price&eq)	Development Well	Development Well	Oil	unknown	Acid+Frac	2270			0	

Pay/Show/Water Information:

API	CMP_DT	ACTIVITY	PRODUCT	SECTION	DEPTH_TOP	FM_TOP	DEPTH_BOT	FM_BOT	G_BEFF	G_AFT	O_BEFF	O_AFT	WATER_QNTY
4708700984	12/20/1972	Pay	Oil	Vertical	2098	Big Lime	2115	Big Lime	0	7			
4708700984	10/27/1963	Show	Gas	Vertical	2102	Big Lime	2118	Big Lime	0	0			
4708700984	10/27/1963	Pay	Gas	Vertical	2190	Big Injun (Price&eq)	2210	Big Injun (Price&eq)	0	35			
4708700984	10/27/1963	Pay	Oil	Vertical	2190	Big Injun (Price&eq)	2210	Big Injun (Price&eq)	0	30			

Production Gas Information: (Volumes in Mcf)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_GAS	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700984	Pennzoil Company	1981	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	Pennzoil Company	1982	999	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	Pennzoil Company	1983	1,493	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	Pennzoil Company	1984	1,470	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	Pennzoil Products Company	1989	1,118	146	80	91	66	131	61	65	103	105	75	94	91
4708700984	Pennzoil Products Company	1990	672	103	77	109	91	58	70	52	24	19	30	21	18
4708700984	Pennzoil Products Company	1991	247	26	20	13	10	19	21	23	21	29	23	16	26
4708700984	Pennzoil Products Company	1992	168	22	42	25	17	20	16	0	0	16	10	0	0
4708700984	Pennzoil Products Company	1993	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	Pennzoil Products Company	1994	17	0	0	0	13	4	0	0	0	0	0	0	0
4708700984	Pennzoil Products Company	1995	277	0	0	0	0	0	41	37	41	44	38	35	41
4708700984	Pennzoil Products Company	1996	343	21	1	37	44	32	38	33	0	28	27	41	41
4708700984	Pennzoil Products Company	1997	352	28	28	31	30	25	8	34	36	6	32	50	44
4708700984	Pennzoil Products Company	1998	396	37	52	43	40	46	29	24	21	22	20	22	
4708700984	Pennzoil Products Company	1999	124	6	0	0	22	15	0	0	12	12	21	22	14
4708700984	East Resources, Inc.	2000	150	13	14	10	0	17	8	0	20	14	16	16	22
4708700984	East Resources, Inc.	2001	276	7	30	22	24	26	20	23	29	31	31	7	
4708700984	East Resources, Inc.	2002	326	29	26	23	23	28	27	29	30	32	27	18	34
4708700984	East Resources, Inc.	2003	79	20	12	0	0	23	6	0	0	0	0	0	18
4708700984	East Resources, Inc.	2004	56	0	0	0	0	0	0	0	0	0	29	27	0
4708700984	East Resources, Inc.	2005	383	22	22	21	24	40	34	29	39	41	40	33	38
4708700984	East Resources, Inc.	2006	509	38	37	41	41	45	44	48	33	36	43	50	53
4708700984	East Resources, Inc.	2007	430	51	38	42	30	27	23	27	34	31	32	49	46
4708700984	East Resources, Inc.	2008	479	40	39	40	37	41	39	40	41	41	45	38	38
4708700984	East Resources, Inc.	2010	506	49	35	40	42	43	40	41	41	40	46	47	42
4708700984	East Resources, Inc.	2011	547	44	41	47	47	47	43	47	48	46	48	44	45
4708700984	HG Energy, LLC	2012	525	40	35	39	40	44	40	28	52	57	57	47	46
4708700984	HG Energy, LLC	2013	533	48	35	38	39	51	47	42	48	45	50	44	46
4708700984	HG Energy, LLC	2014	363	42	37	42	36	1	9	15	35	42	42	39	43
4708700984	HG Energy, LLC	2015	464	37	32	33	37	42	41	42	40	40	40	37	43
4708700984	HG Energy, LLC	2016	467	39	38	39	39	41	38	40	38	39	39	39	38
4708700984	HG Energy, LLC	2017	404	37	32	33	31	34	30	32	32	34	36	37	36
4708700984	HG Energy, LLC	2018	426	36	33	38	36	38	37	39	36	34	33	32	34
4708700984	HG Energy, LLC	2019	365	35	32	34	31	24	24	26	32	30	33	34	30
4708700984	HG Energy, LLC	2020	358	35	31	35	17	29	32	33	32	28	28	29	29
4708700984	HG Energy, LLC	2021	228	10	8	9	13	15	18	26	26	25	25	22	31
4708700984	HG Energy, LLC	2022	339	28	21	29	27	29	28	31	31	29	29	29	28
4708700984	Delta Helix Energy, LLC	2023	58	0	0	0	0	0	0	0	0	0	0	30	28
4708700984	HG Energy, LLC	2023	313	30	27	31	32	32	30	32	32	34	33	0	0

Production Oil Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_OIL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700984	Pennzoil Company	1981	440	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	Pennzoil Company	1982	307	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	Pennzoil Company	1983	445	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	Pennzoil Company	1984	382	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	Pennzoil Products Company	1989	229	23	15	26	14	12	22	23	13	20	22	20	19
4708700984	Pennzoil Products Company	1990	114	22	19	14	18	10	5	4	5	4	4	5	4
4708700984	Pennzoil Products Company	1991	51	3	2	4	4	4	4	5	4	3	5	4	9
4708700984	Pennzoil Products Company	1992	18	6	4	0	3	0	0	3	2	0	0	0	0
4708700984	Pennzoil Products Company	1993	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	Pennzoil Products Company	1994	4	0	3	1	0	0	0	0	0	0	0	0	0
4708700984	Pennzoil Products Company	1995	59	0	0	0	9	8	8	9	8	8	9	0	0
4708700984	Pennzoil Products Company	1996	93	10	12	8	9	7	0	6	9	9	9	7	7
4708700984	Pennzoil Products Company	1997	78	7	8	7	2	9	9	1	7	8	7	6	7
4708700984	Pennzoil Products Company	1998	64	9	8	8	9	3	0	0	0	0	0	19	8
4708700984	Pennzoil Products Company	1999	2	2	0	0	0	0	0	0	0	0	0	0	0
4708700984	East Resources, Inc.	2000	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	East Resources, Inc.	2001	102	0	19	9	8	10	8	7	6	8	10	8	9
4708700984	East Resources, Inc.	2002	98	8	10	7	7	9	9	12	8	9	7	4	8
4708700984	East Resources, Inc.	2003	23	9	4	0	0	8	2	0	0	0	0	0	0
4708700984	East Resources, Inc.	2004	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	East Resources, Inc.	2005	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	East Resources, Inc.	2006	2	0	0	0	0	0	0	0	0	2	0	0	0
4708700984	East Resources, Inc.	2007	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	East Resources, Inc.	2008	54	0	0	8	8	6	5	5	5	4	5	4	4
4708700984	East Resources, Inc.	2010	111	15	12	12	12	0	9	12	7	4	10	10	8
4708700984	East Resources, Inc.	2011	31	6	0	0	0	0	0	0	0	0	0	10	15
4708700984	HG Energy, LLC	2012	113	8	15	12	9	10	7	3	9	6	22	12	0
4708700984	HG Energy, LLC	2013	144	17	22	17	16	10	2	13	10	10	11	8	8
4708700984	HG Energy, LLC	2014	111	8	11	12	12	12	11	9	11	9	8	4	4
4708700984	HG Energy, LLC	2015	56	5	3	4	5	8	4	5	4	4	5	4	5
4708700984	HG Energy, LLC	2016	51	4	4	5	4	4	5	4	5	4	4	3	5
4708700984	HG Energy, LLC	2017	49	4	3	3	5	5	3	4	5	4	4	5	4
4708700984	HG Energy, LLC	2018	50	5	4	4	4	5	4	4	5	4	5	2	4
4708700984	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

4708700984	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0	0
------------	----------------	------	---	---	---	---	---	---	---	---	---	---	---	---	---	---

4708700984

Production NGL Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_NGL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700984	HG Energy, LLC	2013	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	HG Energy, LLC	2014	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	HG Energy, LLC	2015	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	HG Energy, LLC	2016	0												
4708700984	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Production Water Information: (Volumes in Gallons)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_WTR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700984	HG Energy, LLC	2016	0												
4708700984	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700984	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Stratigraphy Information:

API	SUFFIX	FM	FM_QUALITY	DEPTH	TOP	DEPTH_QUALITY	THICKNESS	THICKNESS_QUALITY	ELEV	DATUM
4708700984	Original Loc	Greenbrier Group	Past WVGES Staff Geologist	2060	Reasonable	130	Reasonable		1040	Ground Level
4708700984	Original Loc	Big Lime	Well Record	2080	Reasonable	110	Reasonable		1040	Ground Level
4708700984	Original Loc	Keener	Well Record	2170	Reasonable	20	Reasonable		1040	Ground Level
4708700984	Original Loc	Big Injun (Price&eq)	Past WVGES Staff Geologist	2190	Reasonable	20	Reasonable		1040	Ground Level
4708700984	Original Loc	Undf PRICE b/w INJN	Well Record	2210	Reasonable	0	Reasonable		1040	Ground Level

Wireline (E-Log) Information:

* There is no Scanned/Raster Log data for this well

* There is no Digitized/LAS Log data for this well

Downloadable Log Images/Data: We advise you to save the scanned log or digitized log file(s) to your PC for viewing. To do so, right-click the file of interest and select the save option. Then you can direct the file to a location of your choice. Please note the scanned log images vary in size and some may take several minutes to download.

Quick Reference Guide for Log File Names For more info about WVGES scanned logs click [here](#)

geologic log types:

- d density (includes bulk density, compensated density, density, density porosity, grain density, matrix density, etc.)
- e photoelectric adsorption (PE or Pe, etc.)
- g gamma ray
- i induction (includes dual induction, medium induction, deep induction, etc.)
- l laterolog
- m dipmeter
- n neutron (includes neutron porosity, sidewall neutron--SWN, etc.)
- o other¹
- s sonic or velocity
- t temperature (includes borehole temperature, BHT, differential temperature, etc.)
- z spontaneous potential or potential

mechanical log types:

- b cement bond
- c caliper
- o other¹
- p perforation depth control or perforate

¹other logs may include, but are not limited to, such curves as audio, bit size, CCL--casing collar locator, continuous meter, directional survey, gas detector, guard, NCTL--Nuclear Cement Top Locator, radioactive tracer, tension

There is no Plugging data for this well

There is no Sample data for this well



4708700984

CGOIRG A. HITCHCOCK (INC. VROC)

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

NOV 1963

Quadrangle SPENCERPermit No. ROA-984

WELL RECORD

Oil or Gas Well O & G

(KIND)

Company WOLF'S HEAD OIL REFINING COMPANY, INC.Address P. O. Box 1588, Parkersburg, W. Va.Farm Wm. Kaufman Acres 800Location (waters) Millstone RunWell No. W-5 Elev. 1040.47District Smithfield County RoaneThe surface of tract is owned in fee by Eugene WalbrownOtto Route Address Spencer, W. Va.Mineral rights are owned by Alfred M. Oppenheimer II.300 South Lang Avenue Address Pittsburgh 8, Pa.Drilling commenced October 19, 1963Drilling completed October 27, 1963Date Shot - From - To -With -Open Flow /10ths Water in - Inch/10ths Merc. in - InchVolume Show Oil & Gas (Drilled w/Rotary) - Cu. Ft.Rock Pressure - lbs. - hrs.Oil - bbls., 1st 24 hrs.WELL ACIDIZED -WELL FRACTURED 11/8/63


RESULT AFTER TREATMENT

Gas = 33,000 Cu. Ft.Oil = 30 Bbls.

ROCK PRESSURE AFTER TREATMENT

480 Lbs.Fresh Water -Feet -Salt Water -Feet -

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas, or Water	Depth	Remarks
Shale & Shell			0	65			
Red Rock			65	155			
Sand			155	260			
Sand & Shale			260	365			
Shale & Red Rock			365	535			
Sand & Shale			535	1325			
Sand			1325	1370			
Shale			1370	1405			
Sand & Shale			1405	1996			
Sand & Lime			1996	2060			
Big Lime			2060	2170	Oil	2102-2118	Show Only
Keener Sand			2170	2190			
Big Injun			2190	2210			
Sand & Lime			2210	2233	Oil & Gas	2190-2210	
Shale & Lime			2233	2270			
4 1/2" Casing				2270			
TOTAL DEPTH				2270			



4708700984

[illegible]

OFFICE OF THE ATTORNEY GENERAL
RECEIVED
Date November 22, 1963
Name of Fugitive WOLF'S HEAD OIL REFINING COMPANY, INC.
APPROVED George W. Vilsman Owner
By George W. Vilsman
George W. Vilsman, (Title) Agent

SOUTHERN SUGAR COMPANY

NEW WELL REPORT

4708700984

W-5

12 NO 41219 300 ACRES
 WORKING DISTRICT Spencer # 1
Wm. Lawman FARM
 WELL NO. W-5 N. 47 E. 30
Smithfield DISTRICT OR
Reams COUNTY. QUAD.
 TOWNSHIP
 LOCATION MADE September 20, 19 65
 DRILLING COMMENCED October 17, 19 65
 RIG COMMENCED October 16, 19 65
 DRILLING COMPLETED October 27, 19 65
 RIG COMPLETED October 19, 19 65
 DEPTH 2270' SAND. Rig Injun
 RIG CONTRACTOR Dennings Drilling Co., Inc.
 DRILLING CONTRACTOR Dennings Drilling Co., Inc.
 ELEVATION: FLOOR GROUND 1010.47
 WORK ORDER NO. AFE # W-5-W-Vs.

FORMATION RECORD

KIND	TOP	BOTTOM	STEEL LINE MEAS.	TEST
Shale & Shell	0	65		
Red Rock	65	155		
Sand	155	260	260	
Sand & Shale	260	355		
Shale & RedRock	365	595		
Sand & Shale	585	1325		
Sand	1325	1970		
Shale	1970	1405		
Sand & Shale	1405	1996		
Sand & Lime	1996	2040		
Mg Lime	2040	2170		
M ^c	2102	2118		Show Only
Sand	2170	2190		
Lignum	2190	2210		
Rt. & Gas	2190	2210		
Sand & Lime	2210	2235		
Shale & Lime	2235	2270		
18" Casing		2270	2270	
Total Depth		2270	2270	

(OVER)

4708700984

W-5

NEW WELL REPORT -- CONT'D.

INITIAL TORPEDO RECORD		CASING AND TUBING RECORD					
Date of Shot	SIZE	PUT IN WELL			PULLED OUT		
		TRANSFER NO.	FEET	INCH	TRANSFER NO.	FEET	INCH
Name of Torpedo Co.	8-5/8"	Tally	242	--			
No. of Quarts	4-1/2"	Tally	2270	1			
Length of Shell	2-3/8"						
Diameter of Shell	Tubing	Tally	2270	--			
Length of Anchor							
Top of Shot							
Bottom of Shot							
Feet of Fluid in Hole When Shot							
Results:							

INITIAL PRODUCTION FIRST 24 HOURS		PACKER RECORD			
		KIND	SIZE	DEPTH SET	DATE SET
Open Flow	/10ths Water in _____ Inch	Steel Shoe	8-5/8" OD	240	10-20-63
	/10ths Merc. in _____ Inch	Float Collar	4 1/2" 9.54	2270	10-27-63
Volume	Show Oil & Gas (Drilled w/Rotary) Cu. Ft.	Guide Shoe	4 1/2" 9.54	2270	10-27-63
Rock Pressure	_____ lbs. _____ hrs.				
Oil	*See Electric Log _____ bbls., First 24 hrs.				

ACIDIZATION OR FRACTURING RECORD		CASING CEMENTED	
DATE WELL ACIDIZED _____		From Surface to 1	
DATE WELL FRACTURED <u>11-8-63</u>		8-5/8" SIZE	240 FT. 10-20-63 DA1
NAME OF COMPANY <u>Dowell</u>		4-1/2" SIZE	2270 FT. 10-27-63 DA1
(List below materials used in Acidizing or Fracturing, i.e., Sand, Crude Oil, Gasoline, Water, Kerosene, Mothballs, Acid, etc., giving gallons, barrels and pounds).		SIZE _____ FT. _____ DA1	
Used: 670 Bbls. Oil		USED IN CEMENTING 8-5/8" CASING	
Used: 43,000# Sand		30 Bags - Cement	
Used: 300 Gals. Dowell X-Servise		Cemented by: Gerald D. Jones	
Used: 300 Gals. Mud Acid		USED IN CEMENTING 4-1/2" CASING:	
Used: 40 Gals. Fracflo		65 Bags - Portland Cement	
		500 Gals - Mud Flush	
		1 lb. - Halliburton Weld-A	
		3 - Baker Controllers	
		10 - 5' Sections of Note-Wall	
		Cleaners	
		Cemented by: Halliburton Co.	
BREAKDOWN PRESSURE <u>1300#</u>			
PUMPING PRESSURE <u>2500 to 3150#</u>			
AVERAGE PUMPING RATE/MINUTE <u>20.5 Bbls.</u>			
PUMPING TIME <u>43 Minutes</u>			
RESULT AFTER TREATMENT } GAS <u>35,000</u> CU. FT.			
OIL <u>30</u> BBLS.			
ROCK PRESSURE AFTER TREATMENT <u>400</u> LBS.			

REMARKS: Drilled 10-5/8" Hole from Surface to 240'

Drilled 7-7/8" Hole from 240' to 2270'

Note: Rotary Tools Used

Note: This well was logged by McCullough Tool Company on October 26, 1963.

Note: This well was drilled according to Rule 11, under Section 13, of Article 4, Chapter 22, of the Code of the Department of Mines, Oil and Gas Division.

APPROVED

C. C. C. *[Signature]*

SUPERINTENDENT



Select County: (087) Roane ☐ (Check All)

Enter Permit #: 985

Get Data Reset

☒ Location ☒ Production ☒ Plugging
☒ Owner/Completion ☒ Stratigraphy ☒ Sample
☒ Pay/Show/Water ☒ Logs ☒ Btm Hole Loc

[Table Descriptions](#)
[County Code Translations](#)
[Permit-Numbering Series](#)
[Usage Notes](#)
[Contact Information](#)
[Disclaimer](#)
[WVGES Main](#)
["Pipeline-Plus" New](#)

W-7

WV Geological & Economic Survey:

Well: County = 087 Permit = 985 [Link to all digital records for well](#)

Report Time: Thursday, April 03, 2025 1:09:14 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX_DISTRICT	QUAD_75	QUAD_15	LAT_DD	LON_DD	UTME	UTMN
4708700985	Roane	985	Smithfield	Spencer	Spencer	38.755755	-81.267503	476757	4289707

There is no Bottom Hole Location data for this well

Owner Information:

API	CMP_DT	SUFFIX	STATUS	SURFACE_OWNER	WELL_NUM	CO_NUM	LEASE	LEASE_NUM	MINERAL_OWN	OPERATOR_AT_COMPLETION	PROP_VD	PROP_TRGT_FM
4708700985	11/27/1963	Original Loc	Completed	Harold Rhodes	W-7		William Kaufman	81219	Alfred M Oppenheimer II et al	Wolf's Head Oil Refining Co., Inc.		
4708700985	--	Worked Over	Completed	Terry A Samples	W-7		W M Kaufman			Pennzoil Company		Big Injun (Price&eq)

Completion Information:

API	CMP_DT	SPUD_DT	ELEV	DATUM	FIELD	DEEPEST_FM	DEEPEST_FMT	INITIAL_CLASS	FINAL_CLASS	TYPE	RIG	CMP_MTHD	TVD	TMD	NEW_FTG	KOD	G_E
4708700985	11/27/1963	11/20/1963	1003	Ground Level	Civr-Rsh Rn	Price Fm & equivs	Price Fm & equivs	Development Well	Development Well	Oil and Gas	unknown	Fractured	2219		2219		
4708700985	--	--	1003	Ground Level	Civr-Rsh Rn	Price Fm & equivs	Big Injun (Price&eq)	Service Well	Unsuccessful	Salt Water Disp	unknown	unknown	2219				0

Comment: -- Injection zone footage proposed.

Pay/Show/Water Information:

API	CMP_DT	ACTIVITY	PRODUCT	SECTION	DEPTH_TOP	FM_TOP	DEPTH_BOT	FM_BOT	G_BEf	G_AFT	O_BEf	O_AFT	WATER_QNTY
4708700985	--	Horizon	Injection	Vertical	2163	Big Injun (Price&eq)	2166	Big Injun (Price&eq)					
4708700985	11/27/1963	Pay	Oil & Gas	Vertical			2170	Big Injun (Price&eq)	0		0		

Production Gas Information: (Volumes in Mcf)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_GAS	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700985	Pennzoil Company	1981	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	Pennzoil Company	1982	999	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	Pennzoil Company	1983	1,492	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	Pennzoil Company	1984	1,470	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Production Oil Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_OIL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700985	Pennzoil Company	1981	440	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	Pennzoil Company	1982	307	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	Pennzoil Company	1983	445	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	Pennzoil Company	1984	382	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Production NGL Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_NGL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700985	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Production Water Information: (Volumes in Gallons)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_WTR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700985	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700985	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Stratigraphy Information:

API	SUFFIX	FM	FM_QUALITY	DEPTH_TOP	DEPTH_QUALITY	THICKNESS	THICKNESS_QUALITY	ELEV	DATUM
4708700985	Original Loc	Little Lime	Well Record	1955	Reasonable	15	Reasonable	1003	Ground Level
4708700985	Original Loc	Big Lime	Well Record	1975	Reasonable	155	Reasonable	1003	Ground Level
4708700985	Original Loc	Greenbrier Group	Past WVGES Staff Geologist	1975	Reasonable	155	Reasonable	1003	Ground Level
4708700985	Original Loc	Big Injun (Price&eq)	Past WVGES Staff Geologist	2130	Reasonable	11	Reasonable	1003	Ground Level
4708700985	Original Loc	Keener	Well Record	2130	Reasonable	11	Reasonable	1003	Ground Level

Wireline (E-Log) Information:

* There is no Scanned/Raster Log data for this well

* There is no Digitized/LAS Log data for this well

* There is no Scanned or Digital Logs available for download

There is no Plugging data for this well

There is no Sample data for this well



4708700985

GEORGE H. HAYES, JR. (Vice) VAGUE

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

December 33

1907

Quadrangle SPENCERPermit No. ROA-985

WELL RECORD

Oil or Gas Well

(KIND)


Company WOLF'S HEAD OIL REFINING COMPANY, INC.Address P. O. Box 1588, Parkersburg, W. Va.Farm Wm. Kaufman Acres 800Location (waters) Slab Camp RunWell No. W-7 Elev. 1003.40District Smithfield County RoaneThe surface of tract is owned in fee by Harold RhodesOtto Route Address Spencer, W. Va.Mineral rights are owned by Alfred M. Oppenheimer II,300 South Lang Avenue Address Pittsburgh 8, Pa.Drilling commenced November 20, 1963Drilling completed November 27, 1963Date Shot - From - To -With -Open Flow /10ths Water in Inch/10ths Merc. in InchVolume Show Oil & Gas (Drilled w/Rotary) Cu. Ft.Rock Pressure - lbs. - hrs.Oil - bbls., 1st 24 hrs.

WELL ACIDIZED

WELL FRACTURED December 12, 1963RESULT AFTER TREATMENT Gas - 42,000 Cu. Ft.Oil - 33 Bbls.ROCK PRESSURE AFTER TREATMENT 508 Lbs.Fresh Water - FeetSalt Water - Feet

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Clay			0	10			
Sand			10	70			
Red Rock			70	110			
Shale			110	130			
Sand			130	172			
Shale			172	200			
Sand			200	240			
Red Rock			240	295			
Sand			295	375			
Sandy Shale			375	575			
Shale			575	600			
Red Rock			600	610			
Shale			610	630			
Sand			630	635			
Shale			635	670			
Sand			670	705			
Sand & Shale			705	935			
Sand			935	1020			
Shale			1020	1040			
Sand			1040	1150			
Shale			1150	1300			
Sand			1300	1350			
Sand & Shale			1350	1435			
Sand			1435	1500			
Shale			1500	1530			
Sandy Shale			1530	1600			
Sand			1600	1665			
Lime			1665	1770			
Sand			1770	1925			
Shale			1925	1955			

(over)



4708700985

[illegible]

Date December 23, 1963

APPROVED WOLF'S HEAD OIL REFINING COMPANY, INC. owner

By George W. Wilsman
George W. Wilsman, (Title) Agent



Select County: (087) Roane ☐ (Check All)

Enter Permit #: 987

Get Data Reset

Select datatypes: ☒ Location ☒ Production ☒ Plugging
☒ Owner/Completion ☒ Stratigraphy ☒ Sample
☒ Pay/Show/Water ☒ Logs ☒ Btm Hole Loc

[Table Descriptions](#)
[County Code Translations](#)
[Permit-Numbering Series](#)
[Usage Notes](#)
[Contact Information](#)
[Disclaimer](#)
[WVGES Main](#)
[Pipeline-Plus](#) New

W-6

WV Geological & Economic Survey:

Well: County = 87 Permit = 987 [Link to all digital records for well](#)

Report Time: Thursday, April 03, 2025 1:11:04 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX_DISTRICT	QUAD_75	QUAD_15	LAT_DD	LON_DD	UTME	UTMN
4708700987	Roane	987	Smithfield	Spencer	Spencer	38.754674	-81.272094	478357.8	4289588.2

There is no Bottom Hole Location data for this well

Owner Information:

API	CMP_DT	SUFFIX	STATUS	SURFACE_OWNER	WELL_NUM	CO_NUM	LEASE	LEASE_NUM	MINERAL_OWN	OPERATOR_AT_COMPLETION	PROP_VD	PROP_TRGT_FM	TFM_EST_PR
4708700987	12-/1963	Original Loc	Completed	William Kaufman			W-6			Wolf's Head Oil Refining Co., Inc.			

Completion Information:

API	CMP_DT	SPUD_DT	ELEV	DATUM	FIELD	DEEPEST_FM	DEEPEST_FMT	INITIAL_CLASS	FINAL_CLASS	TYPE	RIG	CMP_MTHD	TVD	TMD	NEW_FTG	KOD	G_BEF	G_
4708700987	12-/1963	-/-		1132	Ground Level	Civ-Rsh Rn	Price Fm & equivs	Price Fm & equivs	Development Well	Development Well	Oil and Gas	unknown	Acid+Frac	2335		2335		0

Pay/Show/Water Information:

API	CMP_DT	ACTIVITY	PRODUCT	SECTION	DEPTH_TOP	FM_TOP	DEPTH_BOT	FM_BOT	G_BEF	G_AFT	O_BEF	O_AFT	WATER_QNTY
4708700987	12-/1963	Pay	Oil & Gas	Vertical			2295	Blg Injun (Price&eq)	0	0			

Production Gas Information: (Volumes in Mcf)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_GAS	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700987	Pennzoil Company	1981	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	Pennzoil Company	1982	999	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	Pennzoil Company	1983	1,492	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	Pennzoil Company	1984	1,470	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	Pennzoil Products Company	1989	1,281	146	94	99	106	136	91	129	75	101	127	90	87
4708700987	Pennzoil Products Company	1990	1,448	108	77	104	91	99	129	178	135	139	145	124	119
4708700987	Pennzoil Products Company	1991	1,213	114	86	93	91	92	152	115	90	97	110	85	88
4708700987	Pennzoil Products Company	1992	423	82	70	67	54	66	84	0	0	0	0	0	0
4708700987	Pennzoil Products Company	1993	1,401	0	115	158	127	102	80	210	140	138	134	94	103
4708700987	Pennzoil Products Company	1994	1,313	111	153	47	139	107	95	102	94	104	126	95	140
4708700987	Pennzoil Products Company	1995	1,389	127	130	109	133	141	119	147	93	107	66	127	90
4708700987	Pennzoil Products Company	1996	1,239	0	0	176	122	166	90	92	39	127	176	127	124
4708700987	Pennzoil Products Company	1997	1,101	12	122	0	134	67	108	53	107	93	52	144	209
4708700987	Pennzoil Products Company	1998	1,832	235	157	245	269	370	251	156	0	18	45	47	39
4708700987	Pennzoil Products Company	1999	295	0	0	0	34	74	8	52	50	28	23	10	16
4708700987	East Resources, Inc.	2000	114	0	12	3	14	14	21	24	11	1	0	4	10
4708700987	East Resources, Inc.	2001	1,763	0	103	33	399	266	226	371	250	113	0	0	0
4708700987	East Resources, Inc.	2002	531	0	400	93	0	0	0	38	0	0	0	0	0
4708700987	East Resources, Inc.	2003	106	0	0	3	25	15	19	12	0	12	20	0	0
4708700987	East Resources, Inc.	2004	82	14	13	0	0	0	0	0	23	0	13	16	3
4708700987	East Resources, Inc.	2005	264	23	33	17	22	15	37	17	25	25	14	24	12
4708700987	East Resources, Inc.	2006	191	5	4	2	2	28	31	25	21	25	14	30	4
4708700987	East Resources, Inc.	2007	253	16	0	10	30	20	29	14	9	31	33	43	18
4708700987	East Resources, Inc.	2008	152	14	17	10	31	36	6	29	9	0	0	0	0
4708700987	East Resources, Inc.	2010	92	26	8	3	18	1	3	14	14	5	0	0	0
4708700987	East Resources, Inc.	2011	199	5	5	5	17	24	18	18	20	0	25	45	17
4708700987	HG Energy, LLC	2012	42	7	6	0	6	5	0	0	6	0	12	0	0
4708700987	HG Energy, LLC	2013	8	0	0	8	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2014	81	0	0	0	0	0	0	0	13	0	0	7	61
4708700987	HG Energy, LLC	2015	385	141	75	0	50	0	17	0	12	0	0	41	49
4708700987	HG Energy, LLC	2016	110	79	0	31	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2017	78	53	2	0	0	0	0	0	0	0	1	22	0
4708700987	HG Energy, LLC	2018	459	0	89	136	41	4	6	0	0	0	0	36	147
4708700987	HG Energy, LLC	2019	355	11	0	42	0	29	21	35	0	105	20	28	64
4708700987	HG Energy, LLC	2020	1,405	128	120	131	94	121	125	127	116	108	110	111	114
4708700987	HG Energy, LLC	2021	228	10	8	9	13	15	18	26	26	25	25	22	31
4708700987	HG Energy, LLC	2022	1,142	103	85	101	95	103	93	97	93	90	91	95	96
4708700987	HG Energy, LLC	2023	1,020	104	91	104	102	101	103	104	101	105	105	0	0
4708700987	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Production Oil Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_OIL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700987	Pennzoil Company	1981	440	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	Pennzoil Company	1982	307	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	Pennzoil Company	1983	445	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	Pennzoil Company	1984	382	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	Pennzoil Products Company	1989	261	25	24	27	21	24	16	22	22	19	21	21	19
4708700987	Pennzoil Products Company	1990	302	21	19	24	33	34	28	30	24	24	26	22	17
4708700987	Pennzoil Products Company	1991	224	21	19	19	29	20	17	17	19	16	17	15	15
4708700987	Pennzoil Products Company	1992	75	16	13	14	16	0	0	0	0	0	0	0	16
4708700987	Pennzoil Products Company	1993	229	24	15	16	21	21	20	20	21	17	17	18	19
4708700987	Pennzoil Products Company	1994	206	9	19	18	18	15	16	17	20	17	20	18	19
4708700987	Pennzoil Products Company	1995	173	14	17	19	17	19	17	18	13	21	18	0	0
4708700987	Pennzoil Products Company	1996	222	23	16	21	19	14	8	20	23	19	20	21	18
4708700987	Pennzoil Products Company	1997	190	15	20	16	21	18	17	9	11	14	18	17	14
4708700987	Pennzoil Products Company	1998	67	18	14	18	12	5	0	0	0	0	0	0	0
4708700987	Pennzoil Products Company	1999	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	East Resources, Inc.	2000	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	East Resources, Inc.	2001	146	0	17	22	19	21	12	11	9	8	10	8	9
4708700987	East Resources, Inc.	2002	21	9	10	2	0	0	0	0	0	0	0	0	0
4708700987	East Resources, Inc.	2003	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	East Resources, Inc.	2004	5	0	0	0	0	0	0	0	0	0	0	0	5
4708700987	East Resources, Inc.	2005	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	East Resources, Inc.	2006	59	0	0	0	0	59	0	0	0	0	0	0	0
4708700987	East Resources, Inc.	2007	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	East Resources, Inc.	2008	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	East Resources, Inc.	2010	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	East Resources, Inc.	2011	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2012	18	0	0	0	0	0	0	0	0	5	13	0	0
4708700987	HG Energy, LLC	2013	24	0	0	0	0	9	11	0	4	0	0	0	0
4708700987	HG Energy, LLC	2014	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2015	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2016	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2017	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Production NGL Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_NGL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
-----	--------------------	----------	---------	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----

4708700987	HG Energy, LLC	2013	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2014	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2015	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2016	0													
4708700987	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0	0

4708700987

Production Water Information: (Volumes in Gallons)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_WTR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700987	HG Energy, LLC	2016	0												
4708700987	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700987	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Stratigraphy Information:

API	SUFFIX	FM	FM_QUALITY	DEPTH_TOP	DEPTH_QUALITY	THICKNESS	THICKNESS_QUALITY	ELEV	DATUM
4708700987	Original Loc	Little Lime	Well Record	2104	Reasonable	46	Reasonable	1132	Ground Level
4708700987	Original Loc	Greenbrier Group	Past WVGES Staff Geologist	2150	Reasonable	120	Reasonable	1132	Ground Level
4708700987	Original Loc	Big Lime	Well Record	2150	Reasonable	105	Reasonable	1132	Ground Level
4708700987	Original Loc	Keener	Well Record	2255	Reasonable	15	Reasonable	1132	Ground Level
4708700987	Original Loc	Big Injun (Price & eq)	Past WVGES Staff Geologist	2270	Reasonable	25	Reasonable	1132	Ground Level

Wireline (E-Log) Information:

* There is no Scanned/Raster Log data for this well

* There is no Digitized/LAS Log data for this well

* There is no Scanned or Digital Logs available for download

There is no Plugging data for this well

There is no Sample data for this well

4708700987



GOVERNOR M. JOHNSON (1963) VEGUE

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

December 31 1963

Quadrangle SPENCERPermit No. ROA-987- Revised Location


WELL RECORD

Oil or Gas Well

(KIND)

Company WOLF'S HEAD OIL REFINING COMPANY, INC.Address P. O. Box 1588, Parkersburg, W. Va.Farm Wm. Kaufman Acres 800Location (waters) Millstone RunWell No. W-6 - Revised Location Elev 1132.36District Smithfield County RoaneThe surface of tract is owned in fee by Roy RhodesOtto Route Address Spencer, W. Va.Mineral rights are owned by Alfred M. Oppenheimer II,300 South Lang Avenue Address Pittsburgh 8, Pa.Drilling commenced December 4, 1963Drilling completed December 12, 1963Date Shot - From - To -With -Open Flow /10ths Water in - Inch/10ths Merc. in - InchVolume Show Oil & Gas (Drilled w/Rotary) Cu. Ft.Rock Pressure Not Taken lbs. - hrs.Oil - bbls., 1st 24 hrs.WELL ACIDIZED -WELL FRACTURED 12/26/63 - Used 37500 Gals. Water, 58,000 Lbs. Sand, 300 Gal. Mud Acid,40 Gal. Preflo, 35 Gal. Deterger, 400 Lbs. J-84 and 200 Lbs. J-98,RESULT AFTER TREATMENT Gas = 38,000 Cu. Ft.ROCK PRESSURE AFTER TREATMENT 495 Lbs.Fresh Water - Feet - Salt Water - Feet -

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Shale			0	407			
Red Rock			407	575			
Sand			575	735			
Shale			735	750			
Red Rock			750	790			
Shale			790	820			
Sand			820	830			
Shale			830	1425			
Sandy Shale			1425	1640			
Sand			1640	1665			
Shale			1665	1725			
Sand			1725	1805			
Red Rock			1805	1840			
Sandy Shale			1840	1855			
Sand			1855	2015			
Sand & Shale			2015	2104			
Little Lime			2104	2150			
Big Lime			2150	2255			
Keener Sand			2255	2270			
Big Injun			2270	2295			
Lime & Shale			2295	2335	Oil & Gas	2270-2295	Show
4 1/2" Casing				2335			
TOTAL DEPTH				2335			



(over)

4708700987
W-6

NEW WELL REPORT - CONT'D.

INITIAL TORPEDO RECORD		CASING AND TUBING RECORD					
Date of Shot	SIZE	PUT IN WELL			PULLED OUT		
		TRANSFER NO.	FEET	INCH	TRANSFER NO.	FEET	INC
	8-5/8"	Tally	120	—			
Name of Torpedo Co.	1 1/2" OD	Tally	2379	6			
No. of Quarts	2-3/8"						
Length of Shell	1 1/2"	Tally	2315	—			
Diameter of Shell							
Length of Anchor							
Top of Shot							
Bottom of Shot							
Feet of Fluid in Hole When Shot							
Results:							

INITIAL PRODUCTION FIRST 24 HOURS		PACKER RECORD			
Open Flow	/10ths Water in	KIND	SIZE	DEPTH SET	DATE SET
		Steel Shoe	8-5/8" OD	1207'	12-6-63
		Float Collar	1 1/2" OD	2301'	12-13-63
		Guide Shoe	1 1/2" OD	2335'	12-13-63
Volume	Show Oil & Gas (Drilled w/Rotary)				
Rock Pressure	None Taken				
Oil Flow	Electric Log				

ACIDIZATION OR FRACTURING RECORD		CASING CEMENTED	
DATE WELL ACIDIZED		Surface to:	
DATE WELL FRACTURED 12-26-63		8-5/8" SIZE 1207 FT. 12-4-63	
NAME OF COMPANY Dowell		1 1/2" SIZE 2335 FT. 12-13-63	
(List below materials used in Acidizing or Fracturing, i.e., Sand, Crude Oil, Gasoline, Water, Kerosene, Mothballs, Acid, etc., giving gallons, barrels and pounds).		SIZE FT. DA1	
Used: 3750 Gals. Water		USED IN CEMENTING 8-5/8" CASING:	
Used: 50,000 Lbs. Sand		50 Bags - Cement	
Used: 300 Gal. Mud Acid		1 Bag - Calcium Chloride	
Used: 10 gal. Freflo		Cemented by: Well Service, Inc	
Used: 25 t.l. Deterger		USED IN CEMENTING 1 1/2" CASING:	
Used: 100 lbs. J-56		65 cu. ft. Formix Cement (Consisting	
Used: 200 lbs. J-98		of 33 cu. ft. of Columbia Cement	
		and 32 cu. ft. of Formix -A and 1-	
		Hall. Gel. blended 2% with 65 cu.	
		of Formix Cement.	
		500 Gals. - Mud Flush	
		Cemented by: Halliburton Company	
BREAKDOWN PRESSURE 1200#			
PUMPING PRESSURE 1300 - 1700 Lbs.			
AVERAGE PUMPING RATE/MINUTE 32 Bbls.			
PUMPING TIME 27 minutes			
RESULT AFTER TREATMENT GAS 30000		CU. FT.	
OIL 32		BBLS.	
ROCK PRESSURE AFTER TREATMENT 1295		LBS.	

REMARKS: Drilled 10-5/8" Hole From Surface to 1207'.
Drilled 7-7/8" Hole From 1207' to 2335'.
Note: Rotary Tools Used.
Note: Used 18 - 5' Sections of Rate-We
Cleaners & 39 R-2 Loh Limits &
1/4 Halliburton Weld-A.

Note: This well was logged by McCullough Tool Company on December 13, 1963.

Note: This well was drilled according to Rule 11, under Section 13, of Article 4, Chapter 22 of the Code of the Department of Mines, Oil and Gas Division.

APPROVED

C. C. C. [Signature]

SUPERINTENDENT



Select County: (087) Roane Select datatypes: ☐ (Check All)

Enter Permit #: 988

☒ Location ☒ Production ☒ Plugging
☒ Owner/Completion ☒ Stratigraphy ☒ Sample
☒ Pay/Show/Water ☒ Logs ☒ Btm Hole Loc

[Table Descriptions](#)
[County Code Translations](#)
[Permit-Numbering Series](#)
[Usage Notes](#)
[Contact Information](#)
[Disclaimer](#)
[WVGES Main](#)
["Pipeline-Plus" New](#)

W-8

WV Geological & Economic Survey:

Well: County = 87 Permit = 988 [Link to all digital records for well](#)

Report Time: Thursday, April 03, 2025 1:09:49 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX DISTRICT	QUAD_75	QUAD_15	LAT_DD	LON_DD	UTME	UTMN
4708700988	Roane	988	Smithfield	Spencer	Spencer	38.755462	-81.262517	477190.2	4289673.2

There is no Bottom Hole Location data for this well

Owner Information:

API	CMP_DT	SUFFIX	STATUS	SURFACE_OWNER	WELL_NUM	CO_NUM	LEASE	LEASE_NUM	MINERAL_OWN	OPERATOR_AT_COMPLETION	PROP_VD	PROP_TRGT_FM	TFM_EST
4708700988	1/13/1964	Original Loc	Completed	W Kaufman, E Walbrown		W-8			Alfred M Oppenheimer II	Wolf's Head Oil Refining Co., Inc.			
4708700988	10/26/1972	Worked Over	Completed	W Kaufman, K Miller		W-8			Alfred M Oppenheimer II	Pennzoil Company			

Completion Information:

API	CMP_DT	SPUD_DT	ELEV	DATUM	FIELD	DEEPEST_FM	DEEPEST_FMT	INITIAL_CLASS	FINAL_CLASS	TYPE	RIG	CMP_MTHD	TVD	TMD	NEW_FTG	KOD	G_E
4708700988	1/13/1964	12/17/1963	1225	Ground Level	Civr-Rsh Rn	Undf PRICE	blw INJN	Big Injun (Price&eq)	Development Well	Development Well	Oil and Gas	Rotary	2430			2430	
4708700988	10/26/1972	J-J	1225	Ground Level	Civr-Rsh Rn	Undf PRICE	blw INJN	Big Injun (Price&eq)	Development Well	Development Well	Oil	Acid+Frac	2430			0	

Pay/Show/Water Information:

API	CMP_DT	ACTIVITY	PRODUCT	SECTION	DEPTH_TOP	FM_TOP	DEPTH_BOT	FM_BOT	G_BEFF	G_AFT	O_BEFF	O_AFT	WATER_QNTY
4708700988	10/26/1972	Pay	Oil	Vertical		Big Lime	2276	Big Lime	0	4			
4708700988	1/13/1964	Pay	Oil	Vertical	2362	Big Injun (Price&eq)	2379	Big Injun (Price&eq)	0	38			
4708700988	1/13/1964	Pay	Gas	Vertical	2362	Big Injun (Price&eq)	2379	Big Injun (Price&eq)	0	38			

Production Gas Information: (Volumes in Mcf)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_GAS	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700988	Pennzoil Company	1981	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	Pennzoil Company	1982	999	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	Pennzoil Company	1983	1,492	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	Pennzoil Company	1984	1,470	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	Pennzoil Products Company	1989	1,299	134	94	99	106	136	91	119	94	105	127	99	95
4708700988	Pennzoil Products Company	1990	1,398	103	68	114	91	99	117	157	140	139	145	124	101
4708700988	Pennzoil Products Company	1991	1,046	114	76	62	19	101	100	115	85	80	116	85	93
4708700988	Pennzoil Products Company	1992	918	93	46	67	66	81	78	97	87	70	87	74	72
4708700988	Pennzoil Products Company	1993	696	52	69	69	34	66	68	65	49	46	61	56	61
4708700988	Pennzoil Products Company	1994	645	63	66	49	51	62	57	66	49	32	57	44	49
4708700988	Pennzoil Products Company	1995	514	44	61	49	41	46	41	42	36	44	29	40	41
4708700988	Pennzoil Products Company	1996	413	21	1	52	44	36	38	33	33	43	30	41	41
4708700988	Pennzoil Products Company	1997	446	49	37	35	30	32	31	34	36	30	32	44	56
4708700988	Pennzoil Products Company	1998	410	55	44	43	40	44	46	29	24	21	22	20	22
4708700988	Pennzoil Products Company	1999	239	46	48	27	22	15	0	0	12	12	21	22	14
4708700988	East Resources, Inc.	2000	150	13	14	10	0	17	8	0	20	14	16	16	22
4708700988	East Resources, Inc.	2001	370	7	0	0	0	55	64	66	35	11	62	63	7
4708700988	East Resources, Inc.	2002	590	51	47	49	47	47	50	53	55	57	46	27	61
4708700988	East Resources, Inc.	2003	1,000	33	21	116	295	94	92	82	71	76	86	0	34
4708700988	East Resources, Inc.	2004	936	98	81	56	66	98	122	88	101	113	29	27	57
4708700988	East Resources, Inc.	2005	383	22	22	21	24	40	34	29	39	41	40	33	38
4708700988	East Resources, Inc.	2006	509	38	37	41	41	45	44	48	33	36	43	50	53
4708700988	East Resources, Inc.	2007	430	51	38	42	30	27	23	27	34	31	32	49	48
4708700988	East Resources, Inc.	2008	479	40	39	40	37	41	39	40	41	41	45	38	38
4708700988	East Resources, Inc.	2010	506	49	35	40	42	43	40	41	41	40	46	47	42
4708700988	East Resources, Inc.	2011	547	44	41	47	47	47	43	47	48	46	48	44	45
4708700988	HG Energy, LLC	2012	525	40	35	39	40	44	40	28	52	57	57	47	46
4708700988	HG Energy, LLC	2013	533	48	35	38	39	51	47	42	48	45	50	44	46
4708700988	HG Energy, LLC	2014	383	42	37	42	36	1	9	15	35	42	42	39	43
4708700988	HG Energy, LLC	2015	464	37	32	33	37	42	41	42	40	40	40	37	43
4708700988	HG Energy, LLC	2016	467	39	38	39	39	41	38	40	38	39	39	39	38
4708700988	HG Energy, LLC	2017	404	37	32	33	31	34	30	32	32	34	36	37	36
4708700988	HG Energy, LLC	2018	426	36	33	38	36	38	37	39	36	34	33	32	34
4708700988	HG Energy, LLC	2019	365	35	32	34	31	24	24	26	32	30	33	34	30
4708700988	HG Energy, LLC	2020	358	35	31	35	17	29	32	33	32	28	28	29	29
4708700988	HG Energy, LLC	2021	583	54	41	54	56	57	56	59	0	52	51	48	55
4708700988	HG Energy, LLC	2022	339	28	21	29	27	29	28	31	31	29	29	29	28
4708700988	Delta Helix Energy, LLC	2023	58	0	0	0	0	0	0	0	0	0	0	30	28
4708700988	HG Energy, LLC	2023	313	30	27	31	32	32	30	32	32	34	33	0	0

Production Oil Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

Production	Oil Information: (volumes in Bbl) -- some operations may have reported NGT under CR														
API	PRODUCING_OPERATOR	PRD_YEAR	ANN_OIL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700988	Pennzoil Company	1981	440	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	Pennzoil Company	1982	307	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	Pennzoil Company	1983	445	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	Pennzoil Company	1984	382	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	Pennzoil Products Company	1989	265	25	24	27	21	22	20	23	22	21	23	20	17
4708700988	Pennzoil Products Company	1990	292	23	19	24	30	30	29	30	24	24	22	22	15
4708700988	Pennzoil Products Company	1991	189	14	4	21	19	20	16	14	20	16	18	17	10
4708700988	Pennzoil Products Company	1992	177	16	16	16	15	17	15	13	17	14	15	10	13
4708700988	Pennzoil Products Company	1993	150	14	10	13	15	14	11	10	13	12	12	12	14
4708700988	Pennzoil Products Company	1994	134	10	12	15	13	13	10	7	12	9	11	9	13
4708700988	Pennzoil Products Company	1995	86	10	8	10	9	9	7	9	9	10	9	9	12
4708700988	Pennzoil Products Company	1996	115	14	12	9	9	7	6	9	10	9	9	9	6
4708700988	Pennzoil Products Company	1997	94	8	8	9	8	9	9	5	7	7	9	9	6
4708700988	Pennzoil Products Company	1998	79	9	8	9	9	3	0	0	0	0	0	25	16
4708700988	Pennzoil Products Company	1999	33	14	15	4	0	0	0	0	0	0	0	0	0
4708700988	East Resources, Inc.	2000	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	East Resources, Inc.	2001	128	0	0	0	0	21	20	23	9	3	20	16	16
4708700988	East Resources, Inc.	2002	179	14	18	15	14	15	17	22	15	16	12	6	15
4708700988	East Resources, Inc.	2003	220	15	7	7	38	33	30	20	15	23	21	0	11
4708700988	East Resources, Inc.	2004	277	15	26	20	20	23	29	21	27	29	19	24	24
4708700988	East Resources, Inc.	2005	311	18	31	37	30	32	30	24	32	33	24	10	10
4708700988	East Resources, Inc.	2006	81	9	5	5	9	8	7	7	0	6	9	8	8
4708700988	East Resources, Inc.	2007	131	8	7	10	11	21	16	12	12	8	10	9	7
4708700988	East Resources, Inc.	2008	86	6	8	9	9	8	8	9	8	4	7	5	5
4708700988	East Resources, Inc.	2010	148	11	15	14	18	0	12	19	13	11	16	10	9
4708700988	East Resources, Inc.	2011	113	7	11	12	8	8	10	8	11	8	9	11	10
4708700988	HG Energy, LLC	2012	151	8	11	14	16	16	7	2	10	4	27	20	16
4708700988	HG Energy, LLC	2013	194	20	24	11	9	15	13	13	22	17	21	16	13
4708700988	HG Energy, LLC	2014	152	13	18	14	16	17	14	13	14	9	8	6	10
4708700988	HG Energy, LLC	2015	142	11	9	14	17	11	13	13	11	8	10	11	14
4708700988	HG Energy, LLC	2016	123	9	12	12	10	11	14	9	15	8	7	6	10
4708700988	HG Energy, LLC	2017	33	7									6	5	9
4708700988	HG Energy, LLC	2018	76	8	8	7	4	6	8	6	5	4	7	5	8
4708700988	HG Energy, LLC	2019	88	11	5	7	8	10	6	8	4	5	10	7	7
4708700988	HG Energy, LLC	2020	91	8	8	6	10	8	7	10	7	8	5	5	9
4708700988	HG Energy, LLC	2021	93	8	6	7	8	6	10	7	9	8	7	7	10
4708700988	HG Energy, LLC	2022	89	8	6	10	7	9	7	8	8	8	8	5	5
4708700988	Delta Helix Energy, LLC	2023	8	0	0	0	0	0	0	0	0	0	0	0	4
4708700988	HG Energy, LLC	2023	64	6	6	6	7	9	7	7	5	4	7	0	

4708700988

Production NGL Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_NGL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700988	HG Energy, LLC	2013	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2014	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2015	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2016	0												
4708700988	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Production Water Information: (Volumes in Gallons)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_WTR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700988	HG Energy, LLC	2016	0												
4708700988	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Stratigraphy Information:

API	SUFFIX	FM	FM_QUALITY	DEPTH	TOP	DEPTH	QUALITY	THICKNESS	THICKNESS_QUALITY	ELEV	DATUM
4708700988	Original Loc	Little Lime	Well Record	2166	Reasonable	49	Reasonable	1225	Ground Level		
4708700988	Original Loc	Greenbrier Group	Past WVGES Staff Geologist	2215	Reasonable	147	Reasonable	1225	Ground Level		
4708700988	Original Loc	Big Lime	Well Record	2215	Reasonable	133	Reasonable	1225	Ground Level		
4708700988	Original Loc	Keener	Well Record	2348	Reasonable	14	Reasonable	1225	Ground Level		
4708700988	Original Loc	Big Injun (Price&eq)	Past WVGES Staff Geologist	2362	Reasonable	17	Reasonable	1225	Ground Level		
4708700988	Original Loc	Undf PRICE blw INJN	Well Record	2379	Reasonable	0	Reasonable	1225	Ground Level		

Wireline (E-Log) Information:

- * There is no Scanned/Raster Log data for this well
- * There is no Digitized/LAS Log data for this well
- * There is no Scanned or Digital Logs available for download

There is no Plugging data for this well

There is no Sample data for this well



4708700988

GEORGE W. MITCHELL, JR., VIRGINIA

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

Quadrangle SPENCERPermit No. ROA-988

WELL RECORD

Oil or Gas Well Comb.

Company WOLF'S HEAD OIL REFINING COMPANY, INC.
Address P. O. Box 1588, Parkersburg, W. Va.
Farm Wm. Kaufman Acres > 800
Location (waters) Millstone Run
Well No. W-8 Elev. 1,224.85
District Smithfield County Roane
The surface of tract is owned in fee by Eugene Walbrown
Otto Route Address Spencer, W. Va.
Mineral rights are owned by Alfred M. Oppenheimer, II,
300 South Lang Avenue Address Pittsburgh 8, Pa.
Drilling commenced December 17, 1963
Drilling completed January 13, 1964
Date Shot - From - To -
With -
Open Flow /10ths Water in Inch
/10ths Merc. in Inch
Volume Show Oil & Gas (Drilled w/Rotary) Cu. Ft.
Rock Pressure None Taken lbs. hrs.
Oil - bbls., 1st 24 hrs.
WELL ACIDIZED

WELL FRACTURED 1/22/64 Used: 40,000 Gals. Water, 45,000 Lbs. Sand, 40 Gals. Morflo,
30 Gals. Suds, 300 Gals. Acid 15% MCA and 350 Lbs. WAC-8,
RESULT AFTER TREATMENT Gas = 38,000 Cu. Ft.
Oil = 38 bbls.


ROCK PRESSURE AFTER TREATMENT 500 Lbs.Fresh Water - Feet - Salt Water - Feet -

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Shale			0	850			
Red Rock			850	949			
Shale			949	1400			
Sand			1400	1480			
Shale			1480	1485			
Sand			1485	1525			
Sandy Shale			1525	1540			
Sand			1540	1685			
Shale			1685	1725			
Sand			1725	1765			
Shale			1765	1775			
Sand			1775	1875			
Sand & Lime			1875	1910			
Shale			1910	1925			
Lime-Shale			1925	1975			
Sand			1975	2005			
Sand & Chert			2005	2040			
Lime & Sand			2040	2100			
Sandy Shale			2100	2125			
Shale			2125	2166			
Little Lime			2166	2215			
Big Lime			2215	2348			
Keener Sand			2348	2362			
Big Injun			2362	2379			
Shale			2379	2430	Oil & Gas	2362-2379	Show Only
4 1/2" Casing				2427			
TOTAL DEPTH				2430			

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			Steel Shoe
10			Float Collar
8 5/8"	266'	266'	Guide Shoe
6 3/4"			Size of OD
4 1/2"	2427'	2427'	4 1/2" OD
3			Depth set
2 3/8" Tbg.	2379'	2379'	2379'
Liners Used			Perf. top
			Perf. bottom
			Perf. top
			Perf. bottom

CASING CEMENTED 8 5/8" SIZE 266 No. Ft. 12/20/63 Date
4 1/2" 2427 1/14/64

COAL WAS ENCOUNTERED AT - FEET - INCHES
- FEET - INCHES - FEET - INCHES
- FEET - INCHES - FEET - INCHES



4708700988

[illegible]

1. OF THE COURT

DEVELOPMENT OF PILES Date

February 4 1964

ΕΛΛΗΝΙΚΗ ΔΗΜΟΚΡΑΤΙΑ

APPROVED ~~WOLF'S~~ HEAD OIL REFINING COMPANY. - INC. ^{owner}

By George W. Wilsman
George W. Wilsman, (Title) Agent



Select County: (087) Roane ☐ (Check All)

Enter Permit #: 1053

Get Data Reset

Select datatypes: ☒ Location ☒ Production ☒ Plugging
☒ Owner/Completion ☒ Stratigraphy ☒ Sample
☒ Pay/Show/Water ☒ Logs ☒ Btm Hole Loc

[Table Descriptions](#)
[County Code Translations](#)
[Permit-Numbering Series](#)
[Usage Notes](#)
[Contact Information](#)
[Disclaimer](#)
[WVGES Map](#)
[Pipeline-Plus, Now](#)

W-17

WV Geological & Economic Survey:

Well: County = 87 Permit = 1053 [Link to all digital records for well](#)

Report Time: Thursday, April 03, 2025 1:33:47 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX_DISTRICT	QUAD_75	QUAD_15	LAT_DD	LONG_DD	UTME	UTMN
4708701053	Roane	1053	Smithfield	Spencer	Spencer	38.757402	-81.263649	477092.4	4289888.7

There is no Bottom Hole Location data for this well

Owner Information:

API	CMP_DT	SUFFIX	STATUS	SURFACE_OWNER	WELL_NUM	CO_NUM	LEASE	LEASE_NUM	MINERAL_OWN	OPERATOR_AT_COMPLETION	PROP_VD	PROP_TRGT_FM	TFM_EST_PR
4708701053	5/-1964	Original Loc	Completed	William Kaufman	24	W17				Wolf's Head Oil Refining Co., Inc.			

Completion Information:

API	CMP_DT	SPUD_DT	ELEV	DATUM	FIELD	DEEPEST_FM	DEEPEST_FMT	INITIAL_CLASS	FINAL_CLASS	TYPE	RIG	CMP_MTHD	TVD	TMD	NEW_FTG	KOD	G_BEF	G_
4708701053	5/-1964	5/-1964	971	Ground Level	Clvr-Rsh Rn	Price Fm & equivs	Price Fm & equivs	Development Well	Development Well	Oil and Gas	unknown	Fractured	2190		2190			0

Pay/Show/Water Information:

API	CMP_DT	ACTIVITY	PRODUCT	SECTION	DEPTH_TOP	FM_TOP	DEPTH_BOT	FM_BOT	G_BEF	G_AFT	O_BEF	O_AFT	WATER_QNTY
4708701053	5/-1964	Water	Unknown Water	Vertical			190						1
4708701053	5/-1964	Pay	Oil & Gas	Vertical			2136	Big Injun (Price&eq)	0	0			

Production Gas Information: (Volumes in Mcf)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_GAS	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701053	Pennzoil Company	1981	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	Pennzoil Company	1982	999	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	Pennzoil Company	1983	1,492	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	Pennzoil Company	1984	1,470	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	Pennzoil Products Company	1989	2,378	210	153	175	176	212	165	232	183	215	272	198	187
4708701053	Pennzoil Products Company	1990	2,919	195	141	218	87	214	250	325	261	280	364	320	284
4708701053	Pennzoil Products Company	1991	3,736	306	293	267	216	357	315	379	340	314	336	302	311
4708701053	Pennzoil Products Company	1992	3,463	324	297	267	257	314	319	298	303	287	282	299	216
4708701053	Pennzoil Products Company	1993	3,350	336	369	331	144	257	240	296	260	260	282	266	309
4708701053	Pennzoil Products Company	1994	3,015	288	265	131	228	261	243	254	296	256	270	252	271
4708701053	Pennzoil Products Company	1995	2,772	260	233	230	200	253	244	241	249	226	233	198	205
4708701053	Pennzoil Products Company	1996	2,115	21	1	199	153	210	191	200	242	242	161	243	252
4708701053	Pennzoil Products Company	1997	2,366	223	223	175	176	148	201	150	172	225	236	207	230
4708701053	Pennzoil Products Company	1998	1,299	227	155	172	171	183	155	127	24	21	22	20	22
4708701053	Pennzoil Products Company	1999	513	144	141	122	22	15	0	0	12	21	22	14	
4708701053	East Resources, Inc.	2000	150	13	14	10	0	17	8	0	20	14	16	16	22
4708701053	East Resources, Inc.	2001	1,148	7	95	124	147	111	112	118	104	115	114	94	7
4708701053	East Resources, Inc.	2002	846	83	71	78	77	69	71	65	59	75	54	45	99
4708701053	East Resources, Inc.	2003	403	0	9	0	23	60	61	49	42	56	53	0	50
4708701053	East Resources, Inc.	2004	274	39	50	34	13	30	21	0	0	0	29	27	31
4708701053	East Resources, Inc.	2005	383	22	22	21	24	40	34	29	39	41	40	33	38
4708701053	East Resources, Inc.	2006	509	38	37	41	41	45	44	48	33	36	43	50	53
4708701053	East Resources, Inc.	2007	430	51	38	42	30	27	23	27	34	31	32	49	46
4708701053	East Resources, Inc.	2008	479	40	39	40	37	41	39	40	41	41	45	38	38
4708701053	East Resources, Inc.	2010	506	49	35	40	42	43	40	41	41	40	46	47	42
4708701053	East Resources, Inc.	2011	547	44	41	47	47	47	43	47	48	46	48	44	45
4708701053	HG Energy, LLC	2012	525	40	35	39	40	44	40	28	52	57	57	47	46
4708701053	HG Energy, LLC	2013	533	48	35	38	39	51	47	42	48	45	50	44	46
4708701053	HG Energy, LLC	2014	383	42	37	42	36	1	9	15	35	42	42	39	43
4708701053	HG Energy, LLC	2015	464	37	32	33	37	42	41	42	40	40	40	37	43
4708701053	HG Energy, LLC	2016	467	39	38	39	39	41	38	40	38	39	39	39	38
4708701053	HG Energy, LLC	2017	404	37	32	33	31	34	30	32	32	34	36	37	36
4708701053	HG Energy, LLC	2018	426	36	33	38	36	38	37	39	36	34	33	32	34
4708701053	HG Energy, LLC	2019	365	35	32	34	31	24	24	26	32	30	33	34	30
4708701053	HG Energy, LLC	2020	358	35	31	35	17	29	32	33	32	28	28	29	29
4708701053	HG Energy, LLC	2021	99	10	7	6	9	10	9	10	9	8	8	7	6
4708701053	HG Energy, LLC	2022	339	28	21	29	27	29	28	31	31	29	29	29	28
4708701053	Delta Helix Energy, LLC	2023	58	0	0	0	0	0	0	0	0	0	0	30	28
4708701053	HG Energy, LLC	2023	313	30	27	31	32	32	30	32	32	34	33	0	0

Production Oil Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_OIL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701053	Pennzoil Company	1981	440	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	Pennzoil Company	1982	307	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	Pennzoil Company	1983	444	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	Pennzoil Company	1984	382	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	Pennzoil Products Company	1989	500	44	40	42	38	43	39	47	42	45	38	35	
4708701053	Pennzoil Products Company	1990	651	44	18	52	64	62	54	56	60	62	62	59	58
4708701053	Pennzoil Products Company	1991	722	60	45	74	60	66	64	55	58	57	60	59	64
4708701053	Pennzoil Products Company	1992	701	64	62	66	61	52	52	53	55	57	45	65	69
4708701053	Pennzoil Products Company	1993	681	67	42	51	53	64	58	57	60	57	61	55	56
4708701053	Pennzoil Products Company	1994	639	27	54	63	55	50	60	57	57	52	61	53	50
4708701053	Pennzoil Products Company	1995	480	47	39	55	53	52	49	46	49	45	45	0	0
4708701053	Pennzoil Products Company	1996	604	54	42	53	45	43	44	51	53	53	56	55	55
4708701053	Pennzoil Products Company	1997	480	40	47	42	52	40	43	37	51	33	37	37	21
4708701053	Pennzoil Products Company	1998	268	36	34	37	30	13	0	0	0	0	0	68	50
4708701053	Pennzoil Products Company	1999	106	44	44	18	0	0	0	0	0	0	0	0	0
4708701053	East Resources, Inc.	2000	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	East Resources, Inc.	2001	392	0	61	51	48	42	35	41	27	0	37	24	26
4708701053	East Resources, Inc.	2002	253	23	27	24	23	22	24	27	16	21	14	10	22
4708701053	East Resources, Inc.	2003	104	0	3	0	3	21	20	12	9	17	13	0	6
4708701053	East Resources, Inc.	2004	50	6	18	12	4	7	5	0	0	0	0	0	0
4708701053	East Resources, Inc.	2005	267	0	0	0	3	37	31	24	38	37	24	41	32
4708701053	East Resources, Inc.	2006	479	40	32	52	34	52	50	45	0	43	41	41	49
4708701053	East Resources, Inc.	2007	474	56	47	52	51	39	25	39	36	32	30	36	31
4708701053	East Resources, Inc.	2008	397	30	25	31	34	29	34	32	38	41	41	30	32
4708701053	East Resources, Inc.	2010	209	20	17	19	24	0	15	23	18	15	22	20	16
4708701053	East Resources, Inc.	2011	131	8	9	12	11	8	11	11	11	10	10	16	14
4708701053	HG Energy, LLC	2012	178	13	17	13	12	17	20	5	21	16	18	12	14
4708701053	HG Energy, LLC	2013	209	18	19	16	16	18	17	22	15	16	19	17	16
4708701053	HG Energy, LLC	2014	176	16	8	7	18	19	14	14	17	14	13	15	23
4708701053	HG Energy, LLC	2015	176	20	15	16	20	19	12	15	12	12	13	9	13
4708701053	HG Energy, LLC	2016	130	9	12	12	9	7	12	12	15	11	12	9	10
4708701053	HG Energy, LLC	2017	85	11	7	9	7	8	6	6	7	4	4	8	8
4708701053	HG Energy, LLC	2018	106	8	8	10	12	10	10	9	7	6	10	6	10
4708701053	HG Energy, LLC	2019	122	15	10	8	11	13	10	10	8	9	13	8	7
4708701053	HG Energy, LLC	2020	108	10	8	7	12	8	8	11	8	10	9	8	9
4708701053	HG Energy, LLC	2021	65	8	5	4	10	8	9	7	10	0	0	0	4
4708701053	HG Energy, LLC	2022	93	9	8	9	8	10	8	7	7	7	9	7	4
4708701053	Delta Helix Energy, LLC	2023	8	0	0	0	0	0	0	0	0	0	0	0	4
4708701053	HG Energy, LLC	2023	73	8	7	9	6	6	6	7	7	7	10	0	

4708701053

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_NGL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701053	HG Energy, LLC	2013	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2014	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2015	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2016	0												
4708701053	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Production Water Information: (Volumes in Gallons)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_WTR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701053	HG Energy, LLC	2016	0												
4708701053	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

There is no Stratigraphy data for this well

Wireline (E-Log) Information:

- * There is no Scanned/Raster Log data for this well
- * There is no Digitized/LAS Log data for this well
- * There is no Scanned or Digital Logs available for download

There is no Plugging data for this well

There is no Sample data for this well



4708701053

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION 12

Quadrangle SPENCERPermit No. ROA-1053

WELL RECORD

Oil or Gas Well Gas-Oil
(KIND)

Company WOLF'S HEAD OIL REFINING COMPANY, INC.
Address P. O. Box 1588, Parkersburg, W. Va.
Farm Wm. Kaufman Acres 800
Location (waters) Millstone Run
Well No. W-17 Elev. 971.38
District Smithfield County Roane
The surface of tract is owned in fee by Romie Smith
Otto Route Address Spencer, W. Va.
Mineral rights are owned by Alfred M. Oppenheimer, II
300 South Lang Avenue Address Pittsburgh 8, Pa.
Drilling commenced May 14, 1964
Drilling completed May 21, 1964
Date Shot _____ From _____ To _____
Wit's _____
Open Flow _____ /10ths Water in _____ Inch
_____ /10ths Merc. in _____ Inch
Volume Drilled w/Rotary _____ Cu. Ft.
Rock Pressure None lbs. _____ hrs.
Oil _____ bbls., 1st 24 hrs.
WELL ACIDIZED _____

WELL FRACTURED 6/2/64 - Used: 1,050 Bbls. Water, 50,000 # Sand 20-40, 300 Gal. M. C. A.,
350 # WAC-8, 25 Gal. Aqua Frac and 40 Gal. Morflo
Gas - 30,000 Cu. Ft.
Oil - 30 Bbls.

RESULT AFTER TREATMENT _____
ROCK PRESSURE AFTER TREATMENT 450 Lbs.


Fresh Water _____ Feet _____ Salt Water _____ Feet _____

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Top Soil			0	5			
10" Casing				10			
Sand			5	80			
Red Rock			80	90			
Sand			90	120			
Red Rock			120	130			
Slate			130	180			
Sand			180	250			
Red Rock			250	275			
Slate			275	300			
Red Rock			300	325			
Slate			325	340			
Sand			340	375			
Red Rock			375	395			
Slate			395	400			
Red Rock			400	420			
Slate			420	460			
8" Casing				470			
Sand			460	500			
Slate			500	600			
Red Rock			600	640			
Slate			640	780			
Red Rock			780	800			
Slate & Shells			800	860			
Red Rock			860	890			
Slate			890	900			
Red Rock			900	915			
Slate			915	920			

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			Steel Shoe
10 3/4" OD	10.00'	10.00'	Float Collar
8 5/8" OD	470.00'	470.00'	Guide Shoe
6 3/4"			Size of 8 1/8"
4 1/2" OD	2204.00'	2204.00'	Depth set
3			2150'
2			2190'
Liners Used			Perf. top
			Perf. bottom
			Perf. top
			Perf. bottom

Surface to: _____
CASING CEMENTED 8 5/8" SIZE 470 No. Ft. 5/16/64 Date
4 1/2" 2190 5/22/64

COAL WAS ENCOUNTERED AT _____ FEET _____ INCHES
_____ FEET _____ INCHES _____ FEET _____ INCHES
_____ FEET _____ INCHES _____ FEET _____ INCHES



(over)

4708701053

Formation	Color	Hard or Soft	Top / 2	Bottom	Oil, Gas or Water	Depth Found	Remarks
Red Rock			920	930			
Slate			930	1035			
Sand			1035	1115			
Slate			1115	1195			
Sand			1195	1285			
Slate			1285	1335			
Red Rock			1335	1355			
Slate			1355	1400			
Sand			1400	1440			
Red Rock			1440	1465			
Sand			1465	1500			
Slate			1500	1580			
Sand			1580	1675			
Slate			1675	1700			
Sand			1700	1875			
Black Sand			1875	1905			
Sand			1905	1965			
Little Lime			1965	1970			
Slate			1970	1980			
Big Lime			1980	2100	Oil & Gas	2020-2035	Show
Keener			2100	2110			
Big Injun			2110	2136	Oil & Gas	2110-2122	
Slate			2136	2190	Oil & Gas	2125-2136	Show
4½" Casing				2190			
TOTAL DEPTH				2190			

Date June 12, 19 64APPROVED WOLF'S HEAD OIL REFINING COMPANY, INC.By George W. Wilsman, (Title) Agent



Select County: (087) Roane ☐ (Check All)

Enter Permit #: 30190

Get Data Reset

Select datatypes: ☐ (Check All)

☒ Location ☒ Production ☒ Plugging

☒ Owner/Completion ☒ Stratigraphy ☒ Sample

☒ Pay/Show/Water ☒ Logs ☒ Btm Hole Loc

[Table Descriptions](#)
[County Code Translations](#)
[Permit-Numbering Series](#)
[Usage Notes](#)
[Contact Information](#)
[Disclaimer](#)
[WVGES Main](#)
[Pipeline-Plus New](#)

WV Geological & Economic Survey:

Well: County = 87 Permit = 30190 [Link to all digital records for well](#)

Report Time: Thursday, April 03, 2025 1:11:25 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX_DISTRICT	QUAD_75	QUAD_15	LAT_DD	LONG_DD	UTME	UTMN
4708730190	Roane	30190	Smithfield	Spencer	Spencer	38.755106	-81.270214	476521.2	4289635.7

There is no Bottom Hole Location data for this well

Owner Information:

API	CMP_DT	SUFFIX	STATUS	SURFACE_OWNER	WELL_NUM	CO_NUM	LEASE	LEASE_NUM	MINERAL_OWN	OPERATOR_AT_COMPLETION	PROP_VD	PROP_TRGT_FM	TFM_EST_PR
4708730190	10/18/1918	Original Loc	Completed	William Kaufman		1725		5922	unknown	Hope Construction & Refining			

Completion Information:

API	CMP_DT	SPUD_DT	ELEV	DATUM	FIELD	DEEPEST_FM	DEEPEST_FMT	INITIAL_CLASS	FINAL_CLASS	TYPE	RIG	CMP_MTHD	TVD	TMD	NEW_FTG	KOD
4708730190	10/18/1918	8/30/1918	1052	Ground Level	Clvr-Rsh Rn	Undf PRICE blw INJN	Big InJn (Price&eq)	Development Well	Development Well	Oil w/ Gas Show	Cable Tool	Shot	2245			2245

Pay/Show/Water Information:

API	CMP_DT	ACTIVITY	PRODUCT	SECTION	DEPTH_TOP	FM_TOP	DEPTH_BOT	FM_BOT	G_BEf	G_AFT	O_BEf	O_AFT	WATER_QNTY
4708730190	10/18/1918	Pay	Oil	Vertical	2190	Big InJn (Price&eq)	0		0	0			
4708730190	10/18/1918	Water	Salt Water	Vertical			1845	Salt Sands (undiff)					
4708730190	10/18/1918	Show	Gas	Vertical			2200	Big InJn (Price&eq)	0	0			

There is no Production Gas data for this well

There is no Production Oil data for this well ** some operators may have reported NGL under Oil

There is no Production NGL data for this well ** some operators may have reported NGL under Oil

There is no Production Water data for this well

Stratigraphy Information:

API	SUFFIX	FM	FM_QUALITY	DEPTH_TOP	DEPTH_QUALITY	THICKNESS	THICKNESS_QUALITY	ELEV	DATUM
4708730190	Original Loc	Bufflo Ss/1st Cow Rn	Well Record	590	Reasonable	430	Reasonable	1052	Ground Level
4708730190	Original Loc	Homewd Ss/2n Cow Run	Well Record	1020	Reasonable	25	Reasonable	1052	Ground Level
4708730190	Original Loc	Salt Sands (undiff)	Well Record	1800	Reasonable	150	Reasonable	1052	Ground Level
4708730190	Original Loc	Maxton	Well Record	1990	Reasonable	30	Reasonable	1052	Ground Level
4708730190	Original Loc	Little Lime	Well Record	2031	Reasonable	20	Reasonable	1052	Ground Level
4708730190	Original Loc	Pencil Cave	Well Record	2051	Reasonable	12	Reasonable	1052	Ground Level
4708730190	Original Loc	Big Lime	Well Record	2063	Reasonable	113	Reasonable	1052	Ground Level
4708730190	Original Loc	Keener	Well Record	2176	Reasonable	14	Reasonable	1052	Ground Level
4708730190	Original Loc	Big InJn (Price&eq)	Well Record	2190	Reasonable	26	Reasonable	1052	Ground Level

Wireline (E-Log) Information:

* There is no Scanned/Raster Log data for this well

* There is no Digitized/LAS Log data for this well

* There is no Scanned or Digital Logs available for download

Plugging Information:

API	PLG_DT	DEPTH_PBT
4708730190	-/1938	0

There is no Sample data for this well



Select County: (087) Roane ☐ (Check All)

Enter Permit #: 70398

☒ Location ☒ Production ☒ Plugging
☒ Owner/Completion ☒ Stratigraphy ☒ Sample
☒ Pay/Show/Water ☒ Logs ☒ Btm Hole Loc

[Table Descriptions](#)
[County Code Translations](#)
[Permit-Numbering Series](#)
[Usage Notes](#)
[Contact Information](#)
[Disclaimer](#)
[WVGES Main](#)
["Pipeline-Plus" New](#)

WV Geological & Economic Survey:

Well: County = 087 Permit = 70398 [Link to all digital records for well](#)

Report Time: Thursday, April 03, 2025 1:27:32 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX_DISTRICT	QUAD_75	QUAD_15	LAT_DD	LONG_DD	UTME	UTMN
4708770398	Roane	70398	Smithfield	Spencer	Spencer	38.754468	-81.2706	476487.5	4289564.9

There is no Bottom Hole Location data for this well

Owner Information:

API	CMP_DT	SUFFIX	STATUS	SURFACE_OWNER	WELL_NUM	CO_NUM	LEASE	LEASE_NUM	MINERAL_OWN	OPERATOR_AT_COMPLETION	PROP_VD	PROP_TRGT
4708770398	--	--	Original Loc	Completed	Oppenheimer & Kaufman	1			OP=Camahan & Smith	Oper in Min. owner fld, no code assign (Orphan well proj)		

Completion Information:

API	CMP_DT	SPUD_DT	ELEV	DATUM	FIELD	DEEPEST_FM	DEEPEST_FTM	INITIAL_CLASS	FINAL_CLASS	TYPE	RIG	CMP_MTHD	TVD	TMD	NEW_FTG	KOD	G_BEF	G_AFT	O_BEF	O_AFT
4708770398	--	--	--	--	--	--	--	unclassified	unclassified	not available	unknown	unknown								

There is no Pay data for this well

There is no Production Gas data for this well

There is no Production Oil data for this well ** some operators may have reported NGL under Oil

There is no Production NGL data for this well ** some operators may have reported NGL under Oil

There is no Production Water data for this well

There is no Stratigraphy data for this well

Wireline (E-Log) Information:

* There is no Scanned/Raster Log data for this well

* There is no Digitized/LAS Log data for this well

* There is no Scanned or Digital Logs available for download

There is no Plugging data for this well

There is no Sample data for this well



Select County: (087) Roane ▼ Select datatypes: ☐ (Check All)

Enter Permit #: 91143

☒ Location ☒ Production ☒ Plugging

☒ Owner/Completion ☒ Stratigraphy ☒ Sample

☒ Pay/Show/Water ☒ Logs ☒ Btm Hole Loc

[Table Descriptions](#)
[County Code Translations](#)
[Permit-Numbering Series](#)
[Usage Notes](#)
[Contact Information](#)
[Disclaimer](#)
[WVGES Main](#)
["Pipeline-Plus" New](#)

WV Geological & Economic Survey:

Well: County = 087 Permit = 91143 [Link to all digital records for well](#)

Report Time: Thursday, April 03, 2025 3:26:25 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX_DISTRICT	QUAD_75	QUAD_15	LAT_DD	LON_DD	UTME	UTMN
4708791143	Roane	91143	Smithfield	Spencer	Spencer	38.754322	-81.272455	476326.3	4289549.2

There is no Bottom Hole Location data for this well

There is no Owner/Completion data for this well

There is no Owner/Completion data for this well

There is no Pay data for this well

There is no Production Gas data for this well

There is no Production Oil data for this well ** some operators may have reported NGL under Oil

There is no Production NGL data for this well ** some operators may have reported NGL under Oil

There is no Production Water data for this well

There is no Stratigraphy data for this well

Wireline (E-Log) Information:

* There is no Scanned/Raster Log data for this well

* There is no Digitized/LAS Log data for this well

* There is no Scanned or Digital Logs available for download

There is no Plugging data for this well

There is no Sample data for this well



Select County: (087) Roane

Select datatypes: ☐ (Check All)

Enter Permit #: 91144



Location



Production



Plugging



Owner/Completion



Stratigraphy



Sample



Pay/Show/Water



Logs



Btm Hole Loc

Get Data

Reset

[Data Selection](#)
[County Code Translations](#)
[Permit-Numbering Series](#)
[Usage Notes](#)
[Contact Information](#)
[Disclaimer](#)
[WVGES Main](#)
["Pipeline-Plus" New](#)

WV Geological & Economic Survey:

Well: County = 87 Permit = 91144 [Link to all digital records for well](#)

Report Time: Thursday, April 03, 2025 3:26:52 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX_DISTRICT	QUAD_75	QUAD_15	LAT_DD	LON_DD	UTME	UTMN
4708791144	Roane	91144	Smithfield	Spencer	Spencer	38.755193	-81.271342	476423.3	4289645.6

There is no Bottom Hole Location data for this well

There is no Owner/Completion data for this well

There is no Owner/Completion data for this well

There is no Pay data for this well

There is no Production Gas data for this well

There is no Production Oil data for this well ** some operators may have reported NGL under Oil

There is no Production NGL data for this well ** some operators may have reported NGL under Oil

There is no Production Water data for this well

There is no Stratigraphy data for this well

Wireline (E-Log) Information:

* There is no Scanned/Raster Log data for this well

* There is no Digitized/LAS Log data for this well

* There is no Scanned or Digital Logs available for download

There is no Plugging data for this well

There is no Sample data for this well



Select County: (087) Roane ▼ Select datatypes: ☐ (Check All)

Enter Permit #: 91145

☒ Location ☒ Production ☒ Plugging

☒ Owner/Completion ☒ Stratigraphy ☒ Sample

☒ Pay/Show/Water ☒ Logs ☒ Btm Hole Loc

[Table Descriptions](#)
[County Code Translations](#)
[Permit-Numbering Series](#)
[Usage Notes](#)
[Contact Information](#)
[Disclaimer](#)
[WVGES Main](#)
["Pipeline-Plus" New](#)

WV Geological & Economic Survey:

Well: County = 87 Permit = 91145 [Link to all digital records for well](#)

Report Time: Thursday, April 03, 2025 3:27:07 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX_DISTRICT	QUAD_75	QUAD_15	LAT_DD	LON_DD	UTME	UTMN
4708791145	Roane	91145	Smithfield	Spencer	Spencer	38.756209	-81.27023	476520.2	4289758

There is no Bottom Hole Location data for this well

There is no Owner/Completion data for this well

There is no Owner/Completion data for this well

There is no Pay data for this well

There is no Production Gas data for this well

There is no Production Oil data for this well ** some operators may have reported NGL under Oil

There is no Production NGL data for this well ** some operators may have reported NGL under Oil

There is no Production Water data for this well

There is no Stratigraphy data for this well

Wireline (E-Log) Information:

* There is no Scanned/Raster Log data for this well

* There is no Digitized/LAS Log data for this well

* There is no Scanned or Digital Logs available for download

There is no Plugging data for this well

There is no Sample data for this well

Well Records for:

4708730190

4708779114

4708791143

4708791144

4708791145

NOT AVAILABLE